



Mundijong-Whitby Urban Traditional Infrastructure Development Contribution Plan Report

Report No. 1

Bookmarked links to each section are enabled in this document within the Table of Contents and in the left-hand navigation pane

Please consider the environment before printing



Shire of
Serpentine
Jarrahdale

sjshire.wa.gov.au

connect
with us





Table of Contents

| | | |
|------|--|----|
| 1 | Revision Schedule..... | 1 |
| 2 | Purpose | 2 |
| 3 | Development Contribution Area | 2 |
| 4 | Period of the plan | 2 |
| 5 | Operation of the DCP | 2 |
| 6 | Application requirements | 3 |
| 7 | Items included in the plan..... | 3 |
| 8 | Estimated Costs | 3 |
| 9 | Land | 4 |
| 9.1 | Land Valuation | 4 |
| 9.2 | Land for Infrastructure (Roads and District Open Space) | 5 |
| 9.3 | Land for Public Open Space and/or Drainage | 5 |
| 10 | Roads to be constructed or upgraded | 7 |
| 10.1 | Bishop Road (East) (Integrator B) upgrade between Tonkin Highway reserve and Bett Road: 7 | |
| 10.2 | Taylor Road (Integrator B) upgrade between Bishop Road and Keirnan Street: | 8 |
| 10.3 | Town Centre Distributor Road (Whitby New Road) (Integrator B) construction between Taylor Road and South Western Highway:..... | 9 |
| 10.4 | North-South Road (Integrator B) construction between Watkins Road and Galvin Road: 10 | |
| 10.5 | Skyline Boulevard (Neighbourhood Connector A) construction between Town Centre Distributor Road (Whitby New Road) and Tinspar Avenue:..... | 11 |
| 10.6 | Tinspar Avenue (Neighbourhood Connector A) construction between Skyline Boulevard and South Western Highway: | 11 |
| 11 | District Open Space to be constructed or upgraded..... | 12 |
| 11.1 | Whitby High School District Sporting Space (Shared project with the CIDCP) | 12 |
| 11.2 | Keirnan Park Stage 3 District Sporting Space (Shared project with the CIDCP) | 13 |
| 11.3 | Taylor Road / Scott Road Primary School Neighbourhood Open Space | 13 |
| 12 | Water Monitoring | 14 |
| 13 | Administration costs | 15 |
| 14 | Method of calculating contributions | 16 |
| 14.1 | Cost Share Apportionment - Land | 16 |



Continued

Mundijong-Whitby Urban Traditional Infrastructure Development Contribution Plan Report

| | | |
|---|---|----|
| 14.2 | Cost Share Apportionment – Roads to be constructed or upgraded | 16 |
| 14.3 | Cost Share Apportionment – District Open Space to be constructed or upgraded | 16 |
| 14.4 | Cost Share Apportionment – Water Monitoring | 16 |
| 14.5 | Cost Share Apportionment – Administration | 17 |
| 14.6 | Calculating the Lot/Dwelling Potential..... | 17 |
| 14.7 | Calculating the Contribution Rate between Cost Reviews..... | 18 |
| 14.8 | Calculating the Contribution liability for Landowners/Developers | 19 |
| 15 | Priority and timing of infrastructure delivery..... | 21 |
| 16 | Payment of contributions | 21 |
| 16.1 | Form of Contributions | 22 |
| 16.2 | Exemptions..... | 22 |
| 17 | DCP Credits | 22 |
| 17.1 | DCP Credits to offset Contributions..... | 22 |
| 17.2 | Credits for DCP Land Ceded | 22 |
| 17.3 | Credits for Pre-Funding of DCP Infrastructure | 23 |
| 17.3.1 | Pre-Funding Agreement..... | 23 |
| 17.3.2 | Acceptance of Works | 23 |
| 17.3.3 | Principles for Cost Recoupment | 23 |
| 17.4 | Repayment of DCP Credit Balance | 24 |
| 18 | Review..... | 24 |
| 18.1 | Major Review (5 Yearly) | 24 |
| 18.2 | Annual (Minor) Review | 24 |
| 18.2.1 | Updates to Infrastructure Cost Estimates | 25 |
| 18.2.2 | Cost Review Reconciliation | 25 |
| 19 | Figures | 27 |
| | Figure 1 – Development Contribution Area 3 (DCA3) Boundary | 27 |
| | Figure 2 – Mundijong District Structure Plan 2020 | 28 |
| | Figure 3 – Roads to be constructed/upgraded | 29 |
| | Figure 4 – District Open Space to be constructed/upgraded | 30 |
| Appendices | | |
| Appendix A: Cost Apportionment Schedule | | |
| Appendix B: Example Calculations | | |
| Appendix C: Capital Expenditure Plan | | |



Continued

Mundijong-Whitby Urban Traditional Infrastructure Development Contribution Plan Report

Appendix D: Infrastructure Designs

Appendix E: Schedule of Costs - Land for Infrastructure (Roads & District Open Space)

Appendix F: Schedule of Costs - Land for Public Open Space & Drainage

Appendix G: Schedule of Costs – Infrastructure to be constructed/upgraded

Appendix H: Schedule of Costs – Administration

Appendix I: Schedule of Costs – Water Monitoring

Appendix J: Cost Review Reconciliation Adjustment

Appendix K: Lots Completed and Remaining

Appendix L: Land Valuation

Appendix M: Infrastructure Delivery Status Report

Appendix N: DCP Dashboard Summary

Appendix O: Infrastructure Costings – full breakdown



2 Purpose

The purpose of this development contribution plan (DCP) report is to:

- enable the application of infrastructure contributions for the development of new, and the upgrade of existing infrastructure which is required as a result of increased demand generated in the Development Contribution Area (DCA)
- provide for the equitable sharing of the costs of infrastructure and administrative items between owners
- ensure that cost contributions are reasonably required as a result of the subdivision and development of land in the DCA
- coordinate the timely provision of infrastructure.

The following documents are relevant documents which coordinate the timely provision of the community infrastructure items:

- The Shire of Serpentine Jarrahdale Community Infrastructure Public Open Space Strategy adopted December 2016
- The Shire of Serpentine Jarrahdale Community Infrastructure Public Open Space Strategy 2020 (Draft)
- The Mundijong District Structure Plan 2020
- The Shire of Serpentine Jarrahdale Local Planning Strategy Number 3 (LPS 3) (Draft)
- The Shire of Serpentine Jarrahdale Strategic Community Plan 2017 - 2027
- The Shire of Serpentine Jarrahdale Corporate Business Plan 2020 - 24, and
- The Shire of Serpentine Jarrahdale Long Term Financial Plan 2020 - 2030.

3 Development Contribution Area

The DCA for this DCP is shown on the scheme map as DCA 3. A map is included in [Figure 1](#).

4 Period of the plan

15 years, from 23 May 2023 to 23 May 2038.

5 Operation of the DCP

The Development Contribution plan and associated report have been prepared in accordance with State Planning Policy 3.6 - Infrastructure Contributions (SPP 3.6).

This DCP came into effect on the date of gazettal of Amendment 209 to Town Planning Scheme No. 2 (TPS2) to incorporate the plan.



The plan will operate in accordance with the provisions of Amendment 209, and Section 9 and Appendix 10 of TPS2.

6 Application requirements

Where an application for subdivision, strata subdivision, development or an extension of land use is lodged which relates to land to which this plan applies, the local government shall take the provisions of the plan into account in making a recommendation on, or determining, that application.

7 Items included in the plan

This section of the DCP Report identifies the infrastructure, land and other items for which development contributions will be collected in the DCA. These items include:

- District distributor roads and local roads playing a district function
- District Open Space facilities
- Land for public and district open space, and drainage
- Water monitoring costs, and
- Administration costs.

Infrastructure items included in the DCP reflect the provisions of the latest Mundijong District Structure Plan (see [Figure 2](#)) and are incorporated into this DCP through Amendment 209 to the Town Planning Scheme No. 2.

8 Estimated Costs

The costs allocated to this DCP have been derived based on the capital investment required for facilities generated by additional development in the DCA.

Initial cost estimates are undertaken by a suitably qualified professional and will be reviewed by a suitably qualified professional at each [Major Review](#) (as a minimum).

At each [Minor Review](#) the costs may be indexed using the previous year's annual escalation rate for "Road and Bridge Construction" in latest WALGA Quarterly Economic Briefing available at the time the DCP Report is adopted. Where deemed pertinent, some items may be reviewed by a suitably qualified professional.

The methodology applied for each item is detailed within [Appendix O](#).

The associated costs for each DCP item *exclude*:

- Ongoing maintenance costs
- Demand for infrastructure that is generated by the current population



- Demand created by external usage (the proportion of the use drawn from outside the DCA)
- Future usage (the proportion of usage that will be generated by future development outside the development contribution plan timeframe).

Due to the fragmented nature of the Mundijong-Whitby Urban area, and the uncertainty around where development will occur first, a consistent “per lot” rate is applied across the DCA.

This means that all new lots and qualifying new development within DCA3 will be required to contribute equally towards the identified DCP items.

Details of the cost apportionment can be seen in the Cost Apportionment Schedule in [Appendix A](#).

Designs associated with the Infrastructure Items to be Constructed or Upgraded (where available) are included in [Appendix D](#).

The cost breakdown (Schedule of Costs) are included in the appendices as follows:

- [Appendix E](#): Land for Infrastructure (Roads and District Open Space)
- [Appendix F](#): Land for Public Open Space and Drainage
- [Appendix G](#): Infrastructure (summary)
- [Appendix H](#): Administration Costs
- [Appendix I](#): Water Monitoring
- [Appendix O](#): Infrastructure Costing – full break down

The Cost Review Reconciliation, which adjusts future costs based on historic development, is included in [Appendix J](#).

An extract from the current Land Valuation which informs the land costs above, is available in [Appendix L](#).

Note: Grants or other external Funding shall be shown as a deduction against the applicable item in the Cost Apportionment Schedule ([Appendix A](#)).

9 Land

9.1 Land Valuation

Many traditional infrastructure items include a land component. To determine the total cost of the items, an estimate of land value therefore needs to be identified.

Land to be acquired may be required for areas which can be categorised (through the land use zoning) as residential or non-residential. There is therefore a requirement for two separate rates; one for ‘Residential’ and one for ‘Mixed Use/Non-Residential’.

Standard Residential/Non-Standard Residential

This rate is based on current valuation advice for an indicative R25 zoned 5 hectares with no servicing constraints within the Development Contribution Area.



Non-Residential/Mixed Use

This rate is based on a Mixed Use R60 zoned area within the planned commercial/town centre precinct. It has been assumed the typical land parcel is a regular shaped 5-hectare area with no major servicing constraints and no major geotechnical/environmental issues.

Pursuant to Clause 9.3.11 of TPS 2, the estimated land value will be reviewed at least annually.

The net land value is to be determined in accordance with the definition of "value" in TPS 2 s.9.3.12 and having general regard to the International Valuation Standards Committee's definition of market value as adopted by the Australian Property Institute. To account for the direct transfer of land, the fair market value should be discounted by standard marketing costs including fees, commissions and advertising cost.

The rate for residential and non-residential land is included in [Appendix L](#).

9.2 Land for Infrastructure (Roads and District Open Space)

The DCP takes responsibility for acquiring land for District Open Space and Road Reserves (such as road widening or for new roads) associated with DCP infrastructure items.

The associated value of this land is credited to the DCP account of the landowner at the time of ceding. In respect of land for road reserves, DCP Credits only apply to the area in excess of the standard 20m. For example, if the road is 30m wide, only 10m width will be compensated for through this Development Contribution Plan.

This approach ensures transparency, equity (particularly in instances of fragmented ownership) and simplicity of calculation.

All land included within the DCP for Infrastructure Items (Roads and District Open Space), is detailed in [Appendix E](#).

9.3 Land for Public Open Space and/or Drainage

A significant amount of land will be provided within the DCA for:

- A mix of multiple-use corridors with a dual drainage and recreation function, as well as land required for drainage only;
- Local and neighbourhood parks;
- Larger district-level playing fields including where provided to complement school playing fields.
- All land required for Public Open Space and Drainage (as prescribed within Liveable Neighbourhoods) is included within the Development Contribution Plan.

The associated value of this land is credited to the DCP account of the landowner at the time of ceding.

This approach ensures transparency, equity (particularly in instances of fragmented ownership) and simplicity of calculation.



How the amount of land for Public Open Space and Drainage is determined

Some detailed planning is in progress in the form of approved and draft LSPs. This level of planning allows for the specific identification of land areas required for drainage and/or Public Open Space. In such cases, data from the draft/adopted LSPs has been used to inform the calculations for land requirements.

There are however several areas within the DCA which have not yet been subject to the preparation of LSPs. To ensure that appropriate funds are collected to allow for the future purchase of land required for POS and drainage within these areas, it has been necessary to determine an estimated amount for some LSPs.

The following methodology has been applied:

1. A review of LSPs and spatial data has been undertaken to identify the total amount of land covered by each LSP and the total amount of land required for Public Open Space and drainage.
2. From these totals, the percentage of land required for Public Open Space and drainage has been calculated.
3. Spatial data has been used to identify the total land area of areas in the DCA for which LSPs have yet to be prepared.
4. The percentage identified in step 2 has then been applied to the total identified in step 3 to generate an estimated amount of land required for Public Open Space and drainage in these areas.
5. The Public Open Space and drainage land areas identified in steps 1 and 4 are then added to identify a total estimate of land required for POS and drainage within the DCA.

[Appendix F](#) details the calculations for Public Open Space and Drainage land.

POS Items not included

State Policy provides a clear indication that the development of POS to a minimum standard, and maintenance for a minimum period, is at the developer's expense. As such, the development and initial maintenance of Public Open Space is not included within the Development Contribution Plan and will be the responsibility of the subdivider.

In addition, land identified as having conservation value, for example Bush forever sites or protected Wetlands, is excluded from the Development Contribution Plan.

While the Development Contribution Plan includes land for drainage purposes, it does not include drainage works themselves (i.e. earthworks, drainage infrastructure such as piping, pits, mechanical treatments, water sensitive urban design treatments or similar). These are considered subdivisional works, generally required by local water management strategies and urban water management plans.

Such drainage works are very difficult to calculate given the varying nature of drainage infrastructure and developers may treat drainage works in various ways to benefit their development. The requirement to provide optimal certainty in costing Development Contribution Plan items to achieve equity between developers, reinforces the need to exclude drainage works.



The drainage works contained within the proposed road infrastructure costings are permitted to be included, in accordance with SPP3.6.

10 Roads to be constructed or upgraded

Figure 3 shows the locations and extent of the Road Upgrades included in the DCP.

It is noted that costs associated with land to be acquired for infrastructure items within this DCP are costed separately to the construction costs, due to different indexation rates applied to the Construction component and the Land Value component.

Road Reserve Improvements Not Included

The amenity of urban areas can be substantially enhanced through public realm improvement works such as vegetation, hard landscaping, public art and higher design standards of infrastructure. Road reserves provide significant opportunities for amenity enhancement, especially in the case of wider reserves such as distributor roads and in the instance of split-carriageways. There is, however, not a clear nexus between development in a new urban area and its associated increase in traffic, and the need for general road reserve improvements.

Nonetheless, it should be noted that most developers undertake works to provide attractive streetscapes as a marketing feature, especially in the context of distributor and connector roads leading into new estates. As such, road reserve improvements, such as hard and soft landscaping and higher design standards of infrastructure, are not included in the DCP.

10.1 Bishop Road (East) (Integrator B) upgrade between Tonkin Highway reserve and Bett Road:

The road currently exists, but will require changes in width, alignment and configuration to support development envisaged under the Mundijong District Structure Plan. The road is also proposed to provide a direct connection to the future extension of Tonkin Highway. The width of Bishop Road will be 30 metres.

The following items are included in the Development Contribution Plan for Bishop Road (East):

- Land required in excess of a standard 20m reserve, to achieve a 30m wide road reserve, plus additional land where necessary to accommodate channelization and/or roundabout construction at the following intersections;
 - Taylor Road (Roundabout)
 - Hopkinson Road (Roundabout)
 - Soldiers Road (Roundabout)
 - Bett Road (Roundabout)
- Earthworks for the whole road reserve;
- Complete road construction based on the Liveable Neighbourhoods Integrator B



standard;

- Associated drainage works including water sensitive urban design measures;
- Traffic control devices including intersection treatments and associated works;
- Shared paths;
- Utility removal, relocation and insertion; and
- Associated costs including design, administration and management.

The following items are not included in the Development Contribution Plan for Bishop Road (East):

- Minor intersections treatments into the adjoining subdivisional road network. These will be subject to a standard truncation requirement;
- Any works carried out between Kargotich Road and the Tonkin Highway. This section of the road upgrade will be borne by the West Mundijong Industrial Development Contribution Plan; and
- Any intersection treatment with Tonkin Highway.

A detailed breakdown of the costing for this project is provided in [Appendix G](#). The value of land associated with each project is included separately in [Appendix E](#).

10.2 Taylor Road (Integrator B) upgrade between Bishop Road and Keirnan Street:

The road currently exists, but will require changes in width, alignment and configuration to support development envisaged under the Mundijong District Structure Plan. The width of Taylor Road will be 30m.

The following items are included in the Development Contribution Plan for Taylor Road:

- Land required in excess of a standard 20m reserve, to achieve a 30m wide road reserve, plus additional land where necessary to accommodate channelization and/or roundabout construction at the following intersections;
 - Keirnan Street (Roundabout)
- Earthworks for the whole road reserve;
- Complete road construction based on the Liveable Neighbourhoods Integrator B standard;
- Associated drainage works including water sensitive urban design measures;
- Traffic control devices including intersection treatments and associated works;
- Shared paths;
- Utility removal, relocation and insertion; and
- Associated costs including design, administration and management.



The following items are not included in the Development Contribution Plan for Taylor Road:

- Minor intersections treatments into the adjoining subdivisional road network. These will be subject to a standard truncation requirement.

A detailed breakdown of the costing for this project is provided in [Appendix G](#). The value of land associated with each project is included separately in [Appendix E](#).

10.3 Town Centre Distributor Road (Whitby New Road) (Integrator B) construction between Taylor Road and South Western Highway:

The road does not currently exist and will be required to support the development envisaged under the Mundijong District Structure Plan. The width of New Whitby Road will be 30 metres.

The following items are included in the Development Contribution Plan for New Whitby Road:

- Land required in excess of a standard 20m reserve, to achieve a 30m wide road reserve, plus additional land where necessary to accommodate channelization and/or roundabout construction at the following intersections;
 - Taylor Road (Roundabout)
 - Soldiers Road (Roundabout)
 - South Western Highway (Channelised Intersection)
- Earthworks for the whole road reserve;
- Complete road construction based on the Liveable Neighbourhoods Integrator B standard;
- Associated drainage works including water sensitive urban design measures;
- Traffic control devices including intersection treatments and associated works;
- Construction of one at-grade rail crossing;
- Costs associated with one rail crossing closure (Keirnan Street);
- Shared paths;
- Utility removal, relocation and insertion; and
- Associated costs including design, administration and management.

The following items are not included in the Development Contribution Plan for New Whitby Road:

- Minor intersections treatments into the adjoining subdivisional road network. These will be subject to a standard truncation requirement.

A detailed breakdown of the costing for this project is provided in [Appendix G](#). The value of land associated with each project is included separately in [Appendix E](#).



Note: The construction of the at-grade crossing is subject to agreement between the Road Manager and Rail Infrastructure Manager. The Local Government is responsible to manage communications between all stakeholders, obtain the required approvals and arrange for an Australian Level Crossing Assessment Model (ALCAM) Report and a Rail Safety Report to be undertaken.

Construction of the at-grade crossing should not be considered prior to the freight rail being realigned away from the Mundijong Urban area.

In the event that an at-grade rail crossing is not approved, the local government is to apply any funds already collected to an approved alternate crossing or if no crossing is approved any collected funds shall be applied to the Town Centre Distributor Road item generally or other items in the DCP.

10.4 North-South Road (Integrator B) construction between Watkins Road and Galvin Road:

The road does not currently exist and will be created through subdivision to support the development envisaged under the Mundijong District Structure Plan. The width of the North-South Road will be 30 metres.

The following items are included in the Development Contribution Plan for North-South Road:

- Land required in excess of a standard 20m reserve, to achieve a 30m wide road reserve plus additional land where necessary to accommodate channelization and/or roundabout construction at the following intersections;
 - Watkins Road (Roundabout)
 - Galvin Road (Roundabout)
- Earthworks for the whole road reserve;
- Complete road construction based on the Liveable Neighbourhoods Integrator B standard;
- Associated drainage works including water sensitive urban design measures;
- Traffic control devices including intersection treatments and associated works;
- Shared paths;
- Utility removal, relocation and insertion; and
- Associated costs including design, administration and management.

The following items are not included in the Development Contribution Plan for North-South Road:

- Minor intersections treatments into the adjoining subdivisional road network. These will be subject to a standard truncation requirement.

A detailed breakdown of the costing for this project is provided in [Appendix G](#). The value of land associated with each project is included separately in [Appendix E](#).



10.5 Skyline Boulevard (Neighbourhood Connector A) construction between Town Centre Distributor Road (Whitby New Road) and Tinspar Avenue:

This is a new road that will be required to support the development envisaged under the Mundijong District Structure Plan. The width of Skyline Boulevard will be 25 metres.

The following items are included in the Development Contribution Plan for Skyline Boulevard:

- Land required in excess of a standard 20m reserve, to achieve a 25m wide road reserve, plus additional land where necessary to accommodate channelization and/or roundabout construction at the following intersections:
 - New Whitby Road (Roundabout)
 - Tinspar Avenue (Roundabout)
- Earthworks for the whole road reserve;
- Complete road construction based on the Liveable Neighbourhoods Connector A standard;
- Associated drainage works including water sensitive urban design measures;
- Traffic control devices including intersection treatments and associated works;
- Shared paths;
- Utility removal, relocation and insertion; and
- Associated costs including design, administration and management.

The following items are not included in the Development Contribution Plan for Skyline Boulevard:

- Minor intersections treatments into the adjoining subdivisional road network. These will be subject to a standard truncation requirement.

A detailed breakdown of the costing for this project is provided in [Appendix G](#). The value of land associated with each project is included separately in [Appendix E](#).

10.6 Tinspar Avenue (Neighbourhood Connector A) construction between Skyline Boulevard and South Western Highway:

This is a new road which will be required to support the development envisaged under the Mundijong District Structure Plan. The width of Tinspar Avenue will be 25 metres.

The following items are included in the Development Contribution Plan for Tinspar Avenue:

- Land required in excess of a standard 20m reserve, to achieve a 25m wide road reserve, plus additional land where necessary to accommodate channelization and/or roundabout construction at the following intersections:
 - Keirnan Street (Seagull Intersection)
 - South Western Highway (Channelised Intersection)



- Earthworks for the whole road reserve
- Complete road construction based on the Liveable Neighbourhoods Connector A standard;
- Associated drainage works including water sensitive urban design measures;
- Traffic control devices including intersection treatments and associated works;
- Shared paths;
- Utility removal, relocation and insertion; and
- Associated costs including design, administration and management.

The following items are not included in the Development Contribution Plan for Tinspar Avenue:

- Minor intersections treatments into the adjoining subdivisional road network. These will be subject to a standard truncation requirement.

A detailed breakdown of the costing for this project is provided in [Appendix G](#). The value of land associated with each project is included separately in [Appendix E](#).

11 District Open Space to be constructed or upgraded

The Shire's Community Infrastructure and Public Open Space Strategy (CIPOS) outlines the general approach and philosophy in planning for community infrastructure and public open space in the Shire of Serpentine Jarrahdale. It provides a guiding document for current and future development relevant to this purpose.

The types of community infrastructure include sport, recreation, community, emergency, tourism and Shire administration requirements. These facilities are to cater for the growing pressures on local clubs, community groups and service providers, where the increasing population increases service delivery requirements. As part of the investigations of CIPOS, it has been identified that the Mundijong Urban area will require increased provision of District Open Space to support population growth.

The scope of construction of District Open Space included in this Development Contribution Plan is confined to land and below surface works including drainage, irrigation and grassing. Further above ground works are included within the Shire's Community Infrastructure Development Contribution Plan (CIDCP).

[Figure 4](#) provides a graphical representation of District Open Space projects included in this DCP.

It is noted that costs associated with land to be acquired for infrastructure items within this DCP are costed separately, due to different indexation rates applied to the Construction component and the Land Value component.

11.1 Whitby High School District Sporting Space (Shared project with the CIDCP)

The Community Infrastructure and Open Space Strategy identifies a district sports oval to be co-located with the planned high school site in Precinct A of the Mundijong District Structure Plan. A



shared-use agreement is anticipated between the Department of Education and the Shire for the use of the oval established on the High School site, to facilitate the District function.

All community buildings and clubroom facilities are funded separately through the CIDCP.

The single playing field is to be designed to a minimum dimension of 205m x 175m (3.6 hectares).

- Earthworks;
- Grassing;
- Irrigation; and
- Associated costs relating to construction including design and management.

A detailed breakdown of the costing for this project is provided in [Appendix G](#). The value of land associated with each project is included separately in [Appendix E](#).

11.2 Keirnan Park Stage 3 District Sporting Space (Shared project with the CIDCP)

At this DCP revision, it is anticipated that enough grant funds will be available for the construction of the first oval. This has been reflected within the costs.

The Community Infrastructure and Open Space Strategy identifies Reserve 4395 along Keirnan Street, Mundijong, as being suitable to be developed as a Sporting Complex.

The Mundijong-Whitby Urban Traditional Infrastructure Development Contribution Plan includes for two senior-sized playing fields on site, as this will support a District function. The playing fields are to have a minimum dimension of 205m x 175m each (7.2 hectares).

The following items were included in the Development Contribution Plan:

- Earthworks;
- Grassing;
- Irrigation; and
- Associated costs relating to construction including design and management.

A detailed breakdown of the costing for this project is provided in [Appendix G](#). The value of land associated with each project is included separately in [Appendix E](#).

11.3 Taylor Road / Scott Road Primary School Neighbourhood Open Space

The Community Infrastructure Open Space Strategy identifies that this sporting space will be a senior sized AFL field. A shared use agreement is anticipated with the Department of Education.

The playing field will be accommodated wholly within a future Shire reserve, funded by the Mundijong-Whitby Urban Traditional Infrastructure Development Contribution Plan.

The single playing field is to be designed to a minimum dimension of 205m x 175m (3.6 hectares).



The following items are included in the Development Contribution Plan

- Earthworks;
- Grassing;
- Irrigation; and
- Associated costs relating to construction including design and management.

A detailed breakdown of the costing for this project is provided in [Appendix G](#). The value of land associated with each project is included separately in [Appendix E](#).

12 Water Monitoring

The Mundijong Whitby District Water Management Strategy (DWMS) establishes a framework for water management in new urban development. This ensures that water quantity and quality design objectives can be achieved, and the concerns and risks identified by the Department of Water and Environmental Regulation (DWER) and the Water Corporation can be addressed. The DWMS reinforces the Shire's commitment to ensuring that water sensitive urban design principles are incorporated into new urban development.

The Shire will implement water quality and quantity monitoring within developments and wetlands guided by a Sampling and Analysis Plan that will be prepared on commencement of the program to confirm sampling and analysis arrangements.

It is proposed that monitoring will be carried out over 10 years with reports prepared annually and provided to stakeholders for review.

This approach will allow longer-term trends in water quality and quantity to be identified and monitored as the DCA3 is fully developed. Suitable remediation works or structural controls may be implemented to rectify any identified problems.

The monitoring program will include:

- 20 groundwater monitoring wells
- 10 surface water quality sampling sites
- 7 surface water level/flow monitoring sites
- 10 sediment sampling sites

Monitoring will be carried out at the following frequencies:

| Year | Groundwater levels | Groundwater quality | Surface water flows /levels | Surface water quality | Sediment |
|------|--------------------|---------------------|--|-----------------------|--------------|
| 1 | Monthly | 4 x per year: | 4 x per year: | | 1 x per year |
| 2-10 | Quarterly | Mar, Jun, Sep & Dec | Mar (baseline), May (1 st flush), Sep & Oct (winter). | | |



Mundijong-Whitby Urban Traditional Infrastructure Development Contribution Plan Report

Water quality and sediment sampling will include the following parameters:

| Group | Frequency | Groundwater | Surface water | Sediment |
|----------------------|------------------|--|------------------------------|----------|
| In-situ | All events | DO, Redox potential (Eh), EC, Temperature, pH | | n/a |
| Physio-chemical | All events | n/a | Total Dissolved Solids (TDS) | n/a |
| Anions and nutrients | All events | TKN, NH ₄ , NO ₃ , DON, TN, TP and PO ₄ (FRP) | | n/a |
| Metals | One annual event | Al, As, Cd, Cr, Cu, Fe, Pb, Ni, Zn and Hg | | |
| Hydrocarbons | One annual event | TRH, BTEX and PAH | | |

It is likely that subdivision and development would not be approved within the Mundijong Whitby area without the approval and ongoing implementation of the Mundijong Whitby DWMS. As such, it is considered reasonable that the costs of, and associated with, the required water monitoring be funded by developers within DCA3.

The DCP will assume funding responsibility for the post development water-monitoring program required by the Mundijong Whitby DWMS.

District level sampling is anticipated to commence in 2028.

[Appendix I](#) gives a detailed breakdown of the costs associated with Water Monitoring.

13 Administration costs

All expended and estimated future costs associated with administration, planning, review and development of the District Structure Plan, District Water Management Plan/s, preparation and implementation of the Mundijong Urban Development Contribution Plan and any technical documents necessary for the implementation of the above, including:

- Planning studies;
- Traffic studies;
- Drainage studies;
- Road design costs where not allocated to specific road items under the DCP;



- Other related technical and professional studies;
- Legal costs;
- Valuations;
- Borrowing costs (including loan repayments); and
- Scheme management costs (including administration and management of the DCP).

In general, Administration costs of the DCP are broken down into Legal Expenses, expenses associated with advertising & consultancy, and proportional salary allocations for overhead personnel whose are involved in the general operation of the DCP(s). This allocation is reflective of the percentage of time the employee is expected to spend on work associated with the general running of the DCP. This does not include time spent on specific DCP funded infrastructure projects, which is captured within the individual project costings).

The Technical Specialist Infrastructure Contributions (previously titled “DCP Coordinator”) is the only employee whose cost is 100% allocated across the DCPs.

It is noted that staff may also be required to spend time on specific DCP funded projects as part of the design and/or project delivery phase. Any such time/cost allocation is recorded separately and where allowable under the scope/costing for the project, will be recovered under those project costings.

A detailed breakdown of the administrative costs is provided in [Appendix H](#).

14 Method of calculating contributions

14.1 Cost Share Apportionment - Land

The cost of land associated with road widening, public open space and district open space is shared equally across the DCA.

14.2 Cost Share Apportionment – Roads to be constructed or upgraded

The costs associated with construction and/or upgrade of roads are shared equally across the DCA.

14.3 Cost Share Apportionment – District Open Space to be constructed or upgraded

The costs associated with construction and/or upgrade of District Open Space are shared equally across the DCA.

14.4 Cost Share Apportionment – Water Monitoring

The costs associated with Water Monitoring within the DCA are shared equally across the DCA. Water Monitoring is a necessary enabler to subdivision and development.



14.5 Cost Share Apportionment – Administration

The costs associated with Administration Costs for this DCP are shared equally across the DCA, as the staff time and related activities which make up these costs are necessary for the preparation and ongoing management of the DCP.

14.6 Calculating the Lot/Dwelling Potential

The development contribution methodology is based on a per lot/dwelling basis (whichever is greater). Therefore, it is necessary to estimate the potential number of additional lots/dwellings to be created in the DCA. This estimate will be used to determine the development contribution rates per lot/dwelling for standard/non-standard residential, non-residential and mixed-use development.

The following methodology has been applied:

- A review of LSPs and spatial data has been undertaken to identify the estimated total lot/dwelling yield for each area covered by an approved or draft LSP, or approved subdivision/development application.
- The estimates for greenfield areas not yet subject to LSPs have been determined through identifying the total land area, deducting 40 percent (accounting for land required for public purposes such as roads, POS and drainage), and then determining the subdivision/development potential of the remaining land area based on its residential density coding.
- The lot/dwelling estimates for infill sites (i.e. existing urban) not yet subject to LSPs were determined through manual calculations of the development potential of each landholding based on the relevant residential density.
- By adding the lot/dwelling yields calculated in steps 1-3, the total estimated lot/dwelling yield for the Development Contribution Plan area has been identified.
- A 'Parent lot' deduction has been included within the total lot count. Parent lots do not generate a contribution requirement in the Development Contribution Plan.

As lots extinguish their liability to pay contributions, and/or an LSP is revised, the future lot count is updated accordingly at the next DCP Report Review.

The yield estimate calculated for mixed development is based on 15 lots per gross hectare to provide for infrastructure of subdivision works such as roads and drainage facilities to be transferred to the state / local government. Where individual lots do not require land to be transferred to the state / local government, 20 lots per gross hectare has been applied.

There are some instances where an LSP is not prepared for an area within the DCA. In those areas, the following approach has been taken to assess the lot yield and public open space considerations:

- Land for public purposes (i.e. Roads, Public Open Space, drainage and similar) is expected to be provided within non-structure planned areas. As such, a 40 percent deduction has been applied to the total site area of each precinct.



- In the absence of finalised (or draft) LSPs depicting residential densities, an R25 code has been utilised to determine the lot/dwelling estimates for the non-structure planned areas.

See [Appendix K](#) for details on lots completed and remaining at this DCP Report revision.

The Total Cost allocated to the DCA and dividing this figure by the estimated number of future lots, gives the Contribution Per Lot Value for the DCA.

$$\begin{aligned} & \text{Allocated Cost} / \text{number of anticipated additional lots/dwellings} \\ & = \text{Contribution per Lot Value} \end{aligned}$$

The “Cost Apportionment Schedule” shows the split of costs by item and shows the total Contribution Per Lot value – See [Appendix A](#).

14.7 Calculating the Contribution Rate between Cost Reviews

To ensure costs are current during the time between cost reviews, all costs will be escalated daily, calculated from the number of days since the last cost review (being the latest adopted DCP revision), using an annual escalation rate.

The annual escalation rates for Administration and Infrastructure reflect the forecasts in latest WALGA Quarterly Economic Briefing (the LGCI Forecasts table) available at the time the DCP Report is adopted. The Administration index reflects the LGCI Component “Employee Costs” and the Infrastructure index reflects the LGCI Component “Road and Bridge Construction”. The Land Value index is provided as part of the independent Land Valuation (see Appendix L).

Escalation rates will separately apply to infrastructure costs, land costs and administration costs. The escalation rates will be set at each cost review. Given that the contribution rate entails items with different escalation rates, it is necessary to calculate a weighted escalation rate as follows:

$ER = (\%IC/TC \times IER) + (\%LV/TC \times LVER) + (\%AC/TC \times AER)$, where:

- ER - is the weighted Escalation Rate;
- DER - is the daily escalation rate (ER/365);
- IC - is the estimated Infrastructure Cost;
- LV - is the estimated Land Value;
- AC - is the estimated administration Cost, including water monitoring;
- TC - is the Total Cost being IC + LV + AC;
- IER - is the Infrastructure Escalation Rate;
- LVER - is the Land Value Escalation Rate;
- AER - is the Administration Escalation Rate; and
- D - is the number of days since the last cost review.



The daily indexing of costs described above, means that at any point in time, the Contribution per Lot/m² value will vary according to the number of days since the last Cost Review.

14.8 Calculating the Contribution liability for Landowners/Developers

The Mundijong Whitby Urban DCA is depicted on Plan 10C of Appendix 10 within the Shire of Serpentine Town Planning Scheme No. 2.

The Cost Contribution rate is to be calculated on a m² basis based on the remaining developable land in the DCP Area identified in Plan 10C. The remaining DCP cost is shared proportionally across the remaining developable land in the DCP Area as follows:

(Remaining Cost / Remaining Developable land = \$ contribution rate per m²).

For simplicity of calculation, all Residential lots/dwellings will be calculated as an average R25 (350m²) lot. For Non-Residential subdivision or development, the actual lot area is used for the calculation.

A cost review is to be undertaken at least annually, at which time the Contribution rate will be established based on:

- Road Upgrades and Construction
- District Open Space Improvements
- Land required for Roads, POS, Drainage and DOS
- Water monitoring costs
- Administration Costs
- Yields and Lots completed and expected
- Escalation Rates

To ensure costs remain current between Cost Reviews, all costs will be calculated daily based upon an annual escalation rate to be established through the Cost Review. The start date for daily escalation is the approval date for the prevailing Cost Review.

The Contribution Rate is to be applied as follows where DER is the daily escalation rate, D is the number of days since the last cost review:

(i) Standard residential subdivision or development

The number of additional dwellings/lots being created at the time of subdivision/development multiplied by the applicable development contribution rate.

(Contribution rate per lot/dwelling x DER x D) x number of additional lots or dwellings being created = Required development contribution



(ii) Non-standard residential subdivision or development (e.g. Lifestyle village, retirement village, caravan park, park home estate or similar).

The number of additional dwellings, residential units or similar created at the time of subdivision/development multiplied by the applicable development contribution rate.

(Contribution rate per lot/dwelling x DER x D) x number of additional lots or dwellings being created = Required development contribution

(iii) Non-residential subdivision or development

A development contribution is required for the creation of non-residential lots based on the actual size and number of lots created (minus the equivalent of one lot), multiplied by the applicable development contribution rate. Where a subdivision creates a lot that accommodates an existing approved non-residential development, that lot shall be exempt from the requirement for a development contribution to be made. For clarity purposes, the area of the lot accommodating the existing approved non-residential development is to be subtracted from the overall subdivision area, before calculating the development contribution for the remaining balance of the subdivision area.

New non-residential development (including alterations and additions to existing non-residential development) will not be required to make a development contribution unless the new non-residential development results in increased traffic to the subject land, as identified by the information provided by the applicant in support of the development application for that new non-residential development. Where increased traffic is identified to occur, the applicable development contribution is to be calculated as follows:

Square metre rate x square metre size of land being developed (including alterations and additions) = Required development contribution

For new private education establishments and associated development, provided a shared use agreement for public access to district open space is agreed to the satisfaction of the Local Government, development contributions shall be levied at 0.3 percent of the total development costs of the site, as agreed with the Local Government based on the building licence application.

(iv) Mixed-use development

The R25 subdivision/development potential of the site, or the actual number of lots/dwellings being created at the time of subdivision/development, whichever is the greater (minus the equivalent of one lot or dwelling), multiplied by the applicable development contribution rate.

Based on the R25 site calculation:

(Contribution rate per lot/dwelling x DER x D) x (R25 subdivision/development potential of the site - the equivalent of one lot or one dwelling) = Required contribution rate

Based on the number of dwellings



(Contribution rate per lot/dwelling x DER x D) x (actual number of residential lots/dwellings being created - the first dwelling being created) = Required development contribution

[Appendix B](#) gives examples of the respective calculations.

Future Subdivision/Development Potential

It is acknowledged that land within the DCA may be developed to a residential density lower than that envisaged within the yield calculations. Such development may however allow for additional subdivision and/or development in the future.

Contributions will be required for the creation of additional lots/dwellings post-initial development at the time that those additional lots/dwellings are created. Such additional contributions will be required in accordance with the Development Contribution Plan.

It is important to note that where the land use is non-residential, the DCP liability will be incurred only once on any site area (footprint) provided the liability discharged is based on the full development potential of the lot. Subsequent non-residential development will not be liable for additional DCP contributions.

For example, multilevel non-residential development or ongoing development on the non-residential site will be exempt from further DCP liability; liability is based on the non-residential land "footprint". However, should there be subsequent *residential* development above the non-residential development footprint; additional contribution liability will be incurred for the additional residential dwellings.

15 Priority and timing of infrastructure delivery

Details of the priority/timing of infrastructure items can be seen in the Capital Expenditure Plan in [Appendix C](#).

Timelines are based on the forecast rate of development and expected DCP funds from forecast contributions to be paid. This is reviewed annually and may be adjusted depending upon the rate of development and available DCA3 funds.

[Appendix M](#) contains the Infrastructure Delivery Status Report, in line with SPP 3.6 requirements, which details the planned timelines and any variation to these from the previous DCP revision.

16 Payment of contributions

An owner's liability to pay the owner's cost contribution to the local government arises on the earlier of:

- the local government recommending its approval on the deposited plan or survey strata plan of the subdivision of the owner's land within the development contribution area (subdivision/strata clearance);
- the commencement of any development on the owner's land within the development contribution area (typically triggered at Building Permit application); or
- the approval of a change or extension of use by the local government on the owner's



land within the development contribution area.

Where a subdivision is staged, the development contribution is payable only on those stages being cleared.

16.1 Form of Contributions

Pursuant to Clause 9.3.14 of TPS 2, conditions relating to development contribution requirements can, to the satisfaction of the Shire, be satisfied by:

- Cheque or cash
- Transferring to the local government or a public authority land in satisfaction of the cost contribution
- The provision of physical infrastructure
- Some other method acceptable to the local government, or
- Any combination of these methods.

16.2 Exemptions

Clause 9.3.13.3 of TPS 2 details specific exemptions for which a development contribution is not required.

17 DCP Credits

17.1 DCP Credits to offset Contributions

A landowner may gain DCP credits for provision of DCP infrastructure items (known as “Pre-Funding”) and/or land ceded for road widening, POS/Drainage, and DOS.

DCP Credits can be used to offset DCP Contributions (within the same DCA). Credits must be “banked” (through ceding land or completion of pre-funded infrastructure), before they can be used to offset a Contribution liability.

DCP Credits will always be allocated to the registered landowner, as likewise, the liability for DCP Contributions is a liability of the landowner. Credits do not transfer upon sale of the land, unless a legal agreement between the seller, purchaser and the Shire is in place to enable this.

17.2 Credits for DCP Land Ceded

Credits are applicable for land included in the DCP for POS/Drainage, DOS and Road Reserves. The land value applied to credits, will be the land value published in the DCP Report Revision at the time the land is ceded (i.e. Subdivision Clearance).



17.3 Credits for Pre-Funding of DCP Infrastructure

17.3.1 Pre-Funding Agreement

The Shire will support pre-funding and delivery of the infrastructure, provided there are good reasons for doing so and in instances where:

- The works are necessary for the progression of an approved subdivision, or
- The Developer wishes to undertake works specified in the DCP and the Shire does not hold enough DCP funds to undertake the works and/or has not prioritised such works.

By way of an exchange of letters, the Shire and the Developer will agree the extent, composition and timing of the infrastructure works to be pre-funded. Once agreed, the works become the Approved Works. The Approved Works must be identified sufficiently to ensure the cost and quantities of completed and remaining works in that item can be quantified.

17.3.2 Acceptance of Works

The Developer shall ensure the works are:

- Undertaken in a proper and workmanlike manner
- In accordance with plans and specifications constituting the Approved Works, and
- Completed within the agreed period.

Following written notification from the Developer, that the Approved Works are complete as above, the Shire will confirm the delivery of the Approved Works to its satisfaction.

The Shire can modify, accept or reject the claim where justified, following review of standard and cost. Referral to the Mundijong Industry Reference Group for comment should be made where rejection of the claim is proposed.

17.3.3 Principles for Cost Recoupment

The recoup is to be based on the current Cost Estimate in accordance with the latest revision of the DCP Report whereby:

- The current cost estimate (excluding contingency allowance) as described in the prevailing DCP Report shall constitute the maximum claimable amount for the completed Approved Works
- If the actual cost of the works exceeds the escalated cost estimate, the developer may claim an additional amount, not exceeding the contingency allowance provided for this item of work. Such a claim shall be independently substantiated to the satisfaction of the Shire
- The cost estimate will be subject to escalation at the rate prescribed from time to time in the DCP Report, up to the time of agreed practical completion of the works.

Once Approved, costs claimed by the Developer/Landowner for the pre-funded works will be independently verified as reasonable and in line with DCP inclusions/exclusions.

DCP credits will only be allocated once agreement is reached on the final claim value for such works after the independent review has occurred.

The value of DCP Credits allocated is *exclusive* of GST.



17.4 Repayment of DCP Credit Balance

Where a developer or landowner has completed all their developments within the DCA and has no further holdings in the DCA, any resulting credit balance amount is held by the local government as a credit to the developer or landowner until sufficient funds are available in the DCP fund to cover the credited amount, taking consideration of planned or committed expenditure at that time.

All credit balance repayment requests during the operation of the DCP, and which qualify for consideration (as per above), will be subject to a council report, and determined by Council. The credit is then reimbursed to the developer or landowner as soon as circumstances permit.

Requests for repayment of a credit balance, once development and landholdings applicable to that developer/landowner within the DCA are complete, should be made in writing to developmentcontributions@sjshire.wa.gov.au.

At the completion of the DCP, all credit balances are to be repaid no later than 90 days from the end date of the DCP.

18 Review

18.1 Major Review (5 Yearly)

In addition to the Annual Review provisions identified below, the Development Contribution Plan will be reviewed five years from the date of gazettal of the local planning scheme, or amendment to the local planning scheme to incorporate or amend the plan, or earlier should the local government consider it appropriate, having regard to the rate of development in the area and the degree of development potential still existing.

There is a statutory obligation for the Shire to advertise and seek comment on a major review of a DCP report. In addition to the statutory provisions, the Shire will consult with the Mundijong Industry Reference Group (MIRG).

18.2 Annual (Minor) Review

The DCP Report which accompanies the Plan, is to be reviewed at least annually. The following contribution rate inputs will be revised as part of this review:

- Remaining infrastructure costs
- Remaining land acquisition costs
- Remaining water monitoring costs
- Future administration Costs
- Remaining lots, and
- Cost Review Reconciliation* surplus or deficit to date.

*The Cost Review Reconciliation is an adjustment made in each revision to adjust for any over-collection or under-collection of DCP contributions versus DCP expenditure. DCP contributions



are always based on an estimate of future costs, whereas DCP expenditure is based on actual values. Any variance at the end of the prevailing DCP Report revision, is therefore adjusted on the “Reconciliation” line in the Cost Apportionment Spreadsheet, to assist the DCP in achieving the ultimate goal of breaking-even at its closure.

There is no statutory obligation for the Shire to advertise or seek comment on the minor annual review of a DCP report, however where the costing and details of the DCP Report are:

- revised based on accounting for completed works
- revised based on construction cost increases/decreases
- revised based on land value increases/decreases
- revised based on revisions to the anticipated undeveloped lot yield; and
- not subject to other material change

the Shire will consult with the Mundijong Industry Reference Group (MIRG).

It is noted that SPP 3.6 requires an Annual Status Report to be prepared by the local government providing an overview of progress of the delivery of infrastructure specified in the DCP, which is to be published on the local government’s website, within 6 months of Financial Year End. It therefore does not form part of this DCP Report.

The Annual Report will be available on the Shire’s website for each respective DCP, by no later than end December of each Financial Year: [Infrastructure Contributions » Shire of Serpentine Jarrahdale \(sjshire.wa.gov.au\)](https://www.sjshire.wa.gov.au/infrastructure-contributions)

18.2.1 Updates to Infrastructure Cost Estimates

Cost estimates will be updated annually.

For the purposes of the cost reviews, infrastructure costs may be reviewed in full by an appropriately qualified person or may be indexed based on the Building Cost Index or other appropriate index.

The Cost of Land will be updated annually, in accordance with section 9.1 of this report.

The Cost Apportionment Schedule will identify and adjust/apportion any funding received/required from non-DCP sources (e.g. grants or any “Shire-Share” portion of costs).

18.2.2 Cost Review Reconciliation

The Cost Review Reconciliation is an adjustment made in each revision to adjust for any over-collection or under-collection of DCP contributions versus DCP expenditure. DCP contributions are always based on an estimate of future costs, whereas DCP expenditure is based on actual values. Any variance at the end of the prevailing DCP Report revision, is therefore adjusted on the “Reconciliation” line in the Cost Apportionment Spreadsheet, to assist the DCP in achieving the ultimate goal of breaking-even at its closure.

At each Cost Review, the net balance of contributions and expenditure will be calculated.



Continued

Mundijong-Whitby Urban Traditional Infrastructure Development Contribution Plan Report

This net balance accounts for all contributions due from development in the previous development periods (no account is taken of contributions paid, i.e. cash received) and all expenditure (including credits earned, whether reimbursed or held on account).

A Cost Review can result in a surplus or deficit at the date of review. A surplus means the total contributions arising from development has exceeded the total costs incurred at the review date. A deficit means that the total contributions arising from development were less than the total costs incurred at the review date.

Future Mundijong-Whitby Urban Traditional Infrastructure Development Contribution Plan contribution rates account for this surplus or deficit, as well as future costs and lots yet to be developed.

Over the life of the Development Contribution Plan, the methodology employed should see the annual surpluses and deficits cancel out, to result in a break-even position for the DCP at the end of its lifespan.

[Appendix J](#) details the annual cost review outcomes from the latest review and any adjustment required for the following DCP Report period.

[Appendix N](#) contains the DCP Dashboard Summary for the DCP to date.



Continued

Mundijong-Whitby Urban Traditional Infrastructure Development Contribution Plan Report

19 Figures

Figure 1 – Development Contribution Area 3 (DCA3) Boundary





Mundijong-Whitby Urban Traditional Infrastructure Development Contribution Plan Report

Figure 2 – Mundijong District Structure Plan 2020



Freight Rail Realignment is a State Government Project provided by Main Roads.

| | | | | | | | | | |
|-----------------------------------|--|---|--|---------------------|--|---|--|---------------|--|
| Mundijong District Structure Plan | | Title: Preliminary Infrastructure Contribution Plan Date: 2020/07/01 | | Scale: 1:5000 04/17 | | Project Number: 2020/01 Drawing Number: 10/19 Revision: 0 | | Hames Sharley | |
|-----------------------------------|--|---|--|---------------------|--|---|--|---------------|--|


LEGEND

| | | |
|--|--|--|
| <ul style="list-style-type: none"> — MUNDIJONG DSP BOUNDARY ■ DISTRICT CENTRE ■ NEIGHBOURHOOD CENTRE ■ PUBLIC PURPOSE- UTILITIES ■ COMMUNITY AND PUBLIC PURPOSE ■ LIGHT INDUSTRIAL ■ INDUSTRIAL ■ BUSH FOREVER ■ DISTRICT/ NEIGHBOURHOOD OPEN SPACE ■ RESERVE ■ MULTIPLE USE CORRIDOR/LOCAL OPEN SPACE ■ INTER-MODAL FACILITY ■ HIGH FREQUENCY TRANSIT CORRIDOR | <ul style="list-style-type: none"> ■ MEDIUM - HIGH: R40-100 ■ LOW (SUBURBAN): R20-35 ■ LOW (TRANSITIONAL): R10-15 ■ SPECIAL USE ■ RURAL SMALL HOLDINGS ■ RURAL ■ URBAN EXPANSION ■ PRIMARY DISTRIBUTOR ■ DISTRICT DISTRIBUTOR ■ RAILWAY RESERVE ■ FREIGHT RAIL REALIGNMENT ■ RAIL LINE ● TRANSIT NODE | <ul style="list-style-type: none"> ● WASTE WATER PUMP STATION AND BUFFER ○ DIA BOUNDARY ○ DEVELOPMENT INVESTIGATION AREA ○ EHS EXISTING HIGH SCHOOL ○ EPS EXISTING PRIMARY SCHOOL ○ HS HIGH SCHOOL ○ PS PRIMARY SCHOOL ○ D DISTRICT OPEN SPACE ○ N NEIGHBOURHOOD OPEN SPACE ○ U UNIVERSITY/ INNOVATION HUB ○ C CEMETERY ○ E EMERGENCY SERVICES |
|--|--|--|



Mundijong-Whitby Urban Traditional Infrastructure Development Contribution Plan Report

Figure 3 – Roads to be constructed/upgraded





Continued

Mundijong-Whitby Urban Traditional Infrastructure Development Contribution Plan Report

Figure 4 – District Open Space to be constructed/upgraded



Mundijong-Whitby Urban Traditional Infrastructure Development Contribution Plan Report

Appendices

Mundijong-Whitby Urban Traditional Infrastructure Development Contribution Plan Report

Appendix A: Cost Apportionment Schedule

Previous Revision
Variance prev rev

Cost Apportionment Schedule

Revision Number

Revision Date

Ave Res Lot Size

Status

| DCA3_ | A | B | C | D | E | F | G |
|----------|---|-------------|---|---|---|---|---|
| 1 | Residential - Starting Contribution Per Lot | \$11,217.16 | | | | | |
| 17/07/23 | Residential Daily Index Value | \$0.8446 | | | | | |
| 350 | Non-Res - Starting Contribution per m2 | \$32.05 | | | | | |
| Final | Non-Res Daily Index Value | \$0.0024 | | | | | |

| | | |
|---|---------|-------|
| Index values: WALGA Economic Briefing - March 2023 | FC IER | 2.80% |
| | FC LVER | 2.50% |
| | FC AER | 3.80% |

| | Land Value | LVDER |
|-----------------|------------|---------|
| Residential | \$ 30.00 | \$0.002 |
| Non Residential | \$ 30.00 | \$0.002 |

| Item Name | Escalation Category | Completion Date | Infrastructure Plan Estimates | | | | Dwelling Yields | | | Contribution Breakdown per Lot | | | | | | | |
|---------------------------------------|---------------------|-----------------|-------------------------------|---------------------|------------------|-------------------|-------------------------------------|------------------------|-------------------------|--------------------------------|------------|------------|--|--|--|--|--|
| | | | Total Project Cost | Less Grants / Other | Less Shire Share | Completed To Date | Remaining Project Cost this DCP Rev | Contributing Precincts | Total Contributing Lots | Remaining Contributing Lots | By Item | Precinct A | | | | | |
| Reconciliation | n/a | | \$0 | \$0 | \$0 | | \$0 | A | 8459 | 8459 | \$0.00 | \$0.00 | | | | | |
| Land_LSP (POS) | LVER | | \$19,325,850 | \$0 | \$0 | \$0 | \$19,325,850 | A | 8459 | 8459 | \$2,284.57 | \$2,284.57 | | | | | |
| Land_Infra (DOS_Roads) | LVER | | \$5,165,670 | \$0 | \$0 | \$0 | \$5,165,670 | A | 8459 | 8459 | \$610.65 | \$610.65 | | | | | |
| Administration | AER | | \$1,400,472 | \$0 | \$0 | \$0 | \$1,400,472 | A | 8459 | 8459 | \$165.55 | \$165.55 | | | | | |
| Water Monitoring | AER | 2038 | \$1,031,650 | \$0 | \$0 | \$0 | \$1,031,650 | A | 8459 | 8459 | \$121.95 | \$121.95 | | | | | |
| Whitby High School DSS (Reilly Rd) | IER | 2035 | \$4,328,000 | \$0 | \$0 | \$0 | \$4,328,000 | A | 8459 | 8459 | \$511.63 | \$511.63 | | | | | |
| Taylor Rd/Scott Rd Primary School NOS | IER | 2033 | \$4,328,000 | \$0 | \$0 | \$0 | \$4,328,000 | A | 8459 | 8459 | \$511.63 | \$511.63 | | | | | |
| Keirnan Park DSS - 1b: Ovals | IER | 2034 | \$4,295,984 | -\$1,288,290 | \$0 | \$0 | \$3,007,693 | A | 8459 | 8459 | \$355.55 | \$355.55 | | | | | |
| Bishop Road East | IER | 2028 | \$11,415,959 | \$0 | \$0 | \$0 | \$11,415,959 | A | 8459 | 8459 | \$1,349.52 | \$1,349.52 | | | | | |
| Taylor Road | IER | 2027 | \$11,692,334 | \$0 | \$0 | \$0 | \$11,692,334 | A | 8459 | 8459 | \$1,382.19 | \$1,382.19 | | | | | |
| Town Centre Distributor Road | IER | 2028 | \$17,485,755 | \$0 | \$0 | \$0 | \$17,485,755 | A | 8459 | 8459 | \$2,067.05 | \$2,067.05 | | | | | |
| North South Road | IER | 2031 | \$6,822,168 | \$0 | \$0 | \$0 | \$6,822,168 | A | 8459 | 8459 | \$806.47 | \$806.47 | | | | | |
| Skyline Boulevard | IER | 2033 | \$2,734,156 | \$0 | \$0 | \$0 | \$2,734,156 | A | 8459 | 8459 | \$323.21 | \$323.21 | | | | | |
| Tinspar Avenue | IER | 2036 | \$6,151,575 | \$0 | \$0 | \$0 | \$6,151,575 | A | 8459 | 8459 | \$727.20 | \$727.20 | | | | | |

Mundijong-Whitby Urban Traditional Infrastructure Development Contribution Plan Report

Appendix B: Example Calculations

Example Contribution Calculations

EXAMPLE CALCULATIONS: Note, for simplicity, daily indexing has not been applied to the below examples.

DCA: DCA3_
Report Revision: 1

Example 1

A residential subdivision creating 50 lots within Precinct A, with one existing parent lot:

| Precinct | Development Contribution Rate per lot/dwelling | Number of additional lots/dwellings | Total development contribution | Calculation |
|----------|--|-------------------------------------|--------------------------------|--|
| A | \$11,217.16 | 49 | \$549,640.61 | $\$11,217.16 \times (50 - 1) = \$549,640.61$ |

Example 2

A residential subdivision in Precinct A, creating 50 lots, with one existing parent lot AND providing 10,000 m2 of creditable public open space / drainage residential land)

Note: creditable land must be cleared before, or at the same time, as the lot clearance in order to be offset against contributions due. Credits that are not yet earned/cleared cannot be used to offset Contributions due.

| Precinct | Development Contribution Rate per lot/dwelling | Number of additional lots/dwellings | Total development contribution | Calculation |
|--------------------------|--|-------------------------------------|--------------------------------|--|
| A | \$11,217.16 | 49 | \$549,640.61 | $\$11,217.16 \times (50 - 1) = \$549,640.61$ |
| Public open space credit | m2 of land being provided | Land value per m2 | Credit amount | Calculation |
| | 10,000 | \$30.00 | \$300,000.00 | $\$10,000.00 \times 30 = \$300,000.00$ |
| | | Total net development contribution | \$249,640.61 | $\$549,640.61 - \$300,000.00 = \$249,640.61$ |

Example 3

A non-residential subdivision creating a 4000m² lot within Precinct A

| Precinct | Development Contribution Rate per m2 | Parent Lot Discount | Total development contribution | Calculation |
|----------|--------------------------------------|---------------------|--------------------------------|---|
| A | \$32.05 | N/A | \$128,196.06 | $(\$32.05 \times 4,000\text{m}^2) = \$128,196.06$ |

#REF!

Mundijong-Whitby Urban Traditional Infrastructure Development Contribution Plan Report

Appendix C: Capital Expenditure Plan

Program Schedule
 Mundijong Whitby Urban Traditional DCP
 Revision Number: 1

DCA3 View Year 2023

Legend Today
 DCP End
 DCP Not

Note: Commencement date is reflective of commencing design stage, not construction stage.

| Item | Item ID | Commencement Phase | Start | End | Duration (Months) | Budget | Notes |
|-------------------------------------|----------------------------------|--------------------|--------|--------|-------------------|---------------|---------------|
| Warren Park Bldg - 1st Deck | First Deck | Skid | 1-5 | Jul 23 | Oct 24 | 85% | \$ 1,268,277 |
| Tram Centre Distribution Road | 1st Whitby New Rd | Developer | 1-5 | Jul 23 | Jul 23 | 100% | \$ 18,147,745 |
| Traylar Road | Developer | 6-10 | Jul 23 | Jul 27 | 100% | \$ 194,000 | |
| Wayline Backward | Expansion of its horizontal Bldg | Developer | 6-10 | Aug 23 | Aug 23 | 100% | \$ 476,045 |
| Whiplog Road Gate | Developer | 1-4 | Jul 23 | Jul 23 | 100% | \$ 11,796,419 | |
| North South Road | Developer | 11-15 | Jul 23 | Jul 23 | 100% | \$ 7,234,144 | |
| Taylor McLeod Rd Primary School RGS | Developer | 11-15 | Jul 23 | Jul 23 | 100% | \$ 1,128,000 | |
| Wayline Backward | Horizontal Bldg to New Whitby Rd | Developer | 6-10 | Aug 23 | Aug 23 | 70% | \$ 2,112,011 |
| Temper Avenue | Developer | 6-10 | Mar 24 | Jun 24 | 100% | \$ 6,937,075 | |
| Whitby High School Bldg (Whitby Rd) | Developer | 11-15 | Jul 23 | Jul 23 | 100% | \$ 1,111,000 | |
| Warren Park Bldg - 1st Deck | Second Deck | Skid | 11-15 | Jul 23 | Jul 23 | 60% | \$ 1,884,414 |
| Water Monitoring | Year 0 (2027) set up | Skid | Feb 27 | Jun 28 | | \$ 120,240 | |
| Water Monitoring | Year 1 | Skid | Feb 28 | Jun 29 | | \$ 82,040 | |
| Water Monitoring | Year 2 | Skid | Feb 29 | Jun 30 | | \$ 82,040 | |
| Water Monitoring | Year 3 | Skid | Feb 30 | Jun 31 | | \$ 82,040 | |
| Water Monitoring | Year 4 | Skid | Feb 31 | Jun 32 | | \$ 82,040 | |
| Water Monitoring | Year 5 | Skid | Feb 32 | Jun 33 | | \$ 82,040 | |
| Water Monitoring | Year 6 | Skid | Feb 33 | Jun 34 | | \$ 82,040 | |
| Water Monitoring | Year 7 | Skid | Feb 34 | Jun 35 | | \$ 82,040 | |
| Water Monitoring | Year 8 | Skid | Feb 35 | Jun 36 | | \$ 82,040 | |
| Water Monitoring | Year 9 | Skid | Feb 36 | Jun 37 | | \$ 82,040 | |
| Water Monitoring | Year 10 | Skid | Feb 37 | Jun 38 | | \$ 77,040 | |

Mundijong-Whitby Urban Traditional Infrastructure Development Contribution Plan Report

Appendix D: Infrastructure Designs

Not applicable

Mundijong-Whitby Urban Traditional Infrastructure Development Contribution Plan Report

Appendix E: Schedule of Costs - Land for Infrastructure (Roads & District Open Space)

Mundijong-Whitby Urban Traditional Infrastructure Development Contribution Plan Report

Appendix F: Schedule of Costs - Land for Public Open Space & Drainage

SCHEDULE OF COSTS

POS Completed and Remaining

DCA: DCA3_
Report Revision: 1

Residential Land Value (this revision): \$30.00
Non-Residential Land Value (this revision): \$30.00

| Structure Plan Areas | ESTIMATED TOTAL Land m2 | | | | COMPLETED Land m2 | | | | REMAINING Land m2 | | | |
|----------------------|-------------------------|-----------------|---------|-----------------------|-------------------|-----------------|-------|-----------------------|-------------------|-----------------|---------|-----------------------|
| | Residential | Non-Residential | Total | Var previous Revision | Residential | Non-Residential | Total | Var previous Revision | Residential | Non-Residential | Total | Var previous Revision |
| Totals: | 644,195 | - | 644,195 | 644,195 | - | - | - | - | 644,195 | - | 644,195 | 644,195 |

Previous DCP Revision Comparison

DCP 0

Residential Land Value (this revision):
Non-Residential Land Value (this revision):

| Structure Plan Areas | ESTIMATED TOTAL Land m2 | | | | COMPLETED Land m2 | | | | REMAINING Land m2 | | | |
|----------------------|-------------------------|-----------------|-------|-----------------------|-------------------|-----------------|-------|-----------------------|-------------------|-----------------|-------|-----------------------|
| | Residential | Non-Residential | Total | Var previous Revision | Residential | Non-Residential | Total | Var previous Revision | Residential | Non-Residential | Total | Var previous Revision |
| Totals: | - | - | - | - | - | - | - | - | - | - | - | - |

| Structure Plan Areas | ESTIMATED TOTAL Land \$ | | | | COMPLETED Land \$ | | | | REMAINING Land \$ | | | |
|----------------------|-------------------------|-----------------|--------------|-----------------------|-------------------|-----------------|-------|-----------------------|-------------------|-----------------|--------------|-----------------------|
| | Residential | Non-Residential | Total | Var previous Revision | Residential | Non-Residential | Total | Var previous Revision | Residential | Non-Residential | Total | Var previous Revision |
| Totals: | \$19,325,850 | \$0 | \$19,325,850 | \$19,325,850 | \$0 | \$0 | \$0 | \$0 | \$19,325,850 | \$0 | \$19,325,850 | \$19,325,850 |

| Structure Plan Areas | ESTIMATED TOTAL Land \$ | | | | COMPLETED Land \$ | | | | REMAINING Land \$ | | | |
|----------------------|-------------------------|-----------------|-------|-----------------------|-------------------|-----------------|-------|-----------------------|-------------------|-----------------|-------|-----------------------|
| | Residential | Non-Residential | Total | Var previous Revision | Residential | Non-Residential | Total | Var previous Revision | Residential | Non-Residential | Total | Var previous Revision |
| Totals: | \$0 | \$0 | \$0 | \$0 | \$0 | \$0 | \$0 | \$0 | \$0 | \$0 | \$0 | \$0 |

Mundijong-Whitby Urban Traditional Infrastructure Development Contribution Plan Report

Appendix G: Schedule of Costs – Infrastructure to be constructed/upgraded

Mundijong-Whitby Urban Traditional Infrastructure Development Contribution Plan Report

Appendix H: Schedule of Costs – Administration

SCHEDULE OF COSTS

ADMINISTRATION COSTS Budget FY 2023
Report Revision
Fiscal Year

DCA3_ 23/05/2023 1 DCA3_ 23/05/2023 1 DCA3_ 23/05/2023 1 No Match

| Mundjongo-Whitby Urban Traditional Infrastructure DCP | Budget FY 2023 | Years Remaining | Remaining Spend | Spent to Date (See Table 4) | Total Forecast Spend |
|---|----------------|-----------------|-----------------|-----------------------------|----------------------|
| Legal Expenses | \$4,000.00 | 14.85 | \$59,400.00 | | |
| Advertising, Promotion & Consultancy | \$3,000.00 | 14.85 | \$44,550.00 | | |
| DWMS Review | \$0.00 | 14.85 | \$0.00 | | |
| Wages Totals (See Table 1) | \$40,325.60 | 14.85 | \$598,835.19 | | |
| Sub Total | \$47,325.60 | 14.85 | \$702,785.19 | \$697,686.87 | \$1,400,472.06 |
| Change from previous year (see Tables 2 and 3) | \$1,513 | -50 | \$15,599 | \$697,687 | \$713,286 |

Table 1 - Budget allocations current FY

| Budget FY 2023 | DCA1 | DCA2 | DCA3 | DCA4 | Totals |
|---|------------|-----------|------------|------------|-----------|
| Legal Expenses | \$4,000 | \$4,000 | \$4,000 | \$4,000 | \$16,000 |
| Advertising, Promotion & Consultancy | \$3,000 | \$3,000 | \$3,000 | \$3,000 | \$12,000 |
| DWMS Review | \$0 | \$0 | \$0 | \$0 | \$0 |
| Wages Totals (see below allocations) | \$80,651 | \$13,441 | \$40,326 | \$134,418 | \$268,836 |
| Sub Totals | \$87,651 | \$20,441 | \$47,326 | \$141,418 | \$296,836 |
| Change from previous year | \$48,723 | -\$25,370 | \$1,613 | \$80,972 | \$8,391 |
| Salary allocations | 30% of FTE | 5% of FTE | 15% of FTE | 50% of FTE | Total FTE |
| Technical Specialist Infrastructure Contributions (DCP Coordinator) | 0.30 | 0.050 | 0.150 | 0.500 | 1.000 |
| Director Development Services | 0.03 | 0.005 | 0.015 | 0.050 | 0.100 |
| Coordinator Strategic Planning | 0.02 | 0.003 | 0.008 | 0.025 | 0.050 |
| Manager Strategic Planning | 0.03 | 0.005 | 0.015 | 0.050 | 0.100 |
| Manager Engineering Services | 0.01 | 0.001 | 0.003 | 0.010 | 0.020 |
| Engineering Development Lead | 0.01 | 0.002 | 0.005 | 0.015 | 0.030 |
| Engineering Design Lead | 0.01 | 0.001 | 0.003 | 0.010 | 0.020 |
| Infrastructure Projects Lead | 0.01 | 0.001 | 0.003 | 0.010 | 0.020 |
| Manager Major Projects | 0.01 | 0.001 | 0.003 | 0.010 | 0.020 |
| Senior Project Engineer | 0.01 | 0.001 | 0.003 | 0.010 | 0.020 |
| Manager Finance | 0.03 | 0.005 | 0.015 | 0.050 | 0.100 |
| Management Accountant | 0.03 | 0.005 | 0.015 | 0.050 | 0.100 |
| Financial Accountant | 0.06 | 0.010 | 0.030 | 0.100 | 0.200 |

Table 2 - Administration Costs Previous FY

| ADMINISTRATION COSTS | DCA3_ 23/05/2023 0 | DCA3_ 23/05/2023 0 | DCA3_ 23/05/2023 0 | DCA3_ 23/05/2023 0 | |
|---|--------------------|--------------------|--------------------|-----------------------------|----------------------|
| Mundjongo-Whitby Urban Traditional Infrastructure DCP | Budget FY 2022 | Years Remaining | Remaining Spend | Spent to Date (See Table 3) | Total Forecast Spend |
| Legal Expenses | \$4,000.00 | 15.00 | \$60,000.00 | | |
| Advertising, Promotion & Consultancy | \$3,000.00 | 15.00 | \$45,000.00 | | |
| DWMS Review | \$0.00 | 15.00 | \$0.00 | | |
| Wages Totals (See Table 1) | \$38,812.41 | 15.00 | \$587,186.16 | \$0.00 | \$687,186.16 |
| Sub Total | \$45,812.41 | 15.00 | \$687,186.16 | \$0.00 | \$687,186.16 |

Table 3 - Budget allocations previous FY

| Budget FY 2022-23 | DCA1 | DCA2 | DCA3 | DCA4 | Totals |
|---|-----------|------------|------------|------------|------------|
| Legal Expenses | \$4,000 | \$4,000 | \$4,000 | \$4,000 | \$16,000 |
| Advertising, Promotion & Consultancy | \$3,000 | \$3,000 | \$3,000 | \$0 | \$9,000 |
| DWMS Review | \$0 | \$0 | \$0 | \$0 | \$0 |
| Wages Totals (see below allocations) | \$129,375 | \$38,812 | \$38,812 | \$96,446 | \$263,445 |
| Sub Totals | \$136,375 | \$45,812 | \$45,812 | \$96,446 | \$288,445 |
| Salary allocations | Total FTE | 50% of FTE | 15% of FTE | 15% of FTE | 20% of FTE |
| Technical Specialist Infrastructure Contributions (DCP Coordinator) | 1.00 | 0.50 | 0.150 | 0.150 | 0.200 |
| Director Development Services | 0.10 | 0.05 | 0.015 | 0.015 | 0.020 |
| Coordinator Strategic Planning | 0.05 | 0.03 | 0.008 | 0.008 | 0.010 |
| Manager Strategic Planning | 0.10 | 0.05 | 0.015 | 0.015 | 0.020 |
| Manager Engineering Services | 0.02 | 0.01 | 0.003 | 0.003 | 0.004 |
| Engineering Development Lead | 0.03 | 0.02 | 0.005 | 0.005 | 0.006 |
| Engineering Design Lead | 0.02 | 0.01 | 0.003 | 0.003 | 0.004 |
| Manager Project Delivery | 0.02 | 0.01 | 0.003 | 0.003 | 0.004 |
| Infrastructure Projects Lead | 0.02 | 0.01 | 0.003 | 0.003 | 0.004 |
| Senior Project Engineer | 0.02 | 0.01 | 0.003 | 0.003 | 0.004 |
| Manager Finance | 0.10 | 0.05 | 0.015 | 0.015 | 0.020 |
| Management Accountant | 0.10 | 0.05 | 0.015 | 0.015 | 0.020 |
| Financial Accountant | 0.20 | 0.10 | 0.030 | 0.030 | 0.040 |

Table 4

| DCA | DCA3_ (All) |
|------------------|----------------|
| Developer | Administration |
| Development Name | |
| Report Revision | (All) |

| Row Labels | Administration spend to date |
|---|------------------------------|
| 2022 | -\$651,874.87 |
| Setup Costs | -\$652,295.42 |
| Up to end FY21/22 | \$420.55 |
| 2023 | -\$45,812.00 |
| Set up costs - Admin costs (budget) 2022/23 - TBC | -\$45,812.00 |
| Grand Total | -\$697,686.87 |

Mundijong-Whitby Urban Traditional Infrastructure Development Contribution Plan Report

Appendix I: Schedule of Costs – Water Monitoring

Shire of Serpentine Jarrahdale DCP
DCA 3 - Mundijong-Whitby Urban Traditional Infrastructure

Our Ref: E23/7712

| | DCP1 | | |
|--------------------------|------------------|-------------|--------------------|
| Summary of Costs: | Costed by | Date | Cost |
| Water Monitoring | Urbaqua | Jun-22 | \$1,031,650 |
| TOTAL (excl. GST) | | | \$1,031,650 |

WATER MONITORING COSTS

Mundijong Whitby Urban Development Contribution Plan

| Description | Hours Qty | People Qty | Salary \$/hr | Sample No. Qty | Sample runs/yr Qty | Cost Per Sample \$ | Sites Qty | Rate \$ | Cost | Contingency 25% | Annual Cost (GST Excl) | Years | Total Cost (GST Excl) |
|---|-----------|------------|--------------|----------------|--------------------|--------------------|-----------|----------|------------------|-----------------|------------------------|-------|-----------------------|
| Sampling Program Management | | | | | | | | | | | | | |
| Preparation of the RFQ/Tender, Tender Brief, Scope and Specification | 120 | 1 | \$200 | | | | | | \$24,000 | \$6,000 | \$30,000 | 1 | \$30,000 |
| Preparation of Sample and Analysis Plan (SAP) | 20 | 1 | \$100 | | | | | | \$2,000 | \$500 | \$2,500 | 1 | \$2,500 |
| Program management (incl updates to SAP as required) | 50 | 1 | \$200 | | | | | | \$10,000 | \$2,500 | \$12,500 | 10 | \$125,000 |
| Data Management (site and program registration, data entry, validation) | 40 | 1 | \$100 | | | | | | \$4,000 | \$1,000 | \$5,000 | 10 | \$50,000 |
| Preparation / assistance with report (Annual Report) | 50 | 2 | \$100 | | | | | | \$10,000 | \$2,500 | \$12,500 | 10 | \$125,000 |
| Total - Sampling Program Management | | | | | | | | | \$50,000 | \$12,500 | \$62,500 | | \$332,500 |
| Water Analysis (20 GW & 10 SW sites) | | | | | | | | | | | | | |
| Nitrogens (TN, TKN, NH4, NOx-N (NO3+NO2)) + TP + FRP | | | | 32 | 6 | 20 | 30 | | \$3,840 | \$960 | \$4,800 | 10 | \$48,000 |
| Dissolved Organic Nitrogen, DON | | | | 32 | 6 | 50 | 30 | | \$9,600 | \$2,400 | \$12,000 | 10 | \$120,000 |
| Total Dissolved Solids, TDS | | | | 32 | 6 | 25 | 30 | | \$4,800 | \$1,200 | \$6,000 | 10 | \$60,000 |
| Metals Set-up (Filtered) | | | | 32 | 1 | 12 | 30 | | \$384 | \$96 | \$480 | 10 | \$4,800 |
| Heavy Metals (Al, As, Cd, Cr, Cu, Fe, Pb, Ni, Zn & Hg) | | | | 32 | 1 | 70 | 30 | | \$2,240 | \$560 | \$2,800 | 10 | \$28,000 |
| Total Recoverable Hydrocarbons (TRH) | | | | 32 | 1 | 40 | 30 | | \$1,280 | \$320 | \$1,600 | 10 | \$16,000 |
| Polycyclic Aromatic Hydrocarbons and BTEX | | | | 32 | 1 | 90 | 30 | | \$2,880 | \$720 | \$3,600 | 10 | \$36,000 |
| Total - Water Analysis | | | | | | | | | \$25,024 | \$6,256 | \$31,280 | | \$312,800 |
| Sediment Analysis (10 sites) | | | | | | | | | | | | | |
| Total Recoverable Hydrocarbons (TRH) & BTEX | | | | 12 | 1 | 40 | 10 | | \$480 | \$120 | \$600 | 10 | \$6,000 |
| Polycyclic Aromatic Hydrocarbons (PAH) | | | | 12 | 1 | 90 | 10 | | \$1,080 | \$270 | \$1,350 | 10 | \$13,500 |
| Metals Set-up | | | | 12 | 1 | 14 | 10 | | \$168 | \$42 | \$210 | 10 | \$2,100 |
| Heavy Metals (Al, As, Cd, Cr, Cu, Fe, Pb, Ni, Zn & Hg) | | | | 12 | 1 | 70 | 10 | | \$840 | \$210 | \$1,050 | 10 | \$10,500 |
| Moisture (no charge with metals) | | | | 12 | 1 | 0 | 10 | | \$0 | \$0 | \$0 | 10 | \$0 |
| Total - Sediment Analysis | | | | | | | | | \$2,568 | \$642 | \$3,210 | | \$32,100 |
| Analysis - Other | | | | | | | | | | | | | |
| Troll 9500 Profiler XP (in-situ analysis) | | | | | | | | \$20,000 | \$20,000 | \$5,000 | \$25,000 | 1 | \$25,000 |
| Consumables (incl. nitrile Gloves) | | | | | 6 | | | \$100 | \$600 | \$150 | \$750 | 10 | \$7,500 |
| Equipment hire (pumps etc) | | | | | 6 | | | \$300 | \$1,800 | \$450 | \$2,250 | 10 | \$22,500 |
| Courier fees | | | | | 6 | | | \$40 | \$240 | \$60 | \$300 | 10 | \$3,000 |
| Total - Analysis - Other | | | | | | | | | \$22,640 | \$5,660 | \$28,300 | | \$58,000 |
| Superficial Groundwater Monitoring (20 sites) | | | | | | | | | | | | | |
| Installation of monitoring wells for superficial aquifer monitoring (average 3m depth, includes survey & development) | | | | | | | 20 | \$4,000 | \$80,000 | \$20,000 | \$100,000 | 1 | \$100,000 |
| Monitor local superficial aquifer groundwater levels (Monthly) - Labour incl travel between sites | 0.25 | 1 | 200 | | 12 | | 20 | | \$12,000 | \$3,000 | \$15,000 | 1 | \$15,000 |
| Monitor local superficial aquifer groundwater quality (Quarterly) - Labour incl travel between sites | 0.25 | 1 | 200 | | 4 | | 20 | | \$4,000 | \$1,000 | \$5,000 | 10 | \$50,000 |
| Monitor local superficial aquifer groundwater levels (Quarterly) - Labour incl travel between sites | 0.25 | 1 | 200 | | 4 | | 20 | | \$4,000 | \$1,000 | \$5,000 | 9 | \$45,000 |
| Total - Superficial Groundwater Monitoring | | | | | | | | | \$100,000 | \$25,000 | \$125,000 | | \$210,000 |
| Surface Water Monitoring | | | | | | | | | | | | | |
| Purchase & installation of surface water level loggers - 7 sites | | | | | | | 7 | \$5,000 | \$35,000 | \$8,750 | \$43,750 | 1 | \$43,750 |
| Monitor flows in Multiple Use Corridors - labour - 7 sites | 0.25 | 1 | 200 | | 4 | | 7 | | \$1,400 | \$350 | \$1,750 | 10 | \$17,500 |
| Monitor quality in Multiple Use Corridors - labour - 10 sites | 0.25 | 1 | 200 | | 4 | | 10 | | \$2,000 | \$500 | \$2,500 | 10 | \$25,000 |
| Total - Surface Water Level Monitoring | | | | | | | | | \$38,400 | \$9,600 | \$48,000 | | \$86,250 |
| Total - Water Quality Management | | | | | | | | | \$238,632 | \$59,658 | \$298,290 | | \$1,031,650 |

Mundijong-Whitby Urban Traditional Infrastructure Development Contribution Plan Report

Appendix J: Cost Review Reconciliation Adjustment

Mundijong-Whitby Urban Traditional Infrastructure Development Contribution Plan Report

Appendix K: Lots Completed and Remaining

Estimated Lots

Lots Completed and Remaining

DCA: DCA3_
 Report Revision: 1

| | ESTIMATED TOTAL LOTS | COMPLETED LOTS | ESTIMATED REMAINING LOTS | Lots Cleared under Amendment (to be carried over into the this next revision) |
|---|----------------------|----------------|--------------------------|---|
| Totals: | 8,459 | - | 8,459 | 429 |
| Whitby Estate - Precinct A | 2,512 | - | 2,512 | 425 |
| Keirnan Street - Precinct B | - | - | - | - |
| Watkins Road North - Precinct C | - | - | - | - |
| Watkins Road South - Precinct D | - | - | - | - |
| Taylor Road / Adams Street - Precinct E1 | 1,261 | - | 1,261 | - |
| L50 Cockram St & L119 Sparkman Rd - Precinct E2 | 574 | - | 574 | - |
| L9503 Mundijong Road - Precinct E3 | - | - | - | - |
| Mundijong Town Centre - Precinct F | - | - | - | 4 |
| Mundijong North - Precinct G1 | 2,945 | - | 2,945 | - |
| Keirnan Street - Precinct G2 | 230 | - | 230 | - |
| Lang Road - Precinct G3 | - | - | - | - |
| Area A Adjustment | 937 | - | 937 | - |

Mundijong-Whitby Urban Traditional Infrastructure Development Contribution Plan Report

Appendix L: Land Valuation

Executive Summary

| | | | | | | | |
|------------------------------|---|------------------------------|---|------------------------------|----------------------------|---|------------------------------|
| Property Address: | Mundijong-Whitby Traditional Infrastructure DCP – Development Contribution Area 3 (DCA3). | | | | | | |
| General Description: | <p>The subject of our valuation comprises notional englobo landholdings zoned as follows:</p> <ol style="list-style-type: none"> 1) “Residential R25” 2) “Mixed Use / R60” <p>Both scenarios assume the land comprises a 5.0ha parcel that requires servicing but is within close proximity to services so there are no major servicing constraints and no major geotechnical/environmental issues.</p> | | | | | | |
| Purpose of Valuation: | Annual Scheme Contribution purposes. | | | | | | |
| Valuation: | <table> <tr> <td>“Residential R25” Land Rate</td> <td>-</td> <td>\$30.00/m²</td> </tr> <tr> <td>“Mixed Use / R60 Land Rate</td> <td>-</td> <td>\$30.00/m²</td> </tr> </table> <p>The above values assume the land comprises a 5ha parcel that requires servicing but is within close proximity to services so there are no major servicing constraints and no major geotechnical/environmental issues.</p> <p>The above values are stated inclusive of GST and have considered a discount of 2.5% including GST, being an allowance for selling costs (sales commission, marketing and legal costs).</p> <p>Our valuation has assumed that there is no significant change in market conditions between the date of inspection and the date of valuation.</p> | “Residential R25” Land Rate | - | \$30.00/m² | “Mixed Use / R60 Land Rate | - | \$30.00/m² |
| “Residential R25” Land Rate | - | \$30.00/m² | | | | | |
| “Mixed Use / R60 Land Rate | - | \$30.00/m² | | | | | |
| Date of Inspection: | 25 November 2022. | | | | | | |
| Date of Valuation: | 1 February 2023. | | | | | | |
| Senior Valuer: | <p>David Molony AAPI, B.Com (Property & Finance) Certified Practising Valuer Licensed Valuer No. 44387 Western Australia</p> | | | | | | |

This Executive Summary is a brief synopsis of the property and our assessment of market value.

It is designed to provide a brief overview and must not be read in isolation, separate from our formal valuation report.

Definition of “Market Value”:

The International Valuation Standards Council (and as adopted by the Australian Property Institute) defines Market Value in the *International Valuation Standards 2022* as:

“The estimated amount for which an asset or liability should exchange on the valuation date between a willing buyer and a willing seller in an arm’s length transaction, after proper marketing and where the parties had each acted knowledgeably, prudently and without compulsion.”

Assumptions, Conditions and Limitations:

- The market is being impacted by the uncertainty caused by the COVID-19 pandemic. As at the date of valuation we consider that there is market uncertainty resulting in significant valuation uncertainty.

This valuation is therefore reported on the basis of ‘significant valuation uncertainty’. As a result, less certainty exists than normal and a higher degree of caution should be attached to our valuation than normally would be the case. Given the unknown future impact that COVID-19 might have on markets, we recommend that the user(s) of this report review this valuation periodically.

This valuation is current at the date of valuation only. The value assessed herein may change significantly and unexpectedly over a relatively short period of time (including as a result of factors that the valuer could not reasonably have been aware of as at the date of valuation). We do not accept responsibility or liability for any losses arising from such subsequent changes in value.

- The planning and cadastral details obtained from the Department of Planning, Lands & Heritage, Main Roads Western Australia, Landgate and Local Authority websites are current and correct.
- Adjoining land owners or community groups do not impede or restrain development as foreseen.
- We are not aware of any Notices currently issued against the property and we have made no enquiries in this regard.
- Our valuation assumes there is no asbestos contamination.

We must point out however, that we are not experts in the detection or quantification of asbestos problems and accordingly, have not carried out a detailed investigation. Therefore, this valuation is made on the assumption that there are no actual or potential asbestos contamination issues affecting the subject property.

Should a subsequent investigation undertaken by a suitably qualified expert show that the site is contaminated, we reserve the right to amend our valuation accordingly.

- The value and utility of land can be adversely affected by the presence of Aboriginal sacred sites and/or sites of Aboriginal heritage significance. We have made no investigations in this regard, as Aboriginal requirements can only be determined by the appointment of an appropriate expert.

Under these circumstances, we cannot warrant that there are no such sites on the land and if it is subsequently determined that the reality is so affected, we reserve the right to review this valuation.

- The land is assumed to comprise topsoils which are relatively free draining, however as no geotechnical investigations have been either undertaken or commissioned, we are unable to report on the underlying nature of the site.
- This market valuation assumes there is no environmental contamination of the property.
- This market valuation assumes there is no encroachment of adjoining buildings onto the subject property.
- This market valuation assumes an unencumbered fee simple title to the property.
- If there are any encumbrances, encroachments, restrictions, leases or covenants which are not noted in this report, they may affect the assessment of market value. If any such matters are known or discovered, we should be advised and asked as to whether they affect our assessment of market value.
- We have assumed that all information supplied in conducting this market valuation consists of a full and accurate disclosure of all information that is relevant.
- It is assumed that no significant event occurs between the date of inspection and the date of valuation that would impact on the market value of the subject property.
- We have not obtained a Property Interest Report in providing our advice. A property-specific report will provide detailed information of property interests not listed on the Certificate of Title that may affect the use and enjoyment of the land.

A report can be obtained from Landgate for a charge of \$54.95 (incl. GST). If a subsequent Property Interest Report reveals any aspects of the property that may impact on its value, we reserve the right to review our market valuation.

If there is any variance/contradiction in any of the above assumptions, then we reserve the right to review this market valuation accordingly.

16.0 VALUATION CONCLUSIONS

In considering suitable lands rate for the subject hypothetical parcels, we are of the opinion the following factors require due regard in this instance.

- The properties comprise notional parent parcels of 5.00ha.
- It is assumed the land requires servicing but is within close proximity to services so there are no major servicing constraints.
- It is assumed there are no major geotechnical/environmental issues.
- The DCP Area is within its infant stages with limited urban development in the local area.
- The first scenario assumes a relatively low notional density coding of “Residential R25”.
- The second scenario assumes a broader scope for development as “Mixed Use / R60”.
- Whilst finished lot values have generally appreciated in recent years, civil development costs have escalated rapidly which is having an associated negative impact on project feasibility.
- The “Mixed Use / R60” product is untested in the subject location and in our opinion offers no significant premium above and beyond traditional residential densities. We anticipate this could change as the area develops and the catchment matures.

Value per m² for Standard Residential/Non-Standard Residential:

Based on our analysis we have adopted a rate of **\$30.00/m²** including GST. This takes into consideration the 2.5% discount applicable for selling costs (sales commission, marketing and legal costs).

The above rate is current as at 1 February 2023.

Our valuation has assumed that there is no significant change in market conditions between the date of inspection and the date of valuation

Value per m² for Non-Residential:

Based on our analysis we have adopted a rate of **\$30.00/m²** including GST. This takes into consideration the 2.5% discount applicable for selling costs (sales commission, marketing and legal costs).

The above rate is current as at 1 February 2023.

Our valuation has assumed that there is no significant change in market conditions between the date of inspection and the date of valuation

Land Value Escalation Rate:

Based on current market conditions, we believe an indicative growth rate of **2.5%** is reasonable for the next 12 months.



David Molony AAPI, B. Com (Property & Finance)
 Certified Practising Valuer
 Licensed Valuer No. 44387
 Western Australia

Mundijong-Whitby Urban Traditional Infrastructure Development Contribution Plan Report

Appendix M: Infrastructure Delivery Status Report

Development Contribution Area: DCA3_
 Report Revision: 1
 Name of DCP: Mundijong-Whitby Urban Traditional Infrastructure DCP

Infrastructure Delivery Status Report

This report reflects the estimated **completion** dates for infrastructure items. Delivery may be staged, and works may be ongoing throughout the life of the DCP.

Summary of delivery of infrastructure





| Item of infrastructure | Scheduled delivery priority in previous DCP Revision | Progress/status (% complete by \$ value) | Expected delivery | % detail of funding | | | % detail of funding | | | Notes (Highlighted Cells) |
|---------------------------------------|--|--|-------------------|---------------------|-------|---------------|---------------------|-------|------|---------------------------|
| | | | | Grants | Shire | DCP | Grants | Shire | DCP | |
| Whitby High School DSS (Reilly Rd) | | 0% | 2035 | \$ - | \$ - | \$ 4,328,000 | 0% | 0% | 100% | |
| Taylor Rd/Scott Rd Primary School NOS | | 0% | 2033 | \$ - | \$ - | \$ 4,328,000 | 0% | 0% | 100% | |
| Keirnan Park DSS - 1b: Ovals | | 0% | 2034 | \$ 1,288,290 | \$ - | \$ 3,007,693 | 30% | 0% | 70% | |
| Bishop Road East | | 0% | 2028 | \$ - | \$ - | \$ 11,415,959 | 0% | 0% | 100% | |
| Taylor Road | | 0% | 2027 | \$ - | \$ - | \$ 11,692,334 | 0% | 0% | 100% | |
| Town Centre Distributor Road | | 0% | 2028 | \$ - | \$ - | \$ 17,485,755 | 0% | 0% | 100% | |
| North South Road | | 0% | 2031 | \$ - | \$ - | \$ 6,822,168 | 0% | 0% | 100% | |
| Skyline Boulevard | | 0% | 2033 | \$ - | \$ - | \$ 2,734,156 | 0% | 0% | 100% | |
| Tinspar Avenue | | 0% | 2036 | \$ - | \$ - | \$ 6,151,575 | 0% | 0% | 100% | |

Mundijong-Whitby Urban Traditional Infrastructure Development Contribution Plan Report

Appendix N: DCP Dashboard Summary

DCP Progress Summary Dashboard Report

DCA: DCA3_
 Report Revision: 1



Mundijong-Whitby Urban Traditional Infrastructure Development Contribution Plan Report

Appendix O: Infrastructure Costings – full breakdown

Shire of Serpentine Jarrahdale DCP
DCA 3 - Mundijong-Whitby Urban Traditional Infrastructure

Our Ref: E22/14032

| Summary of Costs: | DCP1 | | |
|---|---|-------------|---------------------|
| | Costed by | Date | Cost |
| Bishop Road (East) – Integrator B | Rawlinsons | Jun-23 | \$11,415,959 |
| Taylor Road – Integrator B | Rawlinsons | Jun-23 | \$11,692,334 |
| New Whitby Road (aka Town Centre Distributor Road) – Integrator B | Rawlinsons | Jun-23 | \$17,485,755 |
| North-South Road – Integrator B | Rawlinsons | Jun-23 | \$6,822,168 |
| Skyline Boulevard – Neighbourhood Connector A | Rawlinsons | Jun-23 | \$2,734,156 |
| Tinspar Avenue – Neighbourhood Connector A | Rawlinsons | Jun-23 | \$6,151,575 |
| Whitby High School District Sporting Space | Rawlinsons | Jun-23 | \$4,328,000 |
| Taylor Road / Scott Road Primary School Neighbourhood Open Space | Rawlinsons | Jun-23 | \$4,328,000 |
| Keirnan Park DOS Ovals | Shire 2021 Indexed 18% 2022 Indexed 5.1% 2023 | Jun-23 | \$3,007,693 |
| TOTAL (excl. GST) | | | \$67,965,640 |

**Shire of Serpentine Jarrahdale DCP
DCA 3 - Mundijong Whitby - Update**

| Code | Description | Quantity | UOM | Rate | Subtotal | Sub Section Total | Section Total | Road/ DOS Total |
|--------------|--|----------|------|---------|-----------|-------------------|---------------|-----------------|
| A | ROAD - BISHOP ROAD (EAST) | | | | | | | |
| A.A | Road Construction | | | | | | | |
| A.A.A | Road Works | | | | | | | |
| | Earthworks and Site Preparation | | | | \$0 | | | |
| A.A.A.1 | Site Clearance (based on light shrubs) | 37,761 | m2 | \$4 | \$132,919 | | | |
| A.A.A.2 | Removal of topsoil 150mm and stockpile for later re-use | 37,761 | m2 | \$2 | \$60,795 | | | |
| A.A.A.3 | Cut to Fill - General Earthworks | 17,843 | m3 | \$8 | \$146,848 | | | |
| A.A.A.4 | Detailed excavation - mill and profile | 14,161 | m2 | \$19 | \$268,776 | | | |
| A.A.A.5 | Imported Fill | 0 | m3 | \$30 | Excl. | | | |
| A.A.A.6 | Form swale | 7,553 | m2 | \$4 | \$28,626 | | | |
| A.A.A.7 | Subgrade Preparation | | | | \$0 | | | |
| A.A.A.7 | Preparation, trim and compact | 29,786 | m2 | \$6 | \$163,823 | | | |
| A.A.A.8 | Sub Base and Base Course | | | | \$0 | | | |
| A.A.A.8 | 100mm thick crushed rock base course | 32,853 | m2 | \$8 | \$270,052 | | | |
| A.A.A.9 | 250mm thick compacted limestone sub base | 32,853 | m2 | \$17 | \$574,270 | | | |
| A.A.A.10 | Road Paving | | | | \$0 | | | |
| A.A.A.10 | 50mm thick (AC14) | 28,321 | m2 | \$31 | \$884,748 | | | |
| A.A.A.11 | Extra over for 2% red oxide | 5,665 | m2 | \$6 | \$35,293 | | | |
| A.A.A.12 | Primer seal | 28,321 | m2 | \$4 | \$114,417 | | | |
| A.A.A.12 | Kerbing | | | | \$0 | | | |
| A.A.A.13 | Mountable Kerb (MK) | 3,777 | m | \$25 | \$96,087 | | | |
| A.A.A.14 | Kerb openings | 189 | no | \$350 | \$66,150 | | | |
| A.A.A.15 | Semi Mountable Kerb (SMK) | 3,777 | m | \$30 | \$111,988 | | | |
| A.A.A.15 | Line Marking and Furniture | | | | \$0 | | | |
| A.A.A.16 | Line marking | 7,553 | m | \$6 | \$47,886 | | | |
| A.A.A.16 | Landscaping | | | | \$0 | | | |
| A.A.A.17 | Soft landscaping | 10,699 | m2 | \$0 | Excl. | | | |
| A.A.A.18 | Landscape mix | 2,675 | m3 | \$90 | \$240,750 | | | |
| A.A.A.19 | Rock pitching | 630 | m2 | \$155 | \$97,808 | | | |
| A.A.A.20 | Drainage layer | 11,329 | m2 | \$0 | Excl. | | | |
| A.A.A.20 | Other | | | | | | | |
| A.A.A.21 | Allow for connection to existing road | | Item | | \$10,000 | | | |
| A.A.A.21 | TOTAL Road Works | | Item | | | \$3,351,235 | | |
| A.A.B | Shared Paths | | | | | | | |
| | Earthworks and Site Preparation | | | | | | | |
| A.A.B.1 | Site Clearance (based on light shrubs) | 4,721 | m2 | \$4 | \$16,618 | | | |
| A.A.B.2 | Removal of topsoil 150mm and stockpile for later re-use | 4,721 | m2 | \$2 | \$7,601 | | | |
| A.A.B.3 | Cut to Fill - General Earthworks | 1,417 | m3 | \$8 | \$11,662 | | | |
| A.A.B.4 | Imported Fill | 0 | m3 | \$30 | Excl. | | | |
| A.A.B.5 | Subgrade Preparation | | | | | | | |
| A.A.B.5 | Preparation, trim and compact | 4,721 | m2 | \$6 | \$25,966 | | | |
| A.A.B.6 | Pathway | | | | | | | |
| A.A.B.6 | 100 thick concrete footpath with broomed finish | 4,721 | m2 | \$71 | \$334,436 | | | |
| A.A.B.7 | Sand fill below concrete footpath (100mm) | 4,721 | m2 | \$5 | \$25,777 | | | |
| A.A.B.7 | TOTAL Shared Paths | | Item | | | \$422,058 | | |
| A.A.C | Street Lighting | | | | | | | |
| A.A.C.1 | 6.5 SOR Street Light Pole incl. all conduits, light cabling, excavation, and related overheads | 98 | no | \$3,442 | \$337,289 | | | |
| A.A.C.2 | 6.5 DOR Street Light Pole incl. all conduits, light cabling, excavation, and related overheads | 49 | no | \$5,111 | \$250,438 | | | |
| A.A.C.2 | TOTAL Street Lighting | | Item | | | \$587,727 | | |
| A.A.D | Road Drainage | | | | | | | |
| A.A.D.1 | 450dia reinforced concrete pipe including excavation and backfill | 1,709 | m | \$233 | \$398,282 | | | |
| A.A.D.2 | 150dia slotted PVC subsoil drainage pipe including aggregate, geofabric and porous sand | 1,709 | m | \$189 | \$322,317 | | | |

| | | | | | | | |
|--------------|--|---------|------|-------------|---------------------------------------|-------------|--------------------|
| A.A.D.3 | Side entry pits including liner, cover, excavation, and associated works | 0 | no | \$2,667 | CESP measured at intersections, RAB's | | |
| A.A.D.4 | Raised gully / bubble up pits including liner, cover, grate, excavation, rock pitching, and associated works | 57 | no | \$3,021 | \$172,173 | | |
| | TOTAL Road Drainage | | Item | | | \$892,773 | |
| A.A.E | Preliminaries and Project Costs | | | | | | |
| A.A.E.1 | Traffic Management | 5.0000 | % | \$5,253,793 | \$262,690 | | |
| A.A.E.2 | Project Overheads and Preliminaries (Indirect Construction Costs) | 15.0000 | % | \$5,253,793 | \$788,069 | | |
| A.A.E.3 | Project Owner's Cost (Planning and Design Costs) | 7.5000 | % | \$5,253,793 | \$394,034 | | |
| A.A.E.4 | Risk Contingency Allowance | 10.0000 | % | \$6,698,586 | \$669,859 | | |
| | TOTAL Preliminaries and Project Costs | | Item | | | \$2,114,652 | |
| | TOTAL Road Construction | | | | | | \$7,368,444 |
| A.B | Hopkinson Road (T-Junction) | | | | | | |
| A.B.A | Road Works | | | | | | |
| | Earthworks and Site Preparation | | | | \$0 | | |
| A.B.A.1 | Site Clearance (based on light shrubs) | 1,611 | m2 | \$4 | \$5,671 | | |
| A.B.A.2 | Removal of topsoil 150mm and stockpile for later re-use | 1,611 | m2 | \$2 | \$2,594 | | |
| A.B.A.3 | Cut to Fill - General Earthworks | 484 | m3 | \$8 | \$3,983 | | |
| A.B.A.4 | Imported Fill | 0 | m3 | \$30 | \$0 | | |
| A.B.A.5 | Subgrade Preparation | | | | \$0 | | |
| A.B.A.5 | Preparation, trim and compact | 1,611 | m2 | \$6 | \$8,861 | | |
| A.B.A.6 | Sub Base and Base Course | | | | \$0 | | |
| A.B.A.6 | 100mm thick crushed rock base course | 1,563 | m2 | \$8 | \$12,848 | | |
| A.B.A.7 | 250mm thick compacted limestone sub base | 1,563 | m2 | \$17 | \$27,321 | | |
| A.B.A.8 | Road Paving | | | | \$0 | | |
| A.B.A.8 | 50mm thick (AC14) | 1,371 | m2 | \$31 | \$42,830 | | |
| A.B.A.9 | Extra over for 2% red oxide | 180 | m2 | \$6 | \$1,121 | | |
| A.B.A.10 | Primer seal | 1,371 | m2 | \$4 | \$5,539 | | |
| A.B.A.10 | Kerbing | | | | \$0 | | |
| A.B.A.11 | Mountable Kerb (MK) | 24 | m | \$25 | \$611 | | |
| A.B.A.12 | Semi Mountable Kerb (SMK) | 101 | m | \$30 | \$2,995 | | |
| A.B.A.12 | Line Marking and Furniture | | | | \$0 | | |
| A.B.A.13 | Line marking | 140 | m | \$6 | \$888 | | |
| A.B.A.14 | Street sign post | 1 | no | \$122 | \$122 | | |
| A.B.A.15 | Street name plate | 2 | no | \$199 | \$398 | | |
| A.B.A.16 | Chevron sign | 0 | no | \$613 | \$0 | | |
| A.B.A.17 | Traffic sign | 2 | no | \$450 | \$900 | | |
| A.B.A.17 | Landscaping | | | | \$0 | | |
| A.B.A.18 | Mulch to planter boxes (2m x 2m) | 0 | m2 | \$16 | \$0 | | |
| A.B.A.19 | Trees (100l) | 0 | no | \$506 | \$0 | | |
| A.B.A.20 | Soft landscaping | 0 | m2 | \$0 | \$0 | | |
| A.B.A.21 | Landscape mix | 83 | m3 | \$90 | \$7,470 | | |
| A.B.A.22 | Rock pitching | 15 | m2 | \$155 | \$2,329 | | |
| A.B.A.23 | Drainage layer | 0 | m2 | \$0 | \$0 | | |
| A.B.A.23 | Other | | | | \$0 | | |
| A.B.A.24 | Allowed for connection to Hopskins Road | | item | | \$10,000 | | |
| | TOTAL Road Works | | Item | | | \$136,479 | |
| A.B.B | Shared Paths | | | | | | |
| | Earthworks and Site Preparation | | | | | | |
| A.B.B.1 | Site Clearance (based on light shrubs) | 252 | m2 | \$4 | \$887 | | |
| A.B.B.2 | Removal of topsoil 150mm and stockpile for later re-use | 252 | m2 | \$2 | \$406 | | |
| A.B.B.3 | Cut to Fill - General Earthworks | 76 | m3 | \$8 | \$625 | | |
| A.B.B.4 | Detailed excavation - mill and profile | 0 | m3 | \$19 | \$0 | | |
| A.B.B.5 | Imported Fill | 0 | m3 | \$30 | \$0 | | |
| A.B.B.6 | Subgrade Preparation | | | | \$0 | | |
| A.B.B.6 | Preparation, trim and compact | 252 | m2 | \$6 | \$1,386 | | |
| A.B.B.7 | Pathway | | | | \$0 | | |
| A.B.B.7 | 100 thick concrete footpath with broomed finish | 252 | m2 | \$71 | \$17,852 | | |

| | | | | | | | | |
|--------------|--|---------|--------------------|-----------|----------|--|--|------------------|
| A.B.B.8 | Sand fill below concrete footpath (100mm) | 252 | m2 | \$5 | \$1,376 | | | |
| A.B.B.9 | Pram ramp | 0 | no | \$670 | \$0 | | | |
| A.B.B.10 | Pram ramp including tactile Line Marking and Furniture | 2 | no | \$973 | \$1,945 | | | |
| A.B.B.11 | Line marking | 0 | m | \$6 | \$0 | | | |
| A.B.B.12 | Street sign post | 0 | no | \$122 | \$0 | | | |
| A.B.B.13 | Street name plate | 0 | no | \$199 | \$0 | | | |
| A.B.B.14 | Chevron sign | 0 | no | \$613 | \$0 | | | |
| A.B.B.15 | Traffic sign Landscaping | 3 | no | \$450 | \$1,350 | | | |
| A.B.B.16 | Mulch to planter boxes (2m x 2m) | 0 | m2 | \$16 | \$0 | | | |
| A.B.B.17 | Trees (100l) | 0 | no | \$506 | \$0 | | | |
| A.B.B.18 | Soft landscaping TOTAL Shared Paths | 0 | m2 Item | \$0 | \$0 | | | \$25,827 |
| A.B.C | Street Lighting | | | | | | | |
| A.B.C.1 | 6.5 SOR Street Light Pole incl. all conduits, light cabling, excavation, and related overheads TOTAL Street Lighting | 4 | no Item | \$3,442 | \$13,767 | | | \$13,767 |
| A.B.D | Road Drainage | | | | | | | |
| A.B.D.1 | 450dia reinforced concrete pipe including excavation and backfill | 120 | m | \$233 | \$27,966 | | | |
| A.B.D.2 | 150dia slotted PVC subsoil drainage pipe including aggregate, geofabric and porous sand | 0 | m | \$189 | \$0 | | | |
| A.B.D.3 | Side entry pits including liner, cover, excavation, and associated works Drainage layer measured with landscaping TOTAL Road Drainage | 2 | no Note Item | \$2,667 | \$5,333 | | | \$33,299 |
| A.B.E | Preliminaries and Project Costs | | | | | | | |
| A.B.E.1 | Traffic Management | 5.0000 | % | \$209,372 | \$10,469 | | | |
| A.B.E.2 | Project Overheads and Preliminaries (Indirect Construction Costs) | 15.0000 | % | \$209,372 | \$31,406 | | | |
| A.B.E.3 | Project Owner's Cost (Planning and Design Costs) | 7.5000 | % | \$209,372 | \$15,703 | | | |
| A.B.E.4 | Risk Contingency Allowance TOTAL Preliminaries and Project Costs TOTAL Hopkinson Road (T-Junction) | 10.0000 | % Item | \$266,949 | \$26,695 | | | \$84,272 |
| A.C | Taylor Road (T-Junction) | | | | | | | \$293,644 |
| A.C.A | Road Works | | | | | | | |
| A.C.A.1 | Earthworks and Site Preparation Site Clearance (based on light shrubs) Removal of topsoil 150mm and stockpile for later re- use | 1,611 | m2 | \$4 | \$5,671 | | | |
| A.C.A.2 | Cut to Fill - General Earthworks | 1,611 | m2 | \$2 | \$2,594 | | | |
| A.C.A.3 | Imported Fill | 484 | m3 | \$8 | \$3,983 | | | |
| A.C.A.4 | Subgrade Preparation | 0 | m3 | \$30 | \$0 | | | |
| A.C.A.5 | Preparation, trim and compact Sub Base and Base Course | 1,611 | m2 | \$6 | \$8,861 | | | |
| A.C.A.6 | 100mm thick crushed rock base course | 1,563 | m2 | \$8 | \$12,848 | | | |
| A.C.A.7 | 250mm thick compacted limestone sub base Road Paving | 1,563 | m2 | \$17 | \$27,321 | | | |
| A.C.A.8 | 50mm thick (AC14) | 1,371 | m2 | \$31 | \$42,830 | | | |
| A.C.A.9 | Extra over for 2% red oxide | 180 | m2 | \$6 | \$1,121 | | | |
| A.C.A.10 | Primer seal Kerbing | 1,371 | m2 | \$4 | \$5,539 | | | \$0 |
| A.C.A.11 | Mountable Kerb (MK) | 24 | m | \$25 | \$611 | | | |
| A.C.A.12 | Semi Mountable Kerb (SMK) Line Marking and Furniture | 101 | m | \$30 | \$2,995 | | | \$0 |
| A.C.A.13 | Line marking | 140 | m | \$6 | \$888 | | | |
| A.C.A.14 | Street sign post | 1 | no | \$122 | \$122 | | | |
| A.C.A.15 | Street name plate | 2 | no | \$199 | \$398 | | | |
| A.C.A.16 | Chevron sign | 0 | no | \$613 | \$0 | | | |
| A.C.A.17 | Traffic sign | 2 | no | \$450 | \$900 | | | |

| | | | | | | | | |
|--------------|---|---------|--------------|-----------|----------|--|-----------|-----------|
| | Landscaping | | | | \$0 | | | |
| A.C.A.18 | Mulch to planter boxes (2m x 2m) | 0 | m2 | \$16 | \$0 | | | |
| A.C.A.19 | Trees (100l) | 0 | no | \$506 | \$0 | | | |
| A.C.A.20 | Soft landscaping | 0 | m2 | \$0 | \$0 | | | |
| A.C.A.21 | Landscape mix | 83 | m3 | \$90 | \$7,470 | | | |
| A.C.A.22 | Rock pitching | 15 | m2 | \$155 | \$2,329 | | | |
| A.C.A.23 | Drainage layer Other | 0 | m2 | \$0 | \$0 | | | |
| A.C.A.24 | Allowed for connection to Taylor Road TOTAL Road Works | | item Item | | \$10,000 | | \$136,479 | |
| A.C.B | Shared Paths | | | | | | | |
| | Earthworks and Site Preparation | | | | | | | |
| A.C.B.1 | Site Clearance (based on light shrubs) Removal of topsoil 150mm and stockpile for later re-use | 252 | m2 | \$4 | \$887 | | | |
| A.C.B.2 | Cut to Fill - General Earthworks | 252 | m2 | \$2 | \$406 | | | |
| A.C.B.3 | Detailed excavation - mill and profile | 76 | m3 | \$8 | \$625 | | | |
| A.C.B.4 | Imported Fill | 0 | m3 | \$19 | \$0 | | | |
| A.C.B.5 | Subgrade Preparation | 0 | m3 | \$30 | \$0 | | | |
| A.C.B.6 | Preparation, trim and compact Pathway | 252 | m2 | \$6 | \$1,386 | | | |
| A.C.B.7 | 100 thick concrete footpath with broomed finish | 252 | m2 | \$71 | \$17,852 | | | |
| A.C.B.8 | Sand fill below concrete footpath (100mm) | 252 | m2 | \$5 | \$1,376 | | | |
| A.C.B.9 | Pram ramp | 0 | no | \$670 | \$0 | | | |
| A.C.B.10 | Pram ramp including tactile Line Marking and Furniture | 2 | no | \$973 | \$1,945 | | | |
| A.C.B.11 | Line marking | 0 | m | \$6 | \$0 | | | |
| A.C.B.12 | Street sign post | 0 | no | \$122 | \$0 | | | |
| A.C.B.13 | Street name plate | 0 | no | \$199 | \$0 | | | |
| A.C.B.14 | Chevron sign | 0 | no | \$613 | \$0 | | | |
| A.C.B.15 | Traffic sign Landscaping | 3 | no | \$450 | \$1,350 | | | |
| A.C.B.16 | Mulch to planter boxes (2m x 2m) | 0 | m2 | \$16 | \$0 | | | |
| A.C.B.17 | Trees (100l) | 0 | no | \$506 | \$0 | | | |
| A.C.B.18 | Soft landscaping TOTAL Shared Paths | 0 | m2 Item | \$0 | \$0 | | \$25,827 | |
| A.C.C | Street Lighting | | | | | | | |
| | 6.5 SOR Street Light Pole incl. all conduits, light cabling, excavation, and related overheads | 4 | no | \$3,442 | \$13,767 | | | |
| A.C.C.1 | TOTAL Street Lighting | | Item | | | | \$13,767 | |
| A.C.D | Road Drainage | | | | | | | |
| | 450dia reinforced concrete pipe including excavation and backfill | 120 | m | \$233 | \$27,966 | | | |
| A.C.D.1 | 150dia slotted PVC subsoil drainage pipe including aggregate, geofabric and porous sand | 0 | m | \$189 | \$0 | | | |
| A.C.D.2 | Side entry pits including liner, cover, excavation, and associated works | 2 | no | \$2,667 | \$5,333 | | | |
| A.C.D.3 | Drainage layer measured with landscaping TOTAL Road Drainage | | Note Item | | | | \$33,299 | |
| A.C.E | Preliminaries and Project Costs | | | | | | | |
| | Traffic Management | 5.0000 | % | \$209,372 | \$10,469 | | | |
| A.C.E.1 | Project Overheads and Preliminaries (Indirect Construction Costs) | 15.0000 | % | \$209,372 | \$31,406 | | | |
| A.C.E.2 | Project Owner's Cost (Planning and Design Costs) | 7.5000 | % | \$209,372 | \$15,703 | | | |
| A.C.E.3 | Risk Contingency Allowance | 10.0000 | % | \$266,949 | \$26,695 | | | |
| A.C.E.4 | TOTAL Preliminaries and Project Costs TOTAL Taylor Road (T-Junction) | | Item | | | | \$84,272 | \$293,644 |
| A.D | Bett Road (Roundabout) | | | | | | | |
| A.D.A | Road Works | | | | | | | |
| | Earthworks and Site Preparation | | | | | | | |
| A.D.A.1 | Site Clearance (based on light shrubs) | 2,504 | m2 | \$4 | \$8,814 | | | |

| | | | | | | | |
|--------------|--|--------|------------|--------------|----------------|-----------|--|
| A.D.A.2 | Removal of topsoil 150mm and stockpile for later re-use | 2,504 | m2 | \$2 | \$4,031 | | |
| A.D.A.3 | Cut to Fill - General Earthworks | 752 | m3 | \$8 | \$6,189 | | |
| A.D.A.4 | Imported Fill | 0 | m3 | \$30 | Excl. | | |
| A.D.A.5 | Subgrade Preparation Preparation, trim and compact Sub Base and Base Course | 2,504 | m2 | \$6 | \$13,772 | | |
| A.D.A.6 | 100mm thick crushed rock base course | 1,983 | m2 | \$8 | \$16,300 | | |
| A.D.A.7 | 250mm thick compacted limestone sub base Road Paving | 1,983 | m2 | \$17 | \$34,663 | | |
| A.D.A.8 | 50mm thick (AC14) | 1,518 | m2 | \$31 | \$47,422 | | |
| A.D.A.9 | Primer seal Brick Paving | 1,518 | m2 Item | \$4 \$0 | \$6,133 \$0 | | |
| A.D.A.10 | 80 thick brick pavers | 333 | m2 | \$100 | \$33,333 | | |
| A.D.A.11 | 30 thick compacted sand bed | 180 | m2 | \$2 | \$295 | | |
| A.D.A.12 | 40 thick compacted sand bed (RAB) | 153 | m2 | \$2 | \$335 | | |
| A.D.A.13 | 170mm thick compacted limestone | 180 | m2 | \$11 | \$2,047 | | |
| A.D.A.14 | 250mm thick compacted limestone sub base Kerbing | 153 | m2 | \$17 | \$2,674 | | |
| A.D.A.15 | Mountable Kerb (MK) | 70 | m | \$25 | \$1,781 | | |
| A.D.A.16 | Semi Mountable Kerb (SMK) | 143 | m | \$30 | \$4,240 | | |
| A.D.A.17 | Barrier Kerb (BK) Line Marking and Furniture | 54 | m | \$53 | \$2,869 | | |
| A.D.A.18 | Line marking | 53 | m | \$6 | \$336 | | |
| A.D.A.19 | Street sign post | 1 | no | \$122 | \$122 | | |
| A.D.A.20 | Street name plate | 2 | no | \$199 | \$398 | | |
| A.D.A.21 | Chevron sign | 1 | no | \$613 | \$613 | | |
| A.D.A.22 | Traffic sign Landscaping | 3 | no | \$450 | \$1,350 \$0 | | |
| A.D.A.23 | Soft landscaping | 227 | m2 | \$0 | Excl. | | |
| A.D.A.24 | Landscape mix TOTAL Road Works | 57 | m3 Item | \$90 | \$5,130 | \$192,847 | |
| <u>A.D.B</u> | <u>Shared Paths</u> | | | | | | |
| A.D.B.1 | Earthworks and Site Preparation Site Clearance (based on light shrubs) Removal of topsoil 150mm and stockpile for later re-use | 356 | m2 | \$4 | \$1,253 | | |
| A.D.B.2 | Cut to Fill - General Earthworks | 107 | m3 | \$8 | \$881 | | |
| A.D.B.3 | Imported Fill | 178 | m3 | \$30 | \$5,340 | | |
| A.D.B.4 | Subgrade Preparation Preparation, trim and compact Pathway | 356 | m2 | \$6 | \$1,958 | | |
| A.D.B.5 | 100 thick concrete footpath with broomed finish | 356 | m2 | \$71 | \$25,219 | | |
| A.D.B.6 | Sand fill below concrete path (100mm) Pram ramp | 356 | m2 no | \$5 \$670 | \$1,944 | | |
| A.D.B.7 | Pram ramp including tactile | 6 | no | \$973 | \$5,836 | | |
| A.D.B.8 | Tactile paving Line Marking and Furniture | 10 | m2 | \$325 | \$3,250 | | |
| A.D.B.9 | Traffic sign Landscaping TOTAL Shared Paths | 2 | no Item | \$450 | \$900 | \$47,154 | |
| <u>A.D.C</u> | <u>Street Lighting</u> | | | | | | |
| A.D.C.1 | 6.5 SOR Street Light Pole incl. all conduits, light cabling, excavation, and related overheads TOTAL Street Lighting | 4 | no Item | \$3,442 | \$13,767 | \$13,767 | |
| <u>A.D.D</u> | <u>Road Drainage</u> | | | | | | |
| A.D.D.1 | 450dia reinforced concrete pipe including excavation and backfill | 130 | m | \$233 | \$30,297 | | |
| A.D.D.2 | Side entry pits including liner, cover, excavation, and associated works TOTAL Road Drainage | 4 | no Item | \$2,667 | \$10,666 | \$40,963 | |
| <u>A.D.E</u> | <u>Preliminaries and Project Costs</u> | | | | | | |
| A.D.E.1 | Traffic Management | 5.0000 | % | \$294,730 | \$14,737 | | |

| | | | | | | | |
|--------------|---|---------|------|---|-------------|-------------|---------------------|
| A.D.E.2 | Project Overheads and Preliminaries (Indirect Construction Costs) | 15.0000 | % | \$294,730 | \$44,210 | | |
| A.D.E.3 | Project Owner's Cost (Planning and Design Costs) | 7.5000 | % | \$294,730 | \$22,105 | | |
| A.D.E.4 | Risk Contingency Allowance | 10.0000 | % | \$375,781 | \$37,578 | | |
| | TOTAL Preliminaries and Project Costs | | Item | | | \$118,629 | |
| | TOTAL Bett Road (Roundabout) | | | | | | \$413,359 |
| A.E | Utilities | | | | | | |
| A.E.A | Power and Lighting (Western Power) | | | | | | |
| A.E.A.1 | Relocate 1120m of Overhead Power underground - Provisional Sum | 1 | PS | \$1,777,985 | \$1,777,985 | | |
| | TOTAL Power and Lighting (Western Power) | | Item | | | \$1,777,985 | |
| A.E.B | Communications (NBN / Telstra / Westnet / etc.) | | | | | | |
| A.E.B.1 | Relocate 1120m road length of communications related infrastructure about 20m from the current location - Provisional Sum | 1 | PS | \$352,692 | \$352,692 | | |
| | TOTAL Communications (NBN / Telstra / Westnet / etc.) | | Item | | | \$352,692 | |
| A.E.C | Water and Sewer (Water Corporation) | | | | | | |
| | No allowance has been made for Water Corporation diversions as we do not see existing mains from our desktop study | | Note | | | | |
| | TOTAL Water and Sewer (Water Corporation) | | Item | | | \$0 | |
| A.E.D | Gas (ATCO) | | | | | | |
| | No allowance has been made for ATCO diversions as we do not see existing valves from our desktop study | | Note | | | | |
| | TOTAL Gas (ATCO) | | Item | | | \$0 | |
| A.E.E | Preliminaries and Project Costs | | | | | | |
| A.E.E.1 | Traffic Management | 10.0000 | % | \$2,130,677 | \$213,068 | | |
| A.E.E.2 | Project Overheads and Preliminaries (Indirect Construction Costs) | 15.0000 | % | \$2,130,677 | \$319,602 | | |
| A.E.E.3 | Project Owner's Cost (Planning and Design Costs) | 5.0000 | % | \$2,130,677 | \$106,534 | | |
| A.E.E.4 | Risk Contingency Allowance | 10.0000 | % | \$2,769,880 | \$276,988 | | |
| | TOTAL Preliminaries and Project Costs | | Item | | | \$916,191 | |
| | TOTAL Utilities | | | | | | \$3,046,868 |
| A.A.A.7 | Estimated Imported Fill | 6,750 | m3 | | | | |
| A.A.A.5 | Total m3 of Cut to Fill - General Earthworks | 21,239 | m3 | | | | |
| | Less Cut to Fill costed | 0 | m3 | \$30 | \$0 | | |
| | Total Adjustment for Imported Fill (less Cut to Fill) | | | See "Imported Fill" sheet at the end of these costings. | | | \$0 |
| | TOTAL Road - Bishop Road (East) | | Item | | | | \$11,415,959 |

**Shire of Serpentine Jarrahdale DCP
 DCA 3 - Mundijong Whitby - Update**

| Code | Description | Quantity | UOM | Rate | Subtotal | Sub Section Total | Section Total | Road/ DOS Total |
|---------------------|--|----------|------|---------|-----------------------------|-------------------|---------------|-----------------|
| B | ROAD - TAYLOR ROAD | | | | | | | |
| <u>B.A</u> | <u>Road Construction</u> | | | | | | | |
| <u>B.A.A</u> | <u>Road Works</u> | | | | | | | |
| | Earthworks and Site Preparation | | | | \$0 | | | |
| B.A.A.1 | Site Clearance (based on light shrubs) | 25,275 | m2 | \$4 | \$88,968 | | | |
| | Removal of topsoil 150mm and stockpile for later re-use | | | | | | | |
| B.A.A.2 | | 25,275 | m2 | \$2 | \$40,693 | | | |
| B.A.A.3 | Cut to Fill - General Earthworks | 12,566 | m3 | \$8 | \$103,418 | | | |
| B.A.A.4 | Detailed excavation - mill and profile | 10,833 | m2 | \$19 | \$205,610 | | | |
| B.A.A.5 | Imported Fill | 0 | m3 | \$30 | Excl. | | | |
| B.A.A.6 | Form swale | 5,778 | m2 | \$4 | \$21,899 | | | |
| | Subgrade Preparation | | | | \$0 | | | |
| B.A.A.7 | Preparation, trim and compact Sub Base and Base Course | 36,107 | m2 | \$6 | \$198,589 | | | |
| | | | | | \$0 | | | |
| B.A.A.8 | 100mm thick crushed rock base course | 25,131 | m2 | \$8 | \$206,577 | | | |
| B.A.A.9 | 250mm thick compacted limestone sub base | 25,131 | m2 | \$17 | \$439,290 | | | |
| | Road Paving | | | | \$0 | | | |
| B.A.A.10 | 50mm thick (AC14) | 21,665 | m2 | \$31 | \$676,815 | | | |
| B.A.A.11 | Extra over for 2% red oxide | 4,333 | m2 | \$6 | \$26,995 | | | |
| B.A.A.12 | Primer seal | 21,665 | m2 | \$4 | \$87,527 | | | |
| | Kerbing | | | | \$0 | | | |
| B.A.A.13 | Mountable Kerb (MK) | 2,889 | m | \$25 | \$73,496 | | | |
| B.A.A.14 | Kerb openings | 145 | no | \$350 | \$50,750 | | | |
| B.A.A.15 | Semi Mountable Kerb (SMK) | 2,889 | m | \$30 | \$85,659 | | | |
| | Line Marking and Furniture | | | | \$0 | | | |
| B.A.A.16 | Line marking | 5,778 | m | \$6 | \$36,633 | | | |
| | Landscaping | | | | \$0 | | | |
| B.A.A.17 | Soft landscaping | 8,184 | m2 | \$0 | Excl. | | | |
| B.A.A.18 | Landscape mix | 2,046 | m3 | \$90 | \$184,140 | | | |
| B.A.A.19 | Rock pitching | 482 | m2 | \$155 | \$74,831 | | | |
| B.A.A.20 | Drainage layer | 8,666 | m2 | \$0 | Excl. | | | |
| | TOTAL Road Works | | Item | | | \$2,601,887 | | |
| <u>B.A.B</u> | <u>Shared Paths</u> | | | | | | | |
| | Earthworks and Site Preparation | | | | | | | |
| B.A.B.1 | Site Clearance (based on light shrubs) | 9,441 | m2 | \$4 | \$33,232 | | | |
| | Removal of topsoil 150mm and stockpile for later re-use | | | | | | | |
| B.A.B.2 | | 9,441 | m2 | \$2 | \$15,200 | | | |
| B.A.B.3 | Cut to Fill - General Earthworks | 2,833 | m3 | \$8 | \$23,316 | | | |
| B.A.B.4 | Imported Fill | 0 | m3 | \$30 | Excl. | | | |
| | Subgrade Preparation | | | | | | | |
| B.A.B.5 | Preparation, trim and compact Pathway | 9,441 | m2 | \$6 | \$51,926 | | | |
| B.A.B.6 | 100 thick concrete footpath with broomed finish | 9,441 | m2 | \$71 | \$668,800 | | | |
| B.A.B.7 | Sand fill below concrete footpath (100mm) | 9,441 | m2 | \$5 | \$51,548 | | | |
| B.A.B.8 | Pram ramp | | no | \$670 | Included with intersections | | | |
| | TOTAL Shared Paths | | Item | | | \$844,022 | | |
| <u>B.A.C</u> | <u>Street Lighting</u> | | | | | | | |
| B.A.C.1 | 6.5 SOR Street Light Pole incl. all conduits, light cabling, excavation, and related overheads | 83 | no | \$3,442 | \$285,663 | | | |
| B.A.C.2 | 6.5 DOR Street Light Pole incl. all conduits, light cabling, excavation, and related overheads | 42 | no | \$5,111 | \$214,661 | | | |
| | TOTAL Street Lighting | | Item | | | \$500,324 | | |

**Shire of Serpentine Jarrahdale DCP
 DCA 3 - Mundijong Whitby - Update**

| Code | Description | Quantity | UOM | Rate | Subtotal | Sub Section Total | Section Total | Road/ DOS Total |
|--------------|--|----------|------|---------|-------------|-------------------|---------------|-----------------|
| C | ROAD – TOWN CENTRE DISTRIBUTOR RD (NEW WHITBY ROAD) | | | | | | | |
| C.A | Road Construction | | | | | | | |
| C.A.A | Road Works | | | | | | | |
| | Earthworks and Site Preparation | | | | \$0 | | | |
| C.A.A.1 | Site Clearance (based on light shrubs) | 83,385 | m2 | \$4 | \$293,515 | | | |
| C.A.A.2 | Removal of topsoil 150mm and stockpile for later re-use | 83,385 | m2 | \$2 | \$134,250 | | | |
| C.A.A.3 | Cut to Fill - General Earthworks | 29,018 | m3 | \$8 | \$238,818 | | | |
| C.A.A.4 | Imported Fill | 0 | m3 | \$30 | Excl. | | | |
| C.A.A.5 | Form swale | 13,342 | m2 | \$4 | \$50,566 | | | |
| | Subgrade Preparation | | | | | | | |
| C.A.A.6 | Preparation, trim and compact Sub Base and Base Course | 83,385 | m2 | \$6 | \$458,618 | | | |
| C.A.A.7 | 100mm thick crushed rock base course | 58,036 | m2 | \$8 | \$477,056 | | | |
| C.A.A.8 | 250mm thick compacted limestone sub base | 58,036 | m2 | \$17 | \$1,014,469 | | | |
| | Road Paving | | | | \$0 | | | |
| C.A.A.9 | 50mm thick (AC14) | 50,031 | m2 | \$31 | \$1,562,968 | | | |
| C.A.A.10 | Extra over for 2% red oxide | 10,007 | m2 | \$6 | \$62,344 | | | |
| C.A.A.11 | Primer seal | 50,031 | m2 | \$4 | \$202,125 | | | |
| | Kerbing | | | | \$0 | | | |
| C.A.A.12 | Mountable Kerb (MK) | 6,671 | m | \$25 | \$169,710 | | | |
| C.A.A.13 | Kerb openings | 334 | no | \$350 | \$116,900 | | | |
| C.A.A.14 | Semi Mountable Kerb (SMK) | 6,671 | m | \$30 | \$197,795 | | | |
| C.A.A.15 | Concrete flush edge beam | | m | \$67 | \$0 | | | |
| | Line Marking and Furniture | | | | \$0 | | | |
| C.A.A.16 | Line marking | 13,342 | m | \$6 | \$84,588 | | | |
| | Landscaping | | | | \$0 | | | |
| C.A.A.17 | Soft landscaping | 18,881 | m2 | \$0 | Excl. | | | |
| C.A.A.18 | Landscape mix | 4,721 | m3 | \$90 | \$424,890 | | | |
| C.A.A.19 | Rock pitching | 1,112 | m2 | \$155 | \$172,638 | | | |
| C.A.A.20 | Drainage layer | 20,013 | m2 | \$0 | Excl. | | | |
| | TOTAL Road Works | | Item | | | \$5,661,251 | | |
| C.A.B | Shared Paths | | | | | | | |
| | Earthworks and Site Preparation | | | | | | | |
| C.A.B.1 | Site Clearance (based on light shrubs) | 16,677 | m2 | \$4 | \$58,703 | | | |
| C.A.B.2 | Removal of topsoil 150mm and stockpile for later re-use | 16,677 | m2 | \$2 | \$26,850 | | | |
| C.A.B.3 | Cut to Fill - General Earthworks | 5,004 | m3 | \$8 | \$41,183 | | | |
| C.A.B.4 | Imported Fill | 0 | m3 | \$30 | Excl. | | | |
| | Subgrade Preparation | | | | | | | |
| C.A.B.5 | Preparation, trim and compact Pathway | 16,677 | m2 | \$6 | \$91,724 | | | |
| C.A.B.6 | 100 thick concrete footpath with broomed finish | 16,677 | m2 | \$71 | \$1,181,399 | | | |
| C.A.B.7 | Sand fill below concrete footpath (100mm) | 16,677 | m2 | \$5 | \$91,056 | | | |
| | TOTAL Shared Paths | | Item | | | \$1,490,915 | | |
| C.A.C | Street Lighting | | | | | | | |
| C.A.C.1 | 6.5 SOR Street Light Pole incl. all conduits, light cabling, excavation, and related overheads | 188 | no | \$3,442 | \$647,043 | | | |
| C.A.C.2 | 6.5 DOR Street Light Pole incl. all conduits, light cabling, excavation, and related overheads | 94 | no | \$5,111 | \$480,432 | | | |
| | TOTAL Street Lighting | | Item | | | \$1,127,475 | | |
| C.A.D | Road Drainage | | | | | | | |
| C.A.D.1 | 450dia reinforced concrete pipe including excavation and backfill | 3,276 | m | \$233 | \$763,472 | | | |
| C.A.D.2 | 150dia slotted PVC subsoil drainage pipe including aggregate, geofabric and porous sand | 3,276 | m | \$189 | \$617,854 | | | |

| | | | | | | | |
|--------------|--|---------|------|--------------|-------------|-------------|---------------------|
| C.A.D.3 | Raised gully / bubble up pits including liner, cover, grate, excavation, rock pitching, and associated works | 110 | no | \$3,021 | \$332,264 | | |
| C.A.D.4 | 2500x800mm box culvert incl. headwall, excavation, backfill, etc. | 30 | m | \$4,203 | \$126,103 | | |
| C.A.D.5 | Remove existing culvert in preparation for new culvert (approximatley 3m wide) | 1 | LS | \$4,210 | \$4,210 | | |
| | TOTAL Road Drainage | | Item | | | \$1,843,902 | |
| C.A.E | Preliminaries and Project Costs | | | | | | |
| C.A.E.1 | Traffic Management | 5.0000 | % | \$10,123,543 | \$506,177 | | |
| C.A.E.2 | Project Overheads and Preliminaries (Indirect Construction Costs) | 15.0000 | % | \$10,123,543 | \$1,518,532 | | |
| C.A.E.3 | Project Owner's Cost (Planning and Design Costs) | 7.5000 | % | \$10,123,543 | \$759,266 | | |
| C.A.E.4 | Risk Contingency Allowance | 10.0000 | % | \$12,907,518 | \$1,290,752 | | |
| | TOTAL Preliminaries and Project Costs | | Item | | | \$4,074,726 | |
| | TOTAL Road Construction | | | | | | \$14,198,270 |
| C.B | Taylor Road (Roundabout) | | | | | | |
| C.B.A | Road Works | | | | | | |
| | Earthworks and Site Preparation | | | | | | |
| C.B.A.1 | Site Clearance (based on light shrubs) | 2,504 | m2 | \$4 | \$8,814 | | |
| C.B.A.2 | Removal of topsoil 150mm and stockpile for later re-use | 2,504 | m2 | \$2 | \$4,031 | | |
| C.B.A.3 | Cut to Fill - General Earthworks | 752 | m3 | \$8 | \$6,189 | | |
| C.B.A.4 | Imported Fill | 0 | m3 | \$30 | Excl. | | |
| | Subgrade Preparation | | | | | | |
| C.B.A.5 | Preparation, trim and compact Sub Base and Base Course | 2,504 | m2 | \$6 | \$13,772 | | |
| C.B.A.6 | 100mm thick crushed rock base course | 1,983 | m2 | \$8 | \$16,300 | | |
| C.B.A.7 | 250mm thick compacted limestone sub base | 1,983 | m2 | \$17 | \$34,663 | | |
| | Road Paving | | | | | | |
| C.B.A.8 | 50mm thick (AC14) | 1,518 | m2 | \$31 | \$47,422 | | |
| C.B.A.9 | Primer seal | 1,518 | m2 | \$4 | \$6,133 | | |
| | Brick Paving | | Item | | \$0 | | |
| C.B.A.10 | 80 thick brick pavers | 333 | m2 | \$100 | \$33,333 | | |
| C.B.A.11 | 30 thick compacted sand bed | 180 | m2 | \$2 | \$295 | | |
| C.B.A.12 | 40 thick compacted sand bed (RAB) | 153 | m2 | \$2 | \$335 | | |
| C.B.A.13 | 170mm thick compacted limestone | 180 | m2 | \$11 | \$2,047 | | |
| C.B.A.14 | 250mm thick compacted limestone sub base | 153 | m2 | \$17 | \$2,674 | | |
| | Kerbing | | | | | | |
| C.B.A.15 | Mountable Kerb (MK) | 70 | m | \$25 | \$1,781 | | |
| C.B.A.16 | Semi Mountable Kerb (SMK) | 143 | m | \$30 | \$4,240 | | |
| C.B.A.17 | Barrier Kerb (BK) | 54 | m | \$53 | \$2,869 | | |
| | Line Marking and Furniture | | | | | | |
| C.B.A.18 | Line marking | 53 | m | \$6 | \$336 | | |
| C.B.A.19 | Street sign post | 1 | no | \$122 | \$122 | | |
| C.B.A.20 | Street name plate | 2 | no | \$199 | \$398 | | |
| C.B.A.21 | Chevron sign | 1 | no | \$613 | \$613 | | |
| C.B.A.22 | Traffic sign | 3 | no | \$450 | \$1,350 | | |
| | Landscaping | | | | \$0 | | |
| C.B.A.23 | Soft landscaping | 227 | m2 | \$0 | Excl. | | |
| C.B.A.24 | Landscape mix | 57 | m3 | \$90 | \$5,130 | | |
| | TOTAL Road Works | | Item | | | \$192,847 | |
| C.B.B | Shared Paths | | | | | | |
| | Earthworks and Site Preparation | | | | | | |
| C.B.B.1 | Site Clearance (based on light shrubs) | 356 | m2 | \$4 | \$1,253 | | |
| C.B.B.2 | Removal of topsoil 150mm and stockpile for later re-use | 356 | m2 | \$2 | \$573 | | |
| C.B.B.3 | Cut to Fill - General Earthworks | 107 | m3 | \$8 | \$881 | | |
| C.B.B.4 | Imported Fill | 0 | m3 | \$30 | Excl. | | |
| | Subgrade Preparation | | | | | | |
| C.B.B.5 | Preparation, trim and compact Pathway | 356 | m2 | \$6 | \$1,958 | | |

| | | | | | | | | |
|--------------|--|---------|------|-----------|----------|-----------|------------------|--|
| C.B.B.6 | 100 thick concrete footpath with broomed finish | 356 | m2 | \$71 | \$25,219 | | | |
| C.B.B.7 | Sand fill below concrete path (100mm) | 356 | m2 | \$5 | \$1,944 | | | |
| C.B.B.8 | Pram ramp including tactile | 6 | no | \$973 | \$5,836 | | | |
| C.B.B.9 | Tactile paving | 10 | m2 | \$325 | \$3,250 | | | |
| | Line Marking and Furniture | | | | | | | |
| C.B.B.10 | Traffic sign | 2 | no | \$450 | \$900 | | | |
| | TOTAL Shared Paths | | Item | | | \$41,814 | | |
| C.B.C | Street Lighting | | | | | | | |
| C.B.C.1 | 6.5 SOR Street Light Pole incl. all conduits, light cabling, excavation, and related overheads | 4 | no | \$3,442 | \$13,767 | | | |
| | TOTAL Street Lighting | | Item | | | \$13,767 | | |
| C.B.D | Road Drainage | | | | | | | |
| C.B.D.1 | 450dia reinforced concrete pipe including excavation and backfill | 130 | m | \$233 | \$30,297 | | | |
| C.B.D.2 | Side entry pits including liner, cover, excavation, and associated works | 4 | no | \$2,667 | \$10,666 | | | |
| | TOTAL Road Drainage | | Item | | | \$40,963 | | |
| C.B.E | Preliminaries and Project Costs | | | | | | | |
| C.B.E.1 | Traffic Management | 5.0000 | % | \$289,390 | \$14,470 | | | |
| C.B.E.2 | Project Overheads and Preliminaries (Indirect Construction Costs) | 15.0000 | % | \$289,390 | \$43,409 | | | |
| C.B.E.3 | Project Owner's Cost (Planning and Design Costs) | 7.5000 | % | \$289,390 | \$21,704 | | | |
| C.B.E.4 | Risk Contingency Allowance | 10.0000 | % | \$368,973 | \$36,897 | | | |
| | TOTAL Preliminaries and Project Costs | | Item | | | \$116,480 | | |
| | TOTAL Taylor Road (Roundabout) | | | | | | \$405,870 | |
| C.C | Soldiers Road (Roundabout) | | | | | | | |
| C.C.A | Road Works | | | | | | | |
| | Earthworks and Site Preparation | | | | | | | |
| C.C.A.1 | Site Clearance (based on light shrubs) | 2,728 | m2 | \$4 | \$9,603 | | | |
| C.C.A.2 | Removal of topsoil 150mm and stockpile for later re-use | 2,728 | m2 | \$2 | \$4,392 | | | |
| C.C.A.3 | Cut to Fill - General Earthworks | 819 | m3 | \$8 | \$6,740 | | | |
| C.C.A.4 | Imported Fill | 0 | m3 | \$30 | Excl. | | | |
| | Subgrade Preparation | | | | | | | |
| C.C.A.5 | Preparation, trim and compact Sub Base and Base Course | 2,728 | m2 | \$6 | \$15,004 | | | |
| C.C.A.6 | 100mm thick crushed rock base course | 2,139 | m2 | \$8 | \$17,583 | | | |
| C.C.A.7 | 250mm thick compacted limestone sub base | 2,139 | m2 | \$17 | \$37,390 | | | |
| | Road Paving | | | | | | | |
| C.C.A.8 | 50mm thick (AC14) | 1,672 | m2 | \$31 | \$52,233 | | | |
| C.C.A.9 | Primer seal | 1,672 | m2 | \$4 | \$6,755 | | | |
| | Brick Paving | | Item | | \$0 | | | |
| C.C.A.10 | 80 thick brick pavers | 393 | m2 | \$100 | \$39,339 | | | |
| C.C.A.11 | 30 thick compacted sand bed | 240 | m2 | \$2 | \$394 | | | |
| C.C.A.12 | 40 thick compacted sand bed (RAB) | 153 | m2 | \$2 | \$335 | | | |
| C.C.A.13 | 170mm thick compacted limestone | 240 | m2 | \$11 | \$2,729 | | | |
| C.C.A.14 | 250mm thick compacted limestone sub base | 153 | m2 | \$17 | \$2,674 | | | |
| | Kerbing | | | | | | | |
| C.C.A.15 | Mountable Kerb (MK) | 70 | m | \$25 | \$1,781 | | | |
| C.C.A.16 | Semi Mountable Kerb (SMK) | 146 | m | \$30 | \$4,329 | | | |
| C.C.A.17 | Barrier Kerb (BK) | 54 | m | \$53 | \$2,869 | | | |
| | Line Marking and Furniture | | | | | | | |
| C.C.A.18 | Line marking | 70 | m | \$6 | \$444 | | | |
| C.C.A.19 | Street sign post | 1 | no | \$122 | \$122 | | | |
| C.C.A.20 | Street name plate | 2 | no | \$199 | \$398 | | | |
| C.C.A.21 | Traffic sign | 4 | no | \$450 | \$1,800 | | | |
| | Landscaping | | | | \$0 | | | |
| C.C.A.22 | Soft landscaping | 227 | m2 | \$0 | Excl. | | | |
| C.C.A.23 | Landscape mix | 57 | m3 | \$90 | \$5,130 | | | |
| | Other | | | | | | | |

| | | | | | | | | |
|--------------|--|---------|------|-----------|----------|-----------|------------------|--|
| C.C.A.24 | Allow for connection to Soldiers Road (both directions) | | Item | | \$20,000 | | | |
| | TOTAL Road Works | | Item | | | \$232,043 | | |
| <u>C.C.B</u> | <u>Shared Paths</u> | | | | | | | |
| | Earthworks and Site Preparation | | | | | | | |
| C.C.B.1 | Site Clearance (based on light shrubs) | 364 | m2 | \$4 | \$1,281 | | | |
| C.C.B.2 | Removal of topsoil 150mm and stockpile for later re-use | 364 | m2 | \$2 | \$586 | | | |
| C.C.B.3 | Cut to Fill - General Earthworks | 110 | m3 | \$8 | \$905 | | | |
| C.C.B.4 | Imported Fill | 0 | m3 | \$30 | Excl. | | | |
| | Subgrade Preparation | | | | | | | |
| C.C.B.5 | Preparation, trim and compact Pathway | 364 | m2 | \$6 | \$2,002 | | | |
| C.C.B.6 | 100 thick concrete footpath with broomed finish | 364 | m2 | \$71 | \$25,786 | | | |
| C.C.B.7 | Sand fill below concrete path (100mm) | 364 | m2 | \$5 | \$1,987 | | | |
| C.C.B.8 | Pram ramp including tactile | 8 | no | \$973 | \$7,781 | | | |
| C.C.B.9 | Tactile paving | 13 | m2 | \$325 | \$4,225 | | | |
| | Line Marking and Furniture | | | | | | | |
| C.C.B.10 | Traffic sign | 4 | no | \$450 | \$1,800 | | | |
| | TOTAL Shared Paths | | Item | | | \$46,354 | | |
| <u>C.C.C</u> | <u>Street Lighting</u> | | | | | | | |
| | 6.5 SOR Street Light Pole incl. all conduits, light cabling, excavation, and related overheads | 4 | no | \$3,442 | \$13,767 | | | |
| C.C.C.1 | TOTAL Street Lighting | | Item | | | \$13,767 | | |
| <u>C.C.D</u> | <u>Road Drainage</u> | | | | | | | |
| | 450dia reinforced concrete pipe including excavation and backfill | 130 | m | \$233 | \$30,297 | | | |
| C.C.D.1 | Side entry pits including liner, cover, excavation, and associated works | 4 | no | \$2,667 | \$10,666 | | | |
| C.C.D.2 | TOTAL Road Drainage | | Item | | | \$40,963 | | |
| <u>C.C.E</u> | <u>Preliminaries and Project Costs</u> | | | | | | | |
| C.C.E.1 | Traffic Management | 5.0000 | % | \$333,126 | \$16,656 | | | |
| C.C.E.2 | Project Overheads and Preliminaries (Indirect Construction Costs) | 15.0000 | % | \$333,126 | \$49,969 | | | |
| C.C.E.3 | Project Owner's Cost (Planning and Design Costs) | 7.5000 | % | \$333,126 | \$24,984 | | | |
| C.C.E.4 | Risk Contingency Allowance | 10.0000 | % | \$424,736 | \$42,474 | | | |
| | TOTAL Preliminaries and Project Costs | | Item | | | \$134,083 | | |
| | TOTAL Soldiers Road (Roundabout) | | | | | | \$467,210 | |
| <u>C.D</u> | <u>South Western Highway (Channelised Intersection)</u> | | | | | | | |
| <u>C.D.A</u> | <u>Road Works</u> | | | | | | | |
| | Earthworks and Site Preparation | | | | \$0 | | | |
| C.D.A.1 | Site Clearance (based on light shrubs) | 2,550 | m2 | \$4 | \$8,976 | | | |
| C.D.A.2 | Removal of topsoil 150mm and stockpile for later re-use | 2,550 | m2 | \$2 | \$4,106 | | | |
| C.D.A.3 | Cut to Fill - General Earthworks | 765 | m3 | \$8 | \$6,296 | | | |
| C.D.A.4 | Detailed excavation - mill and profile | 1,800 | m2 | \$19 | \$34,164 | | | |
| C.D.A.5 | Imported Fill | 0 | m3 | \$30 | Excl. | | | |
| | Subgrade Preparation | | | | \$0 | | | |
| C.D.A.6 | Preparation, trim and compact Sub Base and Base Course | 2,550 | m2 | \$6 | \$14,025 | | | |
| | | | | | \$0 | | | |
| C.D.A.7 | 100mm thick crushed rock base course | 2,466 | m2 | \$8 | \$20,271 | | | |
| C.D.A.8 | 250mm thick compacted limestone sub base | 2,466 | m2 | \$17 | \$43,106 | | | |
| | Road Paving | | | | \$0 | | | |
| C.D.A.9 | 50mm thick (AC14) | 1,980 | m2 | \$31 | \$61,855 | | | |
| C.D.A.10 | Extra over for 2% red oxide | 90 | m2 | \$6 | \$561 | | | |
| C.D.A.11 | Primer seal | 1,980 | m2 | \$4 | \$7,999 | | | |
| | Kerbing | | | | \$0 | | | |
| C.D.A.12 | Mountable Kerb (MK) | 60 | m | \$25 | \$1,526 | | | |
| C.D.A.13 | Semi Mountable Kerb (SMK) | 80 | m | \$30 | \$2,372 | | | |
| | Line Marking and Furniture | | | | \$0 | | | |
| C.D.A.14 | Line marking | 660 | m | \$6 | \$4,184 | | | |
| C.D.A.15 | Street sign post | 1 | no | \$122 | \$122 | | | |
| C.D.A.16 | Street name plate | 2 | no | \$199 | \$398 | | | |
| C.D.A.17 | Chevron sign | 1 | no | \$613 | \$613 | | | |

| | | | | | | | | |
|--------------|---|---------|--------------|-----------|----------------|-----------|------------------|--|
| C.D.A.18 | Traffic sign Landscaping | 3 | no | \$450 | \$1,350 \$0 | | | |
| C.D.A.19 | Soft landscaping | 180 | m2 | \$0 | Excl. | | | |
| C.D.A.20 | Landscape mix | 42 | m3 | \$90 | \$3,780 | | | |
| C.D.A.21 | Rock pitching | 8 | m2 | \$155 | \$1,242 | | | |
| C.D.A.22 | Drainage layer Other | 180 | m2 | \$0 | Excl. | | | |
| C.D.A.23 | Allow for connection to SWH TOTAL Road Works | | item Item | | \$20,000 | \$236,945 | | |
| C.D.B | Shared Paths | | | | | | | |
| | Earthworks and Site Preparation | | | | | | | |
| C.D.B.1 | Site Clearance (based on light shrubs) | 150 | m2 | \$4 | \$528 | | | |
| C.D.B.2 | Removal of topsoil 150mm and stockpile for later re-use | 150 | m2 | \$2 | \$242 | | | |
| C.D.B.3 | Cut to Fill - General Earthworks | 45 | m3 | \$8 | \$370 | | | |
| C.D.B.4 | Imported Fill | 0 | m3 | \$30 | Excl. | | | |
| | Subgrade Preparation | | | | | | | |
| C.D.B.5 | Preparation, trim and compact Pathway | 150 | m2 | \$6 | \$825 | | | |
| C.D.B.6 | 100 thick concrete footpath with broomed finish | 150 | m2 | \$71 | \$10,626 | | | |
| C.D.B.7 | Sand fill below concrete footpath (100mm) | 150 | m2 | \$5 | \$819 | | | |
| C.D.B.8 | Pram ramp including tactile Line Marking and Furniture | 2 | no | \$973 | \$1,945 | | | |
| C.D.B.9 | Traffic sign TOTAL Shared Paths | 2 | no Item | \$450 | \$900 | \$16,255 | | |
| C.D.C | Street Lighting | | | | | | | |
| | 6.5 SOR Street Light Pole incl. all conduits, light cabling, excavation, and related overheads | | | | | | | |
| C.D.C.1 | TOTAL Street Lighting | 2 | no Item | \$3,442 | \$6,883 | \$6,883 | | |
| C.D.D | Road Drainage | | | | | | | |
| | 450dia reinforced concrete pipe including excavation and backfill | | | | | | | |
| C.D.D.1 | Side entry pits including liner, cover, excavation, and associated works | 90 | m | \$233 | \$20,975 | | | |
| C.D.D.2 | TOTAL Road Drainage | 2 | no Item | \$2,667 | \$5,333 | \$26,308 | | |
| C.D.E | Preliminaries and Project Costs | | | | | | | |
| C.D.E.1 | Traffic Management | 5.0000 | % | \$286,391 | \$14,320 | | | |
| C.D.E.2 | Project Overheads and Preliminaries (Indirect Construction Costs) | 15.0000 | % | \$286,391 | \$42,959 | | | |
| C.D.E.3 | Project Owner's Cost (Planning and Design Costs) | 7.5000 | % | \$286,391 | \$21,479 | | | |
| C.D.E.4 | Risk Contingency Allowance | 10.0000 | % | \$365,148 | \$36,515 | | | |
| | TOTAL Preliminaries and Project Costs | | Item | | | \$115,272 | | |
| | TOTAL South Western Highway (Channelised Intersection) | | | | | | \$401,663 | |
| C.E | At-grade rail crossing | | | | | | | |
| C.E.A | Road Works | | | | | | | |
| | Earthworks and Site Preparation | | | | | | | |
| C.E.A.1 | Site Clearance (based on light shrubs) | 1,063 | m2 | \$4 | \$3,742 | | | |
| C.E.A.2 | Removal of topsoil 150mm and stockpile for later re-use | 1,063 | m2 | \$2 | \$1,711 | | | |
| C.E.A.3 | Cut to Fill - General Earthworks | 532 | m3 | \$8 | \$4,378 | | | |
| C.E.A.4 | Dispose of material off site | 532 | cum | \$10 | \$5,320 | | | |
| C.E.A.5 | Imported Fill | 0 | m3 | \$30 | Excl. | | | |
| | Subgrade Preparation | | | | | | | |
| C.E.A.6 | Preparation, trim and compact Sub Base and Base Course | 1,063 | m2 | \$6 | \$5,847 | | | |
| C.E.A.7 | 100mm thick crushed rock base course | 740 | m2 | \$8 | \$6,083 | | | |
| C.E.A.8 | 250mm thick compacted limestone sub base | 740 | m2 | \$17 | \$12,935 | | | |
| | Road Paving | | | | | | | |
| C.E.A.9 | 50mm thick (AC14) | 995 | m2 | \$31 | \$31,084 | | | |
| C.E.A.10 | Primer seal Kerbing | 995 | m2 | \$4 | \$4,020 | | | |
| C.E.A.11 | Semi Mountable Kerb (SMK) Line Marking and Furniture | 65 | m | \$30 | \$1,927 | | | |
| C.E.A.12 | Line marking | 106 | m | \$6 | \$672 | | | |

| | | | | | | | | |
|--------------|--|---------|------|-------------|-----------|-----------|--|--------------------|
| C.E.A.13 | Line marking at crossing | 995 | sqm | \$10 | \$9,950 | | | |
| C.E.A.14 | Traffic sign | 4 | no | \$450 | \$1,800 | | | |
| | TOTAL Road Works | | Item | | | \$89,469 | | |
| C.E.B | Shared Paths | | | | | | | |
| | Earthworks and Site Preparation | | | | | | | |
| C.E.B.1 | Site Clearance (based on light shrubs) | 213 | m2 | \$4 | \$750 | | | |
| C.E.B.2 | Removal of topsoil 150mm and stockpile for later re-use | 213 | m2 | \$2 | \$343 | | | |
| C.E.B.3 | Cut to Fill - General Earthworks | 107 | m3 | \$8 | \$881 | | | |
| C.E.B.4 | Dispose of material off site | 107 | m3 | \$10 | \$1,070 | | | |
| C.E.B.5 | Imported Fill | 0 | m3 | \$30 | Excl. | | | |
| | Subgrade Preparation | | | | | | | |
| C.E.B.6 | Preparation, trim and compact | 213 | m2 | \$6 | \$1,172 | | | |
| | Pathway | | | | | | | |
| C.E.B.7 | 100 thick concrete footpath with broomed finish | 213 | m2 | \$71 | \$15,089 | | | |
| C.E.B.8 | Sand fill below concrete path (100mm) | 213 | m2 | \$5 | \$1,163 | | | |
| C.E.B.9 | Pram ramp including tactile | 4 | no | \$973 | \$3,891 | | | |
| | Line Marking and Furniture | | | | | | | |
| C.E.B.10 | Traffic sign | 4 | no | \$450 | \$1,800 | | | |
| | TOTAL Shared Paths | | Item | | | \$26,157 | | |
| C.E.C | Street Lighting | | | | | | | |
| | 6.5 SOR Street Light Pole incl. all conduits, light cabling, excavation, and related overheads (provisional allowance) | | | | | | | |
| C.E.C.1 | TOTAL Street Lighting | 4 | no | \$3,442 | \$13,767 | | | \$13,767 |
| | | | Item | | | | | |
| C.E.D | Road Drainage | | | | | | | |
| | 450dia reinforced concrete pipe including excavation and backfill | | | | | | | |
| C.E.D.1 | Side entry pits including liner, cover, excavation, and associated works (provisional allowance) | 115 | m | \$233 | \$26,801 | | | |
| C.E.D.2 | TOTAL Road Drainage | 4 | no | \$2,667 | \$10,666 | | | \$37,467 |
| | | | Item | | | | | |
| C.E.E | Level crossing at Whitby Road | | | | | | | |
| | Level crossing | | | | | | | |
| C.E.E.1 | Allow for new level crossing at Orton Road | 1 | no | \$632,500 | \$632,500 | | | |
| | TOTAL Level crossing at Whitby Road | | item | | | \$632,500 | | |
| C.E.F | Preliminaries and Project Costs | | | | | | | |
| C.E.F.1 | Traffic Management | 10.0000 | % | \$799,360 | \$79,936 | | | |
| C.E.F.2 | Project Overheads and Preliminaries (Indirect Construction Costs) | 15.0000 | % | \$799,360 | \$119,904 | | | |
| C.E.F.3 | Project Owner's Cost (Planning and Design Costs) | 7.5000 | % | \$799,360 | \$59,952 | | | |
| C.E.F.4 | Risk Contingency Allowance | 10.0000 | % | \$1,059,152 | \$105,915 | | | |
| | TOTAL Preliminaries and Project Costs | | Item | | | \$365,707 | | |
| | TOTAL At-grade rail crossing | | | | | | | \$1,165,067 |
| C.F | Bett Road (Roundabout future extension) | | | | | | | |
| C.F.A | Road Works | | | | | | | |
| | Earthworks and Site Preparation | | | | | | | |
| C.F.A.1 | Site Clearance (based on light shrubs) | 2,728 | m2 | \$4 | \$9,603 | | | |
| C.F.A.2 | Removal of topsoil 150mm and stockpile for later re-use | 2,728 | m2 | \$2 | \$4,392 | | | |
| C.F.A.3 | Cut to Fill - General Earthworks | 819 | m3 | \$8 | \$6,740 | | | |
| C.F.A.4 | Detailed excavation - mill and profile | 900 | m2 | \$19 | \$17,082 | | | |
| C.F.A.5 | Imported Fill (Provisional) | 1,316 | m3 | \$30 | \$39,480 | | | |
| | Subgrade Preparation | | | | | | | |
| C.F.A.6 | Preparation, trim and compact | 2,728 | m2 | \$6 | \$15,004 | | | |
| | Sub Base and Base Course | | | | | | | |
| C.F.A.7 | 100mm thick crushed rock base course | 2,139 | m2 | \$8 | \$17,583 | | | |
| C.F.A.8 | 250mm thick compacted limestone sub base | 2,139 | m2 | \$17 | \$37,390 | | | |
| | Road Paving | | | | | | | |
| C.F.A.9 | 50mm thick (AC14) | 1,672 | m2 | \$31 | \$52,233 | | | |
| C.F.A.10 | Primer seal | 1,672 | m2 | \$4 | \$6,755 | | | |
| | Brick Paving | | Item | | \$0 | | | |
| C.F.A.11 | 80 thick brick pavers | 393 | m2 | \$100 | \$39,339 | | | |
| C.F.A.12 | 30 thick compacted sand bed | 240 | m2 | \$2 | \$394 | | | |
| C.F.A.13 | 40 thick compacted sand bed (RAB) | 153 | m2 | \$2 | \$335 | | | |
| C.F.A.14 | 170mm thick compacted limestone | 240 | m2 | \$11 | \$2,729 | | | |

| | | | | | | | | |
|--------------|--|---------|--------------|-----------|----------------|--|------------------|--|
| C.F.A.15 | 250mm thick compacted limestone sub base Kerbing | 153 | m2 | \$17 | \$2,674 | | | |
| C.F.A.16 | Mountable Kerb (MK) | 70 | m | \$25 | \$1,781 | | | |
| C.F.A.17 | Semi Mountable Kerb (SMK) | 146 | m | \$30 | \$4,329 | | | |
| C.F.A.18 | Barrier Kerb (BK) Line Marking and Furniture | 54 | m | \$53 | \$2,869 | | | |
| C.F.A.19 | Line marking | 70 | m | \$6 | \$444 | | | |
| C.F.A.20 | Street sign post | 1 | no | \$122 | \$122 | | | |
| C.F.A.21 | Street name plate | 2 | no | \$199 | \$398 | | | |
| C.F.A.22 | Traffic sign Landscaping | 4 | no | \$450 | \$1,800 \$0 | | | |
| C.F.A.23 | Soft landscaping | 227 | m2 | \$0 | Excl. | | | |
| C.F.A.24 | Landscape mix Other | 57 | m3 | \$90 | \$5,130 | | | |
| C.F.A.25 | Allow for connection to Soldiers Road (both directions) TOTAL Road Works | | Item Item | | \$20,000 | | \$288,605 | |
| C.F.B | Shared Paths | | | | | | | |
| | Earthworks and Site Preparation | | | | | | | |
| C.F.B.1 | Site Clearance (based on light shrubs) | 364 | m2 | \$4 | \$1,281 | | | |
| C.F.B.2 | Removal of topsoil 150mm and stockpile for later re-use | 364 | m2 | \$2 | \$586 | | | |
| C.F.B.3 | Cut to Fill - General Earthworks | 110 | m3 | \$8 | \$905 | | | |
| C.F.B.4 | Imported Fill Subgrade Preparation | 182 | m3 | \$30 | \$5,460 | | | |
| C.F.B.5 | Preparation, trim and compact Pathway | 364 | m2 | \$6 | \$2,002 | | | |
| C.F.B.6 | 100 thick concrete footpath with broomed finish | 364 | m2 | \$71 | \$25,786 | | | |
| C.F.B.7 | Sand fill below concrete path (100mm) | 364 | m2 | \$5 | \$1,987 | | | |
| C.F.B.8 | Pram ramp including tactile | 8 | no | \$973 | \$7,781 | | | |
| C.F.B.9 | Tactile paving Line Marking and Furniture | 13 | m2 | \$325 | \$4,225 | | | |
| C.F.B.10 | Traffic sign TOTAL Shared Paths | 4 | no Item | \$450 | \$1,800 | | \$51,814 | |
| C.F.C | Street Lighting | | | | | | | |
| C.F.C.1 | 6.5 SOR Street Light Pole incl. all conduits, light cabling, excavation, and related overheads TOTAL Street Lighting | 4 | no Item | \$3,442 | \$13,767 | | \$13,767 | |
| C.F.D | Road Drainage | | | | | | | |
| C.F.D.1 | 450dia reinforced concrete pipe including excavation and backfill | 130 | m | \$233 | \$30,297 | | | |
| C.F.D.2 | Side entry pits including liner, cover, excavation, and associated works TOTAL Road Drainage | 6 | no Item | \$2,667 | \$15,999 | | \$46,296 | |
| C.F.E | Preliminaries and Project Costs | | | | | | | |
| C.F.E.1 | Traffic Management | 5.0000 | % | \$400,481 | \$20,024 | | | |
| C.F.E.2 | Project Overheads and Preliminaries (Indirect Construction Costs) | 15.0000 | % | \$400,481 | \$60,072 | | | |
| C.F.E.3 | Project Owner's Cost (Planning and Design Costs) | 7.5000 | % | \$400,481 | \$30,036 | | | |
| C.F.E.4 | Risk Contingency Allowance TOTAL Preliminaries and Project Costs | 10.0000 | % Item | \$510,614 | \$51,061 | | \$161,194 | |
| | TOTAL Bett Road (Roundabout future extension) | | | | | | \$561,675 | |
| C.G | Utilities | | | | | | | |
| C.G.A | Power and Lighting (Western Power) | | | | | | | |
| C.G.A.1 | General Provisional Sum of \$100,000 as it is not clear if diversions are required TOTAL Power and Lighting (Western Power) | 1 | PS Item | \$100,000 | \$100,000 | | \$100,000 | |
| C.G.B | Communications (NBN / Telstra / Westnet / etc.) | | | | | | | |
| C.G.B.1 | General Provisional Sum of \$100,000 as it is not clear if diversions are required TOTAL Communications (NBN / Telstra / Westnet / etc.) | 1 | PS Item | \$100,000 | \$100,000 | | \$100,000 | |

| | | | | | | | |
|--------------|---|---------|--------------|--|----------|----------|---------------------|
| <u>C.G.C</u> | <u>Water and Sewer (Water Corporation)</u> No allowance has been made for Water Corporation diversions as we do not see existing mains from our desktop study TOTAL Water and Sewer (Water Corporation) | | Note Item | | | \$0 | |
| <u>C.G.D</u> | <u>Gas (ATCO)</u> No allowance has been made for ATCO diversions as we do not see existing valves from our desktop study TOTAL Gas (ATCO) | | Note Item | | | \$0 | |
| <u>C.G.E</u> | <u>Preliminaries and Project Costs</u> | | | | | | |
| C.G.E.1 | Traffic Management | 10.0000 | % | \$200,000 | \$20,000 | | |
| C.G.E.2 | Project Overheads and Preliminaries (Indirect Construction Costs) | 15.0000 | % | \$200,000 | \$30,000 | | |
| C.G.E.3 | Project Owner's Cost (Planning and Design Costs) | 5.0000 | % | \$200,000 | \$10,000 | | |
| C.G.E.4 | Risk Contingency Allowance | 10.0000 | % | \$260,000 | \$26,000 | | |
| | TOTAL Preliminaries and Project Costs | | Item | | | \$86,000 | |
| | TOTAL Utilities | | | | | | \$286,000 |
| A.A.A.7 | Estimated Imported Fill | 31,905 | m3 | | | | |
| A.A.A.5 | Total m3 of Cut to Fill - General Earthworks | 38,188 | m3 | | | | |
| | Less Cut to Fill costed | 0 | m3 | \$30 | \$0 | | |
| | Total Adjustment for Imported Fill (less Cut to Fill) | | | <i>See "Imported Fill" sheet at the end of these costings.</i> | | | \$0 |
| | TOTAL Road – New Whitby Road | | Item | | | | \$17,485,755 |

**Shire of Serpentine Jarrahdale DCP
 DCA 3 - Mundijong Whitby - Update**

| Code | Description | Quantity | UOM | Rate | Subtotal | Sub Section Total | Section Total | Road/ DOS Total |
|--------------|--|----------|------|---------|--|-------------------|---------------|-----------------|
| D | ROAD – NORTH-SOUTH ROAD | | | | | | | |
| D.A | <u>Road Construction</u> | | | | | | | |
| D.A.A | <u>Road Works</u> | | | | | | | |
| | Earthworks and Site Preparation | | | | \$0 | | | |
| D.A.A.1 | Site Clearance (based on light shrubs) | 30,970 | m2 | \$4 | \$109,014 | | | |
| D.A.A.2 | Removal of topsoil 150mm and stockpile for later re-use | 30,970 | m2 | \$2 | \$49,862 | | | |
| D.A.A.3 | Cut to Fill - General Earthworks | 10,778 | m3 | \$8 | \$88,703 | | | |
| D.A.A.4 | Imported Fill | 0 | m3 | \$30 | Excl. | | | |
| D.A.A.5 | Form swale | 4,956 | m2 | \$4 | \$18,783 | | | |
| | Subgrade Preparation | | | | \$0 | | | |
| D.A.A.6 | Preparation, trim and compact | 30,970 | m2 | \$6 | \$170,335 | | | |
| | Sub Base and Base Course | | | | \$0 | | | |
| D.A.A.7 | 100mm thick crushed rock base course | 21,555 | m2 | \$8 | \$177,182 | | | |
| D.A.A.8 | 250mm thick compacted limestone sub base | 21,555 | m2 | \$17 | \$376,781 | | | |
| | Road Paving | | | | \$0 | | | |
| D.A.A.9 | 50mm thick (AC14) | 18,582 | m2 | \$31 | \$580,502 | | | |
| D.A.A.10 | Extra over for 2% red oxide | 3,717 | m2 | \$6 | \$23,157 | | | |
| D.A.A.11 | Primer seal | 18,582 | m2 | \$4 | \$75,071 | | | |
| | Kerbing | | | | \$0 | | | |
| D.A.A.12 | Mountable Kerb (MK) | 2,478 | m | \$25 | \$63,040 | | | |
| D.A.A.13 | Kerb openings | 124 | no | \$350 | \$43,400 | | | |
| D.A.A.14 | Semi Mountable Kerb (SMK) | 2,478 | m | \$30 | \$73,473 | | | |
| | Line Marking and Furniture | | | | \$0 | | | |
| D.A.A.15 | Line marking | 4,956 | m | \$6 | \$31,421 | | | |
| | Landscaping | | | | \$0 | | | |
| D.A.A.16 | Soft landscaping | 7,020 | m2 | \$0 | Excl. | | | |
| D.A.A.17 | Landscape mix | 1,755 | m3 | \$90 | \$157,950 | | | |
| D.A.A.18 | Rock pitching | 413 | m2 | \$155 | \$64,118 | | | |
| D.A.A.19 | Drainage layer | 7,433 | m2 | \$0 | Excl. | | | |
| | TOTAL Road Works | | Item | | | \$2,102,793 | | |
| D.A.B | <u>Shared Paths</u> | | | | | | | |
| | Earthworks and Site Preparation | | | | | | | |
| D.A.B.1 | Site Clearance (based on light shrubs) | 6,194 | m2 | \$4 | \$21,803 | | | |
| D.A.B.2 | Removal of topsoil 150mm and stockpile for later re-use | 6,194 | m2 | \$2 | \$9,972 | | | |
| D.A.B.3 | Cut to Fill - General Earthworks | 1,859 | m3 | \$8 | \$15,300 | | | |
| D.A.B.4 | Imported Fill | 0 | m3 | \$30 | Excl. | | | |
| | Subgrade Preparation | | | | | | | |
| D.A.B.5 | Preparation, trim and compact | 6,194 | m2 | \$6 | \$34,067 | | | |
| | Pathway | | | | | | | |
| D.A.B.6 | 100 thick concrete footpath with broomed finish | 6,194 | m2 | \$71 | \$438,783 | | | |
| D.A.B.7 | Sand fill below concrete footpath (100mm) | 6,194 | m2 | \$5 | \$33,819 | | | |
| | TOTAL Shared Paths | | Item | | | \$553,744 | | |
| D.A.C | <u>Street Lighting</u> | | | | | | | |
| D.A.C.1 | 6.5 SOR Street Light Pole incl. all conduits, light cabling, excavation, and related overheads | 71 | no | \$3,442 | \$244,362 | | | |
| D.A.C.2 | 6.5 DOR Street Light Pole incl. all conduits, light cabling, excavation, and related overheads | 36 | no | \$5,111 | \$183,995 | | | |
| | TOTAL Street Lighting | | Item | | | \$428,357 | | |
| D.A.D | <u>Road Drainage</u> | | | | | | | |
| D.A.D.1 | 450dia reinforced concrete pipe including excavation and backfill | 1,239 | m | \$233 | \$288,749 | | | |
| D.A.D.2 | 150dia slotted PVC subsoil drainage pipe including aggregate, geofabric and porous sand | 1,239 | m | \$189 | \$233,675 | | | |
| | | | | | CESP measured at intersections, RAB's | | | |
| D.A.D.3 | Side entry pits including liner, cover, excavation, and associated works | 0 | no | \$2,667 | | | | |

| | | | | | | | |
|--------------|--|---------|------|-------------|-----------|-------------|--------------------|
| D.A.D.4 | Raised gully / bubble up pits including liner, cover, grate, excavation, rock pitching, and associated works | 42 | no | \$3,021 | \$126,864 | | |
| D.A.D.5 | 6500x600mm box culvert incl. headwall, excavation, backfill, etc. | 30 | m | \$9,919 | \$297,583 | | |
| D.A.D.6 | Remove existing culvert in preparation for new culvert (approximatley 7m wide) | 1 | LS | \$9,823 | \$9,823 | | |
| | TOTAL Road Drainage | | Item | | | \$956,695 | |
| <u>D.A.E</u> | <u>Preliminaries and Project Costs</u> | | | | | | |
| D.A.E.1 | Traffic Management | 5.0000 | % | \$4,041,589 | \$202,079 | | |
| D.A.E.2 | Project Overheads and Preliminaries (Indirect Construction Costs) | 15.0000 | % | \$4,041,589 | \$606,238 | | |
| D.A.E.3 | Project Owner's Cost (Planning and Design Costs) | 7.5000 | % | \$4,041,589 | \$303,119 | | |
| D.A.E.4 | Risk Contingency Allowance | 10.0000 | % | \$5,153,026 | \$515,303 | | |
| | TOTAL Preliminaries and Project Costs | | Item | | | \$1,626,740 | |
| | TOTAL Road Construction | | | | | | \$5,668,329 |
| <u>D.B</u> | <u>Watkins Road (Roundabout)</u> | | | | | | |
| <u>D.B.A</u> | <u>Road Works</u> | | | | | | |
| D.B.A.1 | Earthworks and Site Preparation Site Clearance (based on light shrubs) | 2,504 | m2 | \$4 | \$8,814 | | |
| D.B.A.2 | Removal of topsoil 150mm and stockpile for later re-use | 2,504 | m2 | \$2 | \$4,031 | | |
| D.B.A.3 | Cut to Fill - General Earthworks | 752 | m3 | \$8 | \$6,189 | | |
| D.B.A.4 | Imported Fill | 0 | m3 | \$30 | Excl. | | |
| D.B.A.5 | Subgrade Preparation Preparation, trim and compact Sub Base and Base Course | 2,504 | m2 | \$6 | \$13,772 | | |
| D.B.A.6 | 100mm thick crushed rock base course | 1,983 | m2 | \$8 | \$16,300 | | |
| D.B.A.7 | 200mm thick compacted limestone sub base | | m2 | \$14 | \$0 | | |
| D.B.A.8 | 250mm thick compacted limestone sub base | 1,983 | m2 | \$17 | \$34,663 | | |
| D.B.A.9 | Road Paving 50mm thick (AC14) | 1,518 | m2 | \$31 | \$47,422 | | |
| D.B.A.10 | Primer seal Brick Paving | 1,518 | m2 | \$4 | \$6,133 | | |
| | | | Item | | \$0 | | |
| D.B.A.11 | 80 thick brick pavers | 333 | m2 | \$100 | \$33,333 | | |
| D.B.A.12 | 30 thick compacted sand bed | 180 | m2 | \$2 | \$295 | | |
| D.B.A.13 | 40 thick compacted sand bed (RAB) | 153 | m2 | \$2 | \$335 | | |
| D.B.A.14 | 170mm thick compacted limestone | 180 | m2 | \$11 | \$2,047 | | |
| D.B.A.15 | 250mm thick compacted limestone sub base Kerbing | 153 | m2 | \$17 | \$2,674 | | |
| D.B.A.16 | Mountable Kerb (MK) | 70 | m | \$25 | \$1,781 | | |
| D.B.A.17 | Semi Mountable Kerb (SMK) | 143 | m | \$30 | \$4,240 | | |
| D.B.A.18 | Barrier Kerb (BK) Line Marking and Furniture | 54 | m | \$53 | \$2,869 | | |
| D.B.A.19 | Line marking | 53 | m | \$6 | \$336 | | |
| D.B.A.20 | Street sign post | 1 | no | \$122 | \$122 | | |
| D.B.A.21 | Street name plate | 2 | no | \$199 | \$398 | | |
| D.B.A.22 | Chevron sign | 1 | no | \$613 | \$613 | | |
| D.B.A.23 | Traffic sign Landscaping | 3 | no | \$450 | \$1,350 | | |
| | | | | | \$0 | | |
| D.B.A.24 | Soft landscaping | 227 | m2 | \$0 | Excl. | | |
| D.B.A.25 | Landscape mix Other | 57 | m3 | \$90 | \$5,130 | | |
| D.B.A.26 | Allow for connection to Watkins Road (both sides) | | item | | \$20,000 | | |
| | TOTAL Road Works | | Item | | | \$212,847 | |
| <u>D.B.B</u> | <u>Shared Paths</u> | | | | | | |
| D.B.B.1 | Earthworks and Site Preparation Site Clearance (based on light shrubs) | 356 | m2 | \$4 | \$1,253 | | |
| D.B.B.2 | Removal of topsoil 150mm and stockpile for later re-use | 356 | m2 | \$2 | \$573 | | |
| D.B.B.3 | Cut to Fill - General Earthworks | 107 | m3 | \$8 | \$881 | | |

| | | | | | | | | |
|--------------|--|---------|------|-----------|----------|-----------|------------------|--|
| D.B.B.4 | Imported Fill | 0 | m3 | \$30 | Excl. | | | |
| | Subgrade Preparation | | | | | | | |
| D.B.B.5 | Preparation, trim and compact Pathway | 356 | m2 | \$6 | \$1,958 | | | |
| D.B.B.6 | 100 thick concrete footpath with broomed finish | 356 | m2 | \$71 | \$25,219 | | | |
| D.B.B.7 | Sand fill below concrete path (100mm) | 356 | m2 | \$5 | \$1,944 | | | |
| D.B.B.8 | Pram ramp including tactile | 6 | no | \$973 | \$5,836 | | | |
| D.B.B.9 | Tactile paving | 10 | m2 | \$325 | \$3,250 | | | |
| | Line Marking and Furniture | | | | | | | |
| D.B.B.10 | Traffic sign | 2 | no | \$450 | \$900 | | | |
| | TOTAL Shared Paths | | Item | | | \$41,814 | | |
| D.B.C | Street Lighting | | | | | | | |
| D.B.C.1 | 6.5 SOR Street Light Pole incl. all conduits, light cabling, excavation, and related overheads | 4 | no | \$3,442 | \$13,767 | | | |
| | TOTAL Street Lighting | | Item | | | \$13,767 | | |
| D.B.D | Road Drainage | | | | | | | |
| D.B.D.1 | 450dia reinforced concrete pipe including excavation and backfill | 130 | m | \$233 | \$30,297 | | | |
| D.B.D.2 | Side entry pits including liner, cover, excavation, and associated works | 4 | no | \$2,667 | \$10,666 | | | |
| | TOTAL Road Drainage | | Item | | | \$40,963 | | |
| D.B.E | Preliminaries and Project Costs | | | | | | | |
| D.B.E.1 | Traffic Management | 5.0000 | % | \$309,390 | \$15,470 | | | |
| D.B.E.2 | Project Overheads and Preliminaries (Indirect Construction Costs) | 15.0000 | % | \$309,390 | \$46,409 | | | |
| D.B.E.3 | Project Owner's Cost (Planning and Design Costs) | 7.5000 | % | \$309,390 | \$23,204 | | | |
| D.B.E.4 | Risk Contingency Allowance | 10.0000 | % | \$394,473 | \$39,447 | | | |
| | TOTAL Preliminaries and Project Costs | | Item | | | \$124,530 | | |
| | TOTAL Watkins Road (Roundabout) | | | | | | \$433,920 | |
| D.C | Galvin Road (Roundabout) | | | | | | | |
| D.C.A | Road Works | | | | | | | |
| | Earthworks and Site Preparation | | | | | | | |
| D.C.A.1 | Site Clearance (based on light shrubs) | 2,504 | m2 | \$4 | \$8,814 | | | |
| D.C.A.2 | Removal of topsoil 150mm and stockpile for later re-use | 2,504 | m2 | \$2 | \$4,031 | | | |
| D.C.A.3 | Cut to Fill - General Earthworks | 752 | m3 | \$8 | \$6,189 | | | |
| D.C.A.4 | Imported Fill | 0 | m3 | \$30 | Excl. | | | |
| | Subgrade Preparation | | | | | | | |
| D.C.A.5 | Preparation, trim and compact | 2,504 | m2 | \$6 | \$13,772 | | | |
| | Sub Base and Base Course | | | | | | | |
| D.C.A.6 | 100mm thick crushed rock base course | 1,983 | m2 | \$8 | \$16,300 | | | |
| D.C.A.7 | 250mm thick compacted limestone sub base | 1,983 | m2 | \$17 | \$34,663 | | | |
| | Road Paving | | | | | | | |
| D.C.A.8 | 50mm thick (AC14) | 1,518 | m2 | \$31 | \$47,422 | | | |
| D.C.A.9 | Primer seal | 1,518 | m2 | \$4 | \$6,133 | | | |
| | Brick Paving | | | | | | | |
| D.C.A.10 | 80 thick brick pavers | 333 | m2 | \$100 | \$33,333 | | | |
| D.C.A.11 | 30 thick compacted sand bed | 180 | m2 | \$2 | \$295 | | | |
| D.C.A.12 | 40 thick compacted sand bed (RAB) | 153 | m2 | \$2 | \$335 | | | |
| D.C.A.13 | 170mm thick compacted limestone | 180 | m2 | \$11 | \$2,047 | | | |
| D.C.A.14 | 250mm thick compacted limestone sub base | 153 | m2 | \$17 | \$2,674 | | | |
| | Kerbing | | | | | | | |
| D.C.A.15 | Mountable Kerb (MK) | 70 | m | \$25 | \$1,781 | | | |
| D.C.A.16 | Semi Mountable Kerb (SMK) | 143 | m | \$30 | \$4,240 | | | |
| D.C.A.17 | Barrier Kerb (BK) | 54 | m | \$53 | \$2,869 | | | |
| | Line Marking and Furniture | | | | | | | |
| D.C.A.18 | Line marking | 53 | m | \$6 | \$336 | | | |
| D.C.A.19 | Street sign post | 1 | no | \$122 | \$122 | | | |
| D.C.A.20 | Street name plate | 2 | no | \$199 | \$398 | | | |
| D.C.A.21 | Chevron sign | 1 | no | \$613 | \$613 | | | |
| D.C.A.22 | Traffic sign | 3 | no | \$450 | \$1,350 | | | |
| | Landscaping | | | | \$0 | | | |

| | | | | | | | |
|--------------|---|---------|--------------|--------------|-----------|-----------|------------------|
| D.C.A.23 | Soft landscaping | 227 | m2 | \$0 | Excl. | | |
| D.C.A.24 | Landscape mix Other | 57 | m3 | \$90 | \$5,130 | | |
| D.C.A.25 | Allow for connection to Galvin Road (both sides) TOTAL Road Works | | item Item | | \$20,000 | \$212,847 | |
| <u>D.C.B</u> | <u>Shared Paths</u> | | | | | | |
| | Earthworks and Site Preparation | | | | | | |
| D.C.B.1 | Site Clearance (based on light shrubs) | 356 | m2 | \$4 | \$1,253 | | |
| D.C.B.2 | Removal of topsoil 150mm and stockpile for later re-use | 356 | m2 | \$2 | \$573 | | |
| D.C.B.3 | Cut to Fill - General Earthworks | 107 | m3 | \$8 | \$881 | | |
| D.C.B.4 | Imported Fill | 0 | m3 | \$30 | Excl. | | |
| | Subgrade Preparation | | | | | | |
| D.C.B.5 | Preparation, trim and compact Pathway | 356 | m2 | \$6 | \$1,958 | | |
| D.C.B.6 | 100 thick concrete footpath with broomed finish | 356 | m2 | \$71 | \$25,219 | | |
| D.C.B.7 | Sand fill below concrete path (100mm) Pram ramp | 356 | m2 no | \$5 \$670 | \$1,944 | | |
| D.C.B.8 | Pram ramp including tactile | 6 | no | \$973 | \$5,836 | | |
| D.C.B.9 | Tactile paving Line Marking and Furniture | 10 | m2 | \$325 | \$3,250 | | |
| D.C.B.10 | Traffic sign TOTAL Shared Paths | 2 | no Item | \$450 | \$900 | \$41,814 | |
| <u>D.C.C</u> | <u>Street Lighting</u> | | | | | | |
| D.C.C.1 | 6.5 SOR Street Light Pole incl. all conduits, light cabling, excavation, and related overheads TOTAL Street Lighting | 4 | no Item | \$3,442 | \$13,767 | \$13,767 | |
| <u>D.C.D</u> | <u>Road Drainage</u> | | | | | | |
| D.C.D.1 | 450dia reinforced concrete pipe including excavation and backfill | 130 | m | \$233 | \$30,297 | | |
| D.C.D.2 | Side entry pits including liner, cover, excavation, and associated works TOTAL Road Drainage | 4 | no Item | \$2,667 | \$10,666 | \$40,963 | |
| <u>D.C.E</u> | <u>Preliminaries and Project Costs</u> | | | | | | |
| D.C.E.1 | Traffic Management | 5.0000 | % | \$309,390 | \$15,470 | | |
| D.C.E.2 | Project Overheads and Preliminaries (Indirect Construction Costs) | 15.0000 | % | \$309,390 | \$46,409 | | |
| D.C.E.3 | Project Owner's Cost (Planning and Design Costs) | 7.5000 | % | \$309,390 | \$23,204 | | |
| D.C.E.4 | Risk Contingency Allowance | 10.0000 | % | \$394,473 | \$39,447 | | |
| | TOTAL Preliminaries and Project Costs | | Item | | | \$124,530 | |
| | TOTAL Galvin Road (Roundabout) | | | | | | \$433,920 |
| <u>D.D</u> | <u>Utilities</u> | | | | | | |
| <u>D.D.A</u> | <u>Power and Lighting (Western Power)</u> | | | | | | |
| D.D.A.1 | General Provisional Sum of \$100,000 as it is not clear if diversions are required TOTAL Power and Lighting (Western Power) | 1 | PS Item | \$100,000 | \$100,000 | \$100,000 | |
| <u>D.D.B</u> | <u>Communications (NBN / Telstra / Westnet / etc.)</u> | | | | | | |
| D.D.B.1 | General Provisional Sum of \$100,000 as it is not clear if diversions are required TOTAL Communications (NBN / Telstra / Westnet / etc.) | 1 | PS Item | \$100,000 | \$100,000 | \$100,000 | |
| <u>D.D.C</u> | <u>Water and Sewer (Water Corporation)</u> | | | | | | |
| | No allowance has been made for Water Corporation diversions as we do not see existing mains from our desktop study TOTAL Water and Sewer (Water Corporation) | | Note Item | | | \$0 | |
| <u>D.D.D</u> | <u>Gas (ATCO)</u> | | | | | | |
| | No allowance has been made for ATCO diversions as we do not see existing valves from our desktop study TOTAL Gas (ATCO) | | Note Item | | | \$0 | |
| <u>D.D.E</u> | <u>Preliminaries and Project Costs</u> | | | | | | |
| D.D.E.1 | Traffic Management | 10.0000 | % | \$200,000 | \$20,000 | | |
| D.D.E.2 | Project Overheads and Preliminaries (Indirect Construction Costs) | 15.0000 | % | \$200,000 | \$30,000 | | |
| D.D.E.3 | Project Owner's Cost (Planning and Design Costs) | 5.0000 | % | \$200,000 | \$10,000 | | |
| D.D.E.4 | Risk Contingency Allowance | 10.0000 | % | \$260,000 | \$26,000 | | |



| | | | | | | | | | |
|---------|--|--|-------------|------|-----|----------|------------------|--------------------|--|
| | TOTAL Preliminaries and Project Costs | | Item | | | \$86,000 | | | |
| | TOTAL Utilities | | | | | | \$286,000 | | |
| A.A.A.7 | Estimated Imported Fill | 12,060 | m3 | | | | | | |
| A.A.A.5 | Total m3 of Cut to Fill - General Earthworks | 14,355 | m3 | | | | | | |
| | Less Cut to Fill costed | 0 | m3 | \$30 | \$0 | | | | |
| | Total Adjustment for Imported Fill (less Cut to Fill) | <i>See "Imported Fill" sheet at the end of these costings.</i> | | | | | | \$0 | |
| | TOTAL Road – North-South Road | | Item | | | | | \$6,822,168 | |

**Shire of Serpentine Jarrahdale DCP
 DCA 3 - Mundijong Whitby - Update**

| Code | Description | Quantity | UOM | Rate | Subtotal | Sub Section Total | Section Total | Road/ DOS Total |
|--------------|---|----------|------|---------|-----------|-------------------|---------------|-----------------|
| E | ROAD – SKYLINE BOULEVARD | | | | | | | |
| E.A | Road Construction | | | | | | | |
| E.A.A | Road Works | | | | | | | |
| | Earthworks and Site Preparation | | | | \$0 | | | |
| E.A.A.1 | Site Clearance (based on light shrubs) | 6,817 | m2 | \$4 | \$23,996 | | | |
| E.A.A.2 | Removal of topsoil 150mm and stockpile for later re-use | 6,817 | m2 | \$2 | \$10,975 | | | |
| E.A.A.3 | Cut to Fill - General Earthworks | 2,231 | m3 | \$8 | \$18,361 | | | |
| E.A.A.4 | Imported Fill | 0 | m3 | \$30 | \$0 | | | |
| E.A.A.5 | Form swale | 620 | m2 | \$4 | \$2,350 | | | |
| | Subgrade Preparation | | | | \$0 | | | |
| E.A.A.6 | Preparation, trim and compact | 6,817 | m2 | \$6 | \$37,494 | | | |
| | Sub Base and Base Course | | | | \$0 | | | |
| E.A.A.7 | 100mm thick crushed rock base course | 4,617 | m2 | \$8 | \$37,952 | | | |
| E.A.A.8 | 200mm thick compacted limestone sub base | 4,617 | m2 | \$14 | \$64,592 | | | |
| | Road Paving | | | | \$0 | | | |
| E.A.A.9 | 30mm thick (AC10) | 3,486 | m2 | \$18 | \$63,410 | | | |
| E.A.A.10 | Primer seal | 3,486 | m2 | \$4 | \$14,083 | | | |
| | Kerbing | | | | \$0 | | | |
| E.A.A.11 | Mountable Kerb (MK) | 620 | m | \$25 | \$15,773 | | | |
| E.A.A.12 | Kerb openings | 31 | no | \$350 | \$10,850 | | | |
| E.A.A.13 | Semi Mountable Kerb (SMK) | 620 | m | \$30 | \$18,383 | | | |
| E.A.A.14 | Concrete flush edge beam | 155 | m | \$67 | \$10,393 | | | |
| | Line Marking and Furniture | | | | \$0 | | | |
| E.A.A.15 | Line marking | 620 | m | \$6 | \$3,931 | | | |
| | Landscaping | | | | \$0 | | | |
| E.A.A.16 | Soft landscaping | 878 | m2 | \$0 | Excl. | | | |
| E.A.A.17 | Landscape mix | 220 | m3 | \$90 | \$19,800 | | | |
| E.A.A.18 | Rock pitching | 52 | m2 | \$155 | \$8,073 | | | |
| E.A.A.19 | Drainage layer | 930 | m2 | \$0 | Excl. | | | |
| | Other | | | | | | | |
| E.A.A.20 | Connection to existing | | item | | \$10,000 | | | |
| | TOTAL Road Works | | Item | | | \$370,415 | | |
| E.A.B | Shared Paths | | | | | | | |
| | Earthworks and Site Preparation | | | | | | | |
| E.A.B.1 | Site Clearance (based on light shrubs) | 1,550 | m2 | \$4 | \$5,456 | | | |
| E.A.B.2 | Removal of topsoil 150mm and stockpile for later re-use | 1,550 | m2 | \$2 | \$2,496 | | | |
| E.A.B.3 | Cut to Fill - General Earthworks | 465 | m3 | \$8 | \$3,827 | | | |
| E.A.B.4 | Imported Fill | 0 | m3 | \$30 | Excl. | | | |
| | Subgrade Preparation | | | | | | | |
| E.A.B.5 | Preparation, trim and compact | 1,550 | m2 | \$6 | \$8,525 | | | |
| | Pathway | | | | | | | |
| E.A.B.6 | 100 thick concrete footpath with broomed finish | 1,550 | m2 | \$71 | \$109,802 | | | |
| E.A.B.7 | Sand fill below concrete footpath (100mm) | 1,550 | m2 | \$5 | \$8,463 | | | |
| | TOTAL Shared Paths | | Item | | | \$138,568 | | |
| E.A.C | Street Lighting | | | | | | | |
| E.A.C.1 | 6.5 DOR Street Light Pole incl. all conduits, light cabling, excavation, and related overheads (as per remainder of Skyline Blvd) | 9 | no | \$5,111 | \$45,999 | | | |
| | TOTAL Street Lighting | | Item | | | \$45,999 | | |
| E.A.D | Road Drainage | | | | | | | |
| E.A.D.1 | 450dia reinforced concrete pipe including excavation and backfill | 310 | m | \$233 | \$72,246 | | | |
| E.A.D.2 | 150dia slotted PVC subsoil drainage pipe including aggregate, geofabric and porous sand | 310 | m | \$189 | \$58,466 | | | |

| | | | | | | | | |
|--------------|--|---------|------|-----------|---------------------------------------|-----------|--------------------|--|
| E.A.D.3 | Side entry pits including liner, cover, excavation, and associated works | 0 | no | \$2,667 | CESP measured at intersections, RAB's | | | |
| E.A.D.4 | Raised gully / bubble up pits including liner, cover, grate, excavation, rock pitching, and associated works | 11 | no | \$3,021 | \$33,226 | | | |
| | TOTAL Road Drainage | | Item | | | \$163,938 | | |
| E.A.E | Preliminaries and Project Costs | | | | | | | |
| E.A.E.1 | Traffic Management | 5.0000 | % | \$718,920 | \$35,946 | | | |
| E.A.E.2 | Project Overheads and Preliminaries (Indirect Construction Costs) | 15.0000 | % | \$718,920 | \$107,838 | | | |
| E.A.E.3 | Project Owner's Cost (Planning and Design Costs) | 7.5000 | % | \$718,920 | \$53,919 | | | |
| E.A.E.4 | Risk Contingency Allowance | 10.0000 | % | \$916,624 | \$91,662 | | | |
| | TOTAL Preliminaries and Project Costs | | Item | | | \$289,365 | | |
| | TOTAL Road Construction | | | | | | \$1,008,286 | |
| E.B | <u>New Whitby Road (Roundabout)</u> | | | | | | | |
| E.B.A | <u>Road Works</u> | | | | | | | |
| | Earthworks and Site Preparation | | | | | | | |
| E.B.A.1 | Site Clearance (based on light shrubs) | 2,504 | m2 | \$4 | \$8,814 | | | |
| E.B.A.2 | Removal of topsoil 150mm and stockpile for later re-use | 2,504 | m2 | \$2 | \$4,031 | | | |
| E.B.A.3 | Cut to Fill - General Earthworks | 752 | m3 | \$8 | \$6,189 | | | |
| E.B.A.4 | Imported Fill | 0 | m3 | \$30 | Excl. | | | |
| | Subgrade Preparation | | | | | | | |
| E.B.A.5 | Preparation, trim and compact Sub Base and Base Course | 2,504 | m2 | \$6 | \$13,772 | | | |
| E.B.A.6 | 100mm thick crushed rock base course | 1,983 | m2 | \$8 | \$16,300 | | | |
| E.B.A.7 | 250mm thick compacted limestone sub base | 1,983 | m2 | \$17 | \$34,663 | | | |
| | Road Paving | | | | | | | |
| E.B.A.8 | 50mm thick (AC14) | 1,518 | m2 | \$31 | \$47,422 | | | |
| E.B.A.9 | Primer seal | 1,518 | m2 | \$4 | \$6,133 | | | |
| | Brick Paving | | Item | | \$0 | | | |
| E.B.A.10 | 80 thick brick pavers | 333 | m2 | \$100 | \$33,333 | | | |
| E.B.A.11 | 30 thick compacted sand bed | 180 | m2 | \$2 | \$295 | | | |
| E.B.A.12 | 40 thick compacted sand bed (RAB) | 153 | m2 | \$2 | \$335 | | | |
| E.B.A.13 | 170mm thick compacted limestone | 180 | m2 | \$11 | \$2,047 | | | |
| E.B.A.14 | 250mm thick compacted limestone sub base | 153 | m2 | \$17 | \$2,674 | | | |
| | Kerbing | | | | | | | |
| E.B.A.15 | Mountable Kerb (MK) | 70 | m | \$25 | \$1,781 | | | |
| E.B.A.16 | Semi Mountable Kerb (SMK) | 143 | m | \$30 | \$4,240 | | | |
| E.B.A.17 | Barrier Kerb (BK) | 54 | m | \$53 | \$2,869 | | | |
| | Line Marking and Furniture | | | | | | | |
| E.B.A.18 | Line marking | 53 | m | \$6 | \$336 | | | |
| E.B.A.19 | Street sign post | 1 | no | \$122 | \$122 | | | |
| E.B.A.20 | Street name plate | 2 | no | \$199 | \$398 | | | |
| E.B.A.21 | Chevron sign | 1 | no | \$613 | \$613 | | | |
| E.B.A.22 | Traffic sign | 3 | no | \$450 | \$1,350 | | | |
| | Landscaping | | | | \$0 | | | |
| E.B.A.23 | Soft landscaping | 227 | m2 | \$0 | Excl. | | | |
| E.B.A.24 | Landscape mix | 57 | m3 | \$90 | \$5,130 | | | |
| | TOTAL Road Works | | Item | | | \$192,847 | | |
| E.B.B | <u>Shared Paths</u> | | | | | | | |
| | Earthworks and Site Preparation | | | | | | | |
| E.B.B.1 | Site Clearance (based on light shrubs) | 356 | m2 | \$4 | \$1,253 | | | |
| E.B.B.2 | Removal of topsoil 150mm and stockpile for later re-use | 356 | m2 | \$2 | \$573 | | | |
| E.B.B.3 | Cut to Fill - General Earthworks | 107 | m3 | \$8 | \$881 | | | |
| E.B.B.4 | Imported Fill | 0 | m3 | \$30 | Excl. | | | |
| | Subgrade Preparation | | | | | | | |
| E.B.B.5 | Preparation, trim and compact Pathway | 356 | m2 | \$6 | \$1,958 | | | |

| | | | | | | | |
|--------------|--|---------|------|-----------|----------|-----------|------------------|
| E.B.B.6 | 100 thick concrete footpath with broomed finish | 356 | m2 | \$71 | \$25,219 | | |
| E.B.B.7 | Sand fill below concrete path (100mm) | 356 | m2 | \$5 | \$1,944 | | |
| E.B.B.8 | Pram ramp including tactile | 6 | no | \$973 | \$5,836 | | |
| E.B.B.9 | Tactile paving | 10 | m2 | \$325 | \$3,250 | | |
| | Line Marking and Furniture | | | | | | |
| E.B.B.10 | Traffic sign | 2 | no | \$450 | \$900 | | |
| | TOTAL Shared Paths | | Item | | | \$41,814 | |
| E.B.C | Street Lighting | | | | | | |
| E.B.C.1 | 6.5 SOR Street Light Pole incl. all conduits, light cabling, excavation, and related overheads | 4 | no | \$3,442 | \$13,767 | | |
| | TOTAL Street Lighting | | Item | | | \$13,767 | |
| E.B.D | Road Drainage | | | | | | |
| E.B.D.1 | 450dia reinforced concrete pipe including excavation and backfill | 130 | m | \$233 | \$30,297 | | |
| E.B.D.2 | Side entry pits including liner, cover, excavation, and associated works | 4 | no | \$2,667 | \$10,666 | | |
| | TOTAL Road Drainage | | Item | | | \$40,963 | |
| E.B.E | Preliminaries and Project Costs | | | | | | |
| E.B.E.1 | Traffic Management | 5.0000 | % | \$289,390 | \$14,470 | | |
| E.B.E.2 | Project Overheads and Preliminaries (Indirect Construction Costs) | 15.0000 | % | \$289,390 | \$43,409 | | |
| E.B.E.3 | Project Owner's Cost (Planning and Design Costs) | 7.5000 | % | \$289,390 | \$21,704 | | |
| E.B.E.4 | Risk Contingency Allowance | 10.0000 | % | \$368,973 | \$36,897 | | |
| | TOTAL Preliminaries and Project Costs | | Item | | | \$116,480 | |
| | TOTAL New Whitby Road (Roundabout) | | | | | | \$405,870 |
| E.C | Tinspar Avenue (Roundabout) - already constructed | | | | | | |
| E.C.A | Road Works | | | | | | |
| E.C.A.1 | Already Constructed | | | | \$0 | | |
| | TOTAL Road Works | | Item | | | \$0 | |
| E.C.B | Shared Paths | | | | | | |
| E.C.B.1 | Already Constructed | | | | \$0 | | |
| | TOTAL Shared Paths | | Item | | | \$0 | |
| E.C.C | Street Lighting | | | | | | |
| E.C.C.1 | Already Constructed | | | | \$0 | | |
| | TOTAL Street Lighting | | Item | | | \$0 | |
| E.C.D | Road Drainage | | | | | | |
| E.C.D.1 | Already Constructed | | | | \$0 | | |
| | TOTAL Road Drainage | | Item | | | \$0 | |
| E.C.E | Preliminaries and Project Costs | | | | | | |
| E.C.E.1 | Already Constructed | | | | \$0 | | |
| | TOTAL Preliminaries and Project Costs | | Item | | | \$0 | |
| | TOTAL Tinspar Avenue (Roundabout) - already constructed | | | | | | \$0 |
| E.D | Utilities | | | | | | |
| E.D.A | Power and Lighting (Western Power) | | | | | | |
| | No allowance has been made for Western Power diversions as we do not see existing mains from our desktop study | | Note | | | | |
| | TOTAL Power and Lighting (Western Power) | | Item | | | \$0 | |
| E.D.B | Communications (NBN / Telstra / Westnet / etc.) | | | | | | |
| | No allowance has been made for Communications diversions as we do not see existing mains from our desktop study | | Note | | | | |
| | TOTAL Communications (NBN / Telstra / Westnet / etc.) | | Item | | | \$0 | |
| E.D.C | Water and Sewer (Water Corporation) | | | | | | |
| | No allowance has been made for Water Corporation diversions as we do not see existing mains from our desktop study | | Note | | | | |
| | TOTAL Water and Sewer (Water Corporation) | | Item | | | \$0 | |
| E.D.D | Gas (ATCO) | | | | | | |
| | No allowance has been made for ATCO diversions as we do not see existing valves from our desktop study | | Note | | | | |
| | TOTAL Gas (ATCO) | | Item | | | \$0 | |

| | | | | | | | | | |
|---------|--|--|-------------|------|-----|-----|--|--------------------|------------|
| E.D.E | Preliminaries and Project Costs | | | | | | | | |
| E.D.E.1 | Traffic Management | 10.0000 | % | \$0 | \$0 | | | | |
| E.D.E.2 | Project Overheads and Preliminaries (Indirect Construction Costs) | 15.0000 | % | \$0 | \$0 | | | | |
| E.D.E.3 | Project Owner's Cost (Planning and Design Costs) | 5.0000 | % | \$0 | \$0 | | | | |
| E.D.E.4 | Risk Contingency Allowance | 10.0000 | % | \$0 | \$0 | | | | |
| | TOTAL Preliminaries and Project Costs | | Item | | | \$0 | | | |
| | TOTAL Utilities | | | | | | | \$0 | |
| A.A.A.7 | Estimated Imported Fill | 2,640 | m3 | | | | | | |
| A.A.A.5 | Total m3 of Cut to Fill - General Earthworks | 3,555 | m3 | | | | | | |
| | Less Cut to Fill costed | 0 | m3 | \$30 | \$0 | | | | |
| | Total Adjustment for Imported Fill (less Cut to Fill) | <i>See "Imported Fill" sheet at the end of these costings.</i> | | | | | | | \$0 |
| | TOTAL Road (Remaining) – Skyline Boulevard | | Item | | | | | \$1,414,156 | |
| | Prefunded build completed prior to gazettal of the Amendment under DCP Condition | | | | | | | \$1,320,000 | |
| | Total to be included in DCP1 | | | | | | | \$2,734,156 | |

**Shire of Serpentine Jarrahdale DCP
 DCA 3 - Mundijong Whitby - Update**

| Code | Description | Quantity | UOM | Rate | Subtotal | Sub Section Total | Section Total | Road/ DOS Total |
|--------------|---|----------|------|---------|-----------|-------------------|---------------|-----------------|
| F | ROAD – TINSPAR AVENUE | | | | | | | |
| F.A | Road Construction | | | | | | | |
| F.A.A | Road Works | | | | | | | |
| | Earthworks and Site Preparation | | | | \$0 | | | |
| F.A.A.1 | Site Clearance (based on light shrubs) | 26,701 | m2 | \$4 | \$93,988 | | | |
| F.A.A.2 | Removal of topsoil 150mm and stockpile for later re-use | 26,701 | m2 | \$2 | \$42,989 | | | |
| F.A.A.3 | Cut to Fill - General Earthworks | 8,739 | m3 | \$8 | \$71,922 | | | |
| F.A.A.4 | Imported Fill | 0 | m3 | \$30 | Excl. | | | |
| F.A.A.5 | Form swale | 2,428 | m2 | \$4 | \$9,202 | | | |
| | Subgrade Preparation | | | | \$0 | | | |
| F.A.A.6 | Preparation, trim and compact Sub Base and Base Course | 26,701 | m2 | \$6 | \$146,856 | | | |
| F.A.A.7 | 100mm thick crushed rock base course | 15,050 | m2 | \$8 | \$123,711 | | | |
| F.A.A.8 | 200mm thick compacted limestone sub base | 15,050 | m2 | \$14 | \$210,550 | | | |
| | Road Paving | | | | \$0 | | | |
| F.A.A.9 | 30mm thick (AC10) | 12,137 | m2 | \$18 | \$220,772 | | | |
| F.A.A.10 | Primer seal | 12,137 | m2 | \$4 | \$49,033 | | | |
| | Brick Paving | | Item | | \$0 | | | |
| F.A.A.11 | 80 thick brick pavers | 3,035 | m2 | \$100 | \$303,804 | | | |
| F.A.A.12 | 30 thick compacted sand bed | 3,035 | m2 | \$2 | \$4,977 | | | |
| F.A.A.13 | 170mm thick compacted limestone Kerbing | 3,035 | m2 | \$11 | \$34,508 | | | |
| | | | | | \$0 | | | |
| F.A.A.14 | Mountable Kerb (MK) | 2,428 | m | \$25 | \$61,768 | | | |
| F.A.A.15 | Kerb openings | 122 | no | \$350 | \$42,700 | | | |
| F.A.A.16 | Semi Mountable Kerb (SMK) | 2,428 | m | \$30 | \$71,990 | | | |
| F.A.A.17 | Concrete flush edge beam | 1,214 | m | \$67 | \$81,399 | | | |
| | Line Marking and Furniture | | | | \$0 | | | |
| F.A.A.18 | Line marking | 2,428 | m | \$6 | \$15,394 | | | |
| | Landscaping | | | | \$0 | | | |
| F.A.A.19 | Soft landscaping | 3,439 | m2 | \$0 | Excl. | | | |
| F.A.A.20 | Landscape mix | 860 | m3 | \$90 | \$77,400 | | | |
| F.A.A.21 | Rock pitching | 203 | m2 | \$155 | \$31,516 | | | |
| F.A.A.22 | Drainage layer | 3,642 | m2 | \$0 | Excl. | | | |
| | TOTAL Road Works | | Item | | | \$1,694,477 | | |
| F.A.B | Shared Paths | | | | | | | |
| | Earthworks and Site Preparation | | | | | | | |
| F.A.B.1 | Site Clearance (based on light shrubs) | 6,069 | m2 | \$4 | \$21,363 | | | |
| F.A.B.2 | Removal of topsoil 150mm and stockpile for later re-use | 6,069 | m2 | \$2 | \$9,771 | | | |
| F.A.B.3 | Cut to Fill - General Earthworks | 1,821 | m3 | \$8 | \$14,987 | | | |
| F.A.B.4 | Imported Fill | 0 | m3 | \$30 | Excl. | | | |
| | Subgrade Preparation | | | | | | | |
| F.A.B.5 | Preparation, trim and compact Pathway | 6,069 | m2 | \$6 | \$33,380 | | | |
| F.A.B.6 | 100 thick concrete footpath with broomed finish | 6,069 | m2 | \$71 | \$429,928 | | | |
| F.A.B.7 | Sand fill below concrete footpath (100mm) | 6,069 | m2 | \$5 | \$33,137 | | | |
| | TOTAL Shared Paths | | Item | | | \$542,565 | | |
| F.A.C | Street Lighting | | | | | | | |
| | 6.5 DOR Street Light Pole incl. all conduits, light cabling, excavation, and related overheads (as per remainder of Skyline Blvd) | 35 | no | \$5,111 | \$178,884 | | | |
| | TOTAL Street Lighting | | Item | | | \$178,884 | | |
| F.A.D | Road Drainage | | | | | | | |
| F.A.D.1 | 450dia reinforced concrete pipe including excavation and backfill | 1,214 | m | \$233 | \$282,923 | | | |

| | | | | | | | | |
|--------------|--|---------|------|-------------|--|-------------|--|--------------------|
| F.A.D.2 | 150dia slotted PVC subsoil drainage pipe including aggregate, geofabric and porous sand | 1,214 | m | \$189 | \$228,960 | | | |
| F.A.D.3 | Side entry pits including liner, cover, excavation, and associated works | 0 | no | \$2,667 | CESP measured at intersections, RAB's | | | |
| F.A.D.4 | Raised gully / bubble up pits including liner, cover, grate, excavation, rock pitching, and associated works | 41 | no | \$3,021 | \$123,844 | | | |
| | TOTAL Road Drainage | | Item | | | \$635,727 | | |
| F.A.E | Preliminaries and Project Costs | | | | | | | |
| F.A.E.1 | Traffic Management | 5.0000 | % | \$3,051,653 | \$152,583 | | | |
| F.A.E.2 | Project Overheads and Preliminaries (Indirect Construction Costs) | 15.0000 | % | \$3,051,653 | \$457,748 | | | |
| F.A.E.3 | Project Owner's Cost (Planning and Design Costs) | 7.5000 | % | \$3,051,653 | \$228,874 | | | |
| F.A.E.4 | Risk Contingency Allowance | 10.0000 | % | \$3,890,858 | \$389,086 | | | |
| | TOTAL Preliminaries and Project Costs | | Item | | | \$1,228,290 | | |
| | TOTAL Road Construction | | | | | | | \$4,279,944 |
| | <u>Kiernan Street (Seagull Intersection) - already constructed</u> | | | | | | | |
| F.B | Road Works | | | | | | | |
| F.B.A | Already Constructed | | | | \$0 | | | |
| F.B.A.1 | TOTAL Road Works | | Item | | | \$0 | | |
| F.B.B | Shared Paths | | | | | | | |
| F.B.B.1 | Already Constructed | | | | \$0 | | | |
| | TOTAL Shared Paths | | Item | | | \$0 | | |
| F.B.C | Street Lighting | | | | | | | |
| F.B.C.1 | Already Constructed | | | | \$0 | | | |
| | TOTAL Street Lighting | | Item | | | \$0 | | |
| F.B.D | Road Drainage | | | | | | | |
| F.B.D.1 | Already Constructed | | | | \$0 | | | |
| | TOTAL Road Drainage | | Item | | | \$0 | | |
| F.B.E | Preliminaries and Project Costs | | | | | | | |
| F.B.E.1 | Already Constructed | | | | \$0 | | | |
| | TOTAL Preliminaries and Project Costs | | Item | | | \$0 | | |
| | TOTAL Kiernan Street (Seagull Intersection) - already constructed | | | | | | | \$0 |
| F.C | <u>South Western Highway (Channelised Intersection)</u> | | | | | | | |
| F.C.A | Road Works | | | | | | | |
| F.C.A.1 | Earthworks and Site Preparation | | | | \$0 | | | |
| F.C.A.1 | Site Clearance (based on light shrubs) | 2,550 | m2 | \$4 | \$8,976 | | | |
| F.C.A.2 | Removal of topsoil 150mm and stockpile for later re-use | 2,550 | m2 | \$2 | \$4,106 | | | |
| F.C.A.3 | Cut to Fill - General Earthworks | 765 | m3 | \$8 | \$6,296 | | | |
| F.C.A.4 | Detailed excavation - mill and profile | 1,800 | m2 | \$19 | \$34,164 | | | |
| F.C.A.5 | Imported Fill | 0 | m3 | \$30 | Excl. | | | |
| F.C.A.6 | Subgrade Preparation | | | | \$0 | | | |
| F.C.A.6 | Preparation, trim and compact | 2,550 | m2 | \$6 | \$14,025 | | | |
| | Sub Base and Base Course | | | | \$0 | | | |
| F.C.A.7 | 100mm thick crushed rock base course | 2,466 | m2 | \$8 | \$20,271 | | | |
| F.C.A.8 | 250mm thick compacted limestone sub base | 2,466 | m2 | \$17 | \$43,106 | | | |
| | Road Paving | | | | \$0 | | | |
| F.C.A.9 | 50mm thick (AC14) | 1,980 | m2 | \$31 | \$61,855 | | | |
| F.C.A.10 | Extra over for 2% red oxide | 90 | m2 | \$6 | \$561 | | | |
| F.C.A.11 | Primer seal | 1,980 | m2 | \$4 | \$7,999 | | | |
| | Kerbing | | | | \$0 | | | |
| F.C.A.12 | Mountable Kerb (MK) | 60 | m | \$25 | \$1,526 | | | |
| F.C.A.13 | Semi Mountable Kerb (SMK) | 80 | m | \$30 | \$2,372 | | | |
| | Line Marking and Furniture | | | | \$0 | | | |
| F.C.A.14 | Line marking | 660 | m | \$6 | \$4,184 | | | |
| F.C.A.15 | Street sign post | 1 | no | \$122 | \$122 | | | |
| F.C.A.16 | Street name plate | 2 | no | \$199 | \$398 | | | |
| F.C.A.17 | Chevron sign | 1 | no | \$613 | \$613 | | | |

| | | | | | | | |
|--------------|--|---------|--------------|-----------|----------------|-----------|------------------|
| F.C.A.18 | Traffic sign Landscaping | 3 | no | \$450 | \$1,350 \$0 | | |
| F.C.A.19 | Soft landscaping | 180 | m2 | \$0 | Excl. | | |
| F.C.A.20 | Landscape mix | 42 | m3 | \$90 | \$3,780 | | |
| F.C.A.21 | Rock pitching | 8 | m2 | \$155 | \$1,242 | | |
| F.C.A.22 | Drainage layer Other | 180 | m2 | \$0 | Excl. | | |
| F.C.A.23 | Allow for connection to SWH TOTAL Road Works | | item Item | | \$20,000 | \$236,945 | |
| F.C.B | Shared Paths | | | | | | |
| | Earthworks and Site Preparation | | | | | | |
| F.C.B.1 | Site Clearance (based on light shrubs) | 150 | m2 | \$4 | \$528 | | |
| F.C.B.2 | Removal of topsoil 150mm and stockpile for later re-use | 150 | m2 | \$2 | \$242 | | |
| F.C.B.3 | Cut to Fill - General Earthworks | 45 | m3 | \$8 | \$370 | | |
| F.C.B.4 | Imported Fill | 0 | m3 | \$30 | Excl. | | |
| | Subgrade Preparation | | | | | | |
| F.C.B.5 | Preparation, trim and compact Pathway | 150 | m2 | \$6 | \$825 | | |
| F.C.B.6 | 100 thick concrete footpath with broomed finish | 150 | m2 | \$71 | \$10,626 | | |
| F.C.B.7 | Sand fill below concrete footpath (100mm) | 150 | m2 | \$5 | \$819 | | |
| F.C.B.8 | Pram ramp including tactile Line Marking and Furniture | 2 | no | \$973 | \$1,945 | | |
| F.C.B.9 | Traffic sign TOTAL Shared Paths | 2 | no Item | \$450 | \$900 | \$16,255 | |
| F.C.C | Street Lighting | | | | | | |
| | 6.5 SOR Street Light Pole incl. all conduits, light cabling, excavation, and related overheads | | | | | | |
| F.C.C.1 | TOTAL Street Lighting | 2 | no Item | \$3,442 | \$6,883 | \$6,883 | |
| F.C.D | Road Drainage | | | | | | |
| | 450dia reinforced concrete pipe including excavation and backfill | | | | | | |
| F.C.D.1 | Side entry pits including liner, cover, excavation, and associated works | 90 | m | \$233 | \$20,975 | | |
| F.C.D.2 | TOTAL Road Drainage | 2 | no Item | \$2,667 | \$5,333 | \$26,308 | |
| F.C.E | Preliminaries and Project Costs | | | | | | |
| F.C.E.1 | Traffic Management | 5.0000 | % | \$286,391 | \$14,320 | | |
| F.C.E.2 | Project Overheads and Preliminaries (Indirect Construction Costs) | 15.0000 | % | \$286,391 | \$42,959 | | |
| F.C.E.3 | Project Owner's Cost (Planning and Design Costs) | 7.5000 | % | \$286,391 | \$21,479 | | |
| F.C.E.4 | Risk Contingency Allowance | 10.0000 | % | \$365,148 | \$36,515 | | |
| | TOTAL Preliminaries and Project Costs | | Item | | | \$115,272 | |
| | TOTAL South Western Highway (Channelised Intersection) | | | | | | \$401,663 |
| F.D | Utilities | | | | | | |
| F.D.A | Power and Lighting (Western Power) | | | | | | |
| | General Provisional Sum of \$50,000 as it is not clear if diversions are required | | | | | | |
| F.D.A.1 | TOTAL Power and Lighting (Western Power) | 1 | PS Item | \$50,000 | \$50,000 | \$50,000 | |
| F.D.B | Communications (NBN / Telstra / Westnet / etc.) | | | | | | |
| | General Provisional Sum of \$50,000 as it is not clear if diversions are required | | | | | | |
| F.D.B.1 | TOTAL Communications (NBN / Telstra / Westnet / etc.) | 1 | PS Item | \$50,000 | \$50,000 | \$50,000 | |
| F.D.C | Water and Sewer (Water Corporation) | | | | | | |
| | Offset and sleeve approximately 30m road length of water and sewer about 1m deeper from the current location - Provisional Sum | | | | | | |
| F.D.C.1 | TOTAL Water and Sewer (Water Corporation) | 1 | PS Item | \$49,068 | \$49,068 | \$49,068 | |
| F.D.D | Gas (ATCO) | | | | | | |
| | No allowance has been made for ATCO diversions as we do not see existing valves from our desktop study | | | | | | |
| | TOTAL Gas (ATCO) | | Note Item | | | \$0 | |
| F.D.E | Preliminaries and Project Costs | | | | | | |

| | | | | | | | | | |
|---------|--|--|------|-----------|----------|----------|------------------|--------------------|--|
| F.D.E.1 | Traffic Management | 5.0000 | % | \$149,068 | \$7,453 | | | | |
| F.D.E.2 | Project Overheads and Preliminaries (Indirect Construction Costs) | 15.0000 | % | \$149,068 | \$22,360 | | | | |
| F.D.E.3 | Project Owner's Cost (Planning and Design Costs) | 5.0000 | % | \$149,068 | \$7,453 | | | | |
| F.D.E.4 | Risk Contingency Allowance | 10.0000 | % | \$186,335 | \$18,633 | | | | |
| | TOTAL Preliminaries and Project Costs | | Item | | | \$55,900 | | | |
| | TOTAL Utilities | | | | | | \$204,968 | | |
| A.A.A.7 | Estimated Imported Fill | 8,715 | m3 | | | | | | |
| A.A.A.5 | Total m3 of Cut to Fill - General Earthworks | 11,370 | m3 | | | | | | |
| | Less Cut to Fill costed | 0 | m3 | \$30 | \$0 | | | | |
| | Total Adjustment for Imported Fill (less Cut to Fill) | <i>See "Imported Fill" sheet at the end of these costings.</i> | | | | | | \$0 | |
| | TOTAL Road – Tinspar Avenue | | Item | | | | | \$4,886,575 | |
| | Prefunded build completed prior to gazettal of the Amendment under DCP Condition | | | | | | | \$1,265,000 | |
| | Total to be included in DCP1 | | | | | | | \$6,151,575 | |

**Shire of Serpentine Jarrahdale DCP
 DCA 3 - Mundijong Whitby - Update**

| Code | Description | Quantity | UOM | Rate | Subtotal | Sub Section Total | Section Total | Road/ DOS Total |
|------------|---|------------|-------------|-------------|----------|-------------------|--------------------|--------------------|
| G | DISTRICT OPEN SPACE – WHITBY HIGH SCHOOL DISTRICT SPORTING SPACE | | | | | | | |
| G.A | Siteworks & Earthworks | | | | | | | |
| G.A.A | Site Clearance (based on light shrubs) | 46,000 | m2 | \$4 | | \$169,280 | | |
| G.A.B | Removal of topsoil 150mm and remove off-site | 46,000 | m2 | \$2 | | \$77,234 | | |
| G.A.C | Cut to Fill - General Earthworks of 300mm across site | 13,800 | m3 | \$8 | | \$113,471 | | |
| G.A.D | Levelling, grading and compaction to final design levels | 46,000 | m2 | \$3 | | \$151,800 | | |
| G.A.E | Weed eradication | 46,000 | m2 | \$1 | | \$26,910 | | |
| G.A.F | Excavation to 300 below finished levels | 13,800 | m2 | \$14 | | \$190,440 | | |
| G.A.G | 300 deep clean sand fill | 13,800 | m3 | \$30 | | \$414,000 | | |
| G.A.H | Gypsum soil conditioner | 46,000 | m2 | \$2 | | \$77,740 | | |
| G.A.I | 15 deep C-Wise Horticulture soil conditioner | 46,000 | m2 | \$5 | | \$251,160 | | |
| G.A.J | 100 thick imported turf sand | 46,000 | sqm | \$5 | | \$227,240 | | |
| G.A.K | Organic fertilizer to turf | 46,000 | sqm | \$1 | | \$53,820 | | |
| | TOTAL Siteworks & Earthworks | | | | | | \$1,754,000 | |
| G.B | Grassing & Irrigation | | | | | | | |
| G.B.A | Supply and lay roll on turf including maintaining | 46,000 | sqm | \$20 | | \$920,000 | | |
| G.B.B | Irrigation | 46,000 | sqm | \$8 | | \$368,000 | | |
| G.B.C | Provisional sum allowance for pumps, bores and controls - no allowance for storage tank | 1 | Item | \$80,000 | | \$80,000 | | |
| | TOTAL Grassing & Irrigation | | | | | | \$1,368,000 | |
| G.C | Landscaping & Equipment | | | | | | | |
| | Equipment | | | | | | | |
| G.C.A | AFL goal posts (set of 8) including sleeves, footings, cages and post padding | 1 | no | \$7,406 | | \$7,406 | | |
| G.C.B | Timber Bollards @1200 spacing | 188 | no | \$121 | | \$22,748 | | |
| G.C.C | <u>Line marking to oval</u> | | | | | | | |
| G.C.C.1 | Allow 2 guys 1 day | 16 | hrs | \$100 | \$1,600 | | | |
| G.C.C.2 | Equipment | 1 | no | \$1,000 | \$1,000 | | | |
| G.C.C.3 | Profit | | | | \$260 | | | |
| | TOTAL Line marking to oval | 710 | m | \$4 | | \$2,860 | | |
| G.C.D | Provisional Sums Provisional sum allowance for signage | 1 | item | \$5,000 | | \$5,000 | | |
| | TOTAL Landscaping & Equipment | | | | | | \$39,000 | |
| G.D | Drainage | | | | | | | |
| G.D.A | 150 diameter pipe including excavation and backfill | 1,310 | m | \$143 | | \$186,675 | | |
| | TOTAL Drainage | | | | | | \$187,000 | |
| G.E | Preliminaries & Project Costs | | | | | | | |
| G.E.A | Traffic Management | 0.0000 | % | \$3,348,000 | | \$0 | | |
| G.E.B | Project Overheads and Preliminaries (Indirect Construction Costs) | 10.0000 | % | \$3,348,000 | | \$334,800 | | |
| G.E.C | Project Owner's Cost (Planning and Design Costs) | 7.5000 | % | \$3,348,000 | | \$251,100 | | |
| G.E.D | Risk Contingency Allowance | 10.0000 | % | \$3,933,900 | | \$393,390 | | |
| | TOTAL Preliminaries & Project Costs | | | | | | \$980,000 | |
| | TOTAL District Open Space – Whitby High School District Sporting Space | | Item | | | | | \$4,328,000 |

**Shire of Serpentine Jarrahdale DCP
 DCA 3 - Mundijong Whitby - Update**

| Code | Description | Quantity | UOM | Rate | Subtotal | Sub Section Total | Section Total | Road/ DOS Total |
|--|--|------------|-------------|-------------|----------|-------------------|--------------------|--------------------|
| DISTRICT OPEN SPACE – TAYLOR ROAD/ SCOTT ROAD PRIMARY SCHOOL NEIGHBOURHOOD OPEN SPACE | | | | | | | | |
| H | Siteworks & Earthworks | | | | | | | |
| H.A.A | Site Clearance (based on light shrubs) | 46,000 | m2 | \$4 | | \$169,280 | | |
| H.A.B | Removal of topsoil 150mm and remove off-site | 46,000 | m2 | \$2 | | \$77,234 | | |
| H.A.C | Cut to Fill - General Earthworks of 300mm across site | 13,800 | m3 | \$8 | | \$113,471 | | |
| H.A.D | Levelling, grading and compaction to final design levels | 46,000 | m2 | \$3 | | \$151,800 | | |
| H.A.E | Weed eradication | 46,000 | m2 | \$1 | | \$26,910 | | |
| H.A.F | Excavation to 300 below finished levels | 13,800 | m2 | \$14 | | \$190,440 | | |
| H.A.G | 300 deep clean sand fill | 13,800 | m3 | \$30 | | \$414,000 | | |
| H.A.H | Gypsum soil conditioner | 46,000 | m2 | \$2 | | \$77,740 | | |
| H.A.I | 15 deep C-Wise Horticulture soil conditioner | 46,000 | m2 | \$5 | | \$251,160 | | |
| H.A.J | 100 thick imported turf sand | 46,000 | sqm | \$5 | | \$227,240 | | |
| H.A.K | Organic fertilizer to turf | 46,000 | sqm | \$1 | | \$53,820 | | |
| | TOTAL Siteworks & Earthworks | | | | | | \$1,754,000 | |
| H.B | Grassing & Irrigation | | | | | | | |
| H.B.A | Supply and lay roll on turf including maintaining | 46,000 | sqm | \$20 | | \$920,000 | | |
| H.B.B | Irrigation | 46,000 | sqm | \$8 | | \$368,000 | | |
| H.B.C | Provisional sum allowance for pumps, bores and controls - no allowance for storage tank | 1 | Item | \$80,000 | | \$80,000 | | |
| | TOTAL Grassing & Irrigation | | | | | | \$1,368,000 | |
| H.C | Landscaping & Equipment | | | | | | | |
| | Equipment | | | | | | | |
| H.C.A | AFL goal posts (set of 8) including sleeves, footings, cages and post padding | 1 | no | \$7,406 | | \$7,406 | | |
| H.C.B | Timber Bollards @1200 spacing | 188 | no | \$121 | | \$22,748 | | |
| H.C.C | Line marking to oval | | | | | | | |
| H.C.C.1 | Allow 2 guys 1 day | 16 | hrs | \$100 | \$1,600 | | | |
| H.C.C.2 | Equipment | 1 | no | \$1,000 | \$1,000 | | | |
| H.C.C.3 | Profit | | | | \$260 | | | |
| | TOTAL Line marking to oval | 710 | m | \$4 | | \$2,860 | | |
| H.C.D | | | | | | \$0 | | |
| H.C.E | Provisional Sums | | | | | \$0 | | |
| H.C.F | Provisional sum allowance for signage | 1 | item | \$5,000 | | \$5,000 | | |
| | TOTAL Landscaping & Equipment | | | | | | \$39,000 | |
| H.D | Drainage | | | | | | | |
| H.D.A | 150 diameter pipe including excavation and backfill | 1,310 | m | \$143 | | \$186,675 | | |
| | TOTAL Drainage | | | | | | \$187,000 | |
| H.E | Preliminaries & Project Costs | | | | | | | |
| H.E.A | Traffic Management | 0.0000 | % | \$3,348,000 | | \$0 | | |
| H.E.B | Project Overheads and Preliminaries (Indirect Construction Costs) | 10.0000 | % | \$3,348,000 | | \$334,800 | | |
| H.E.C | Project Owner's Cost (Planning and Design Costs) | 7.5000 | % | \$3,348,000 | | \$251,100 | | |
| H.E.D | Risk Contingency Allowance | 10.0000 | % | \$3,933,900 | | \$393,390 | | |
| | TOTAL Preliminaries & Project Costs | | | | | | \$980,000 | |
| | TOTAL District Open Space – Taylor Road/ Scott Road Primary School Neighbourhood Open Space | | Item | | | | | \$4,328,000 |

M11b Keirnan Park DSS– 1b: Ovals

Updated Jun 2023

Costs undertaken internally by Shire Personnel - to be updated by external QS on final design.

\$ 3,007,693

| KIERNAN PARK MASTERPLAN SCENARIOS | | INDICATIVE SCENARIO 1A | | | |
|-----------------------------------|--|------------------------|-------|-----------|----------------|
| Item | Description | Quantity | Unit | Rate (\$) | Total (\$) |
| 1.00 | BUILDINGS | | | | |
| 1.01 | Allowance for Recreation Centre | | Note | | Excluded |
| 1.02 | Allowance for Hockey/Soccer/Rugby Pavillion | | Note | | Excluded |
| 1.03 | Allowance for Baseball/Softball Pavillion | | Note | | Excluded |
| 1.04 | Allowance for Soccer Change Rooms | | Note | | Excluded |
| 1.05 | Allowance for AFL / Cricket Pavillion | | m2 | | - |
| 1.06 | Allowance for Athletics Pavillion | | Note | | Excluded |
| 1.07 | Allowance for BMX Grandstand (basic tiered mound with shade cover) | | Note | | Excluded |
| 1.08 | Allowance for BMX Pavillion | | Note | | Excluded |
| | TOTAL BUILDING COST | | - | | - |
| 2.00 | External Works & Landscaping | | | | |
| 2.01 | Allowance for Site Clearance | | m2 | | - |
| 2.02 | Allowance for demolition of buildings / structures | | Note | | Not Applicable |
| 2.03 | Allowance for demolition / removal of hardstandings | | Note | | Not Applicable |
| 2.04 | Allowance for general cut to fill | | m3 | | - |
| 2.05 | Allowance for imported fill material | | m3 | | - |
| 2.06 | Allowance for removal of unsuitable cut | | Note | | Excluded |
| 2.07 | Allowance for formation of batters including fabric cover | | m2 | | - |
| 2.08 | Allowance for retaining walls | | Note | | Excluded |
| 2.09 | Allowance for temporary battering / retaining to suit staging (no details) | | P.Sum | | - |
| 2.10 | Allowance for sub soil drainage | | Note | | Excluded |
| 2.11 | Allowance for ground remediation | | Note | | Excluded |
| 2.12 | Allowance for car parking complete | | m2 | | - |
| 2.13 | Allowance for roads complete | | m2 | | - |
| 2.14 | Allowance for cross overs complete | | No | | - |
| 2.15 | Allowance for bridge structures | | No | | - |
| 2.16 | Allowance for outdoor 50m pool and surrounds | | Note | | Excluded |
| 2.17 | Allowance for leisure pool | | Note | | Excluded |
| 2.18 | Allowance for Tennis Courts (9) | | Note | | Excluded |
| 2.19 | Allowance for Netball Courts (15) | | Note | | Excluded |
| 2.20 | Allowance for Soccer Pitches - Grass | | Note | | Excluded |
| 2.21 | Allowance for Hockey Pitches - Grass | | Note | | Excluded |
| 2.22 | Allowance for Hockey Pitches - Synthetic | | Note | | Excluded |
| 2.23 | Allowance for Rugby Pitches - Grass | | Note | | Excluded |
| 2.24 | Allowance for Baseball Diamonds - Grass | | Note | | Excluded |
| 2.25 | Allowance for Baseball pitch - Grass | | Note | | Included |
| 2.26 | Allowance for AFL Pitches - Grass (halved for 1 oval - see Stage 2) | 32,000 | m2 | 93 | 2,976,432 |
| 2.27 | Extra over Soft Landscaping Allowance for Athletics Track - Grass including infill | | Note | - | Excluded |
| 2.28 | Allowance for general grassed areas between playing surfaces (halved for 1 oval - see Stage 2) | 26,600 | | 50 | 1,319,552 |
| 2.29 | Allowance for Cricket Pitch | | No | | - |
| 2.30 | Allowance for Cricket Pitch and Net | | No | | - |
| 2.31 | Allowance for Bowls - Grass / Lawn | | Note | | Excluded |
| 2.32 | Allowance for BMX Track | | Note | | Excluded |
| 2.33 | Allowance for Pump Track | | Note | | Excluded |
| 2.34 | Allowance for BMW Shade Structures | | Note | | Excluded |
| 2.35 | Allowance for fencing to BMX | | Note | | Excluded |
| 2.36 | Allowance for Mountain Bike Trail | | Note | | Excluded |
| 2.37 | Allowance for works to shrub areas | | Note | | Excluded |
| 2.38 | Allowance for works to stream | | Sum | | - |
| 2.39 | Allowance for formation of water treatment pond | | Note | | Excluded |
| 2.40 | E.O Allowance for feature lagoon to above | | | | Excluded |
| 2.41 | Allowance for hard landscaping / pavements generally (20% balance of site area) | | P.Sum | | - |
| 2.42 | Allowance for soft landscaping / shrubs generally (40% balance of site area) | | P.Sum | | - |
| 2.43 | Allowance for works to balance of site | | Note | | Excluded |

| | | | | | |
|-------------|--|--------|-------|---------|------------------|
| 2.44 | Allowance for playground / equipment | | Sum | | - |
| 2.45 | Allowance for shelters etc | | Sum | | - |
| 2.46 | Allowance for fitments; bins, seats, furniture | | Sum | | - |
| 2.47 | Allowance for stepped seating | | | | |
| 2.48 | Allowance for signage | | Sum | | - |
| 2.49 | Allowance for site fencing | | Note | | Excluded |
| 2.50 | Allowance for Main Contractors Preliminaries and Margin | 8% | Sum | 343,679 | Excluded |
| | External Works & Landscaping Sub Total | | | | 4,295,984 |
| 3.00 | Site Services | | | | |
| 3.01 | Allowance for common service trench to each building | | m | | - |
| 3.02 | Allowance for services infrastructure to Recreation Centre | | Note | | Excluded |
| 3.03 | Allowance for services infrastructure to Hockey/Soccer/Rugby Pavillion | | Note | | Excluded |
| 3.04 | Allowance for services infrastructure to Baseball/Softball Pavillion | | Note | | Excluded |
| 3.05 | Allowance for services infrastructure to Soccer Change Rooms | | Note | | Excluded |
| 3.06 | Allowance for services infrastructure to AFL / Cricket Pavillion | | P.Sum | | - |
| 3.07 | Allowance for services infrastructure to Athletics Pavillion | | Note | | Excluded |
| 3.08 | Allowance for services infrastructure to BMX Pavillion | | Note | | Excluded |
| 3.09 | Allowance for lighting to car parks; 1 light per 400sqm | | P.Sum | | - |
| 3.10 | Allowance for lighting to roads; 1 light per 400sqm | | P.Sum | | - |
| 3.11 | Allowance for sports lighting to Tennis | | Note | | Excluded |
| 3.12 | Allowance for sports lighting to Netball | | Note | | Excluded |
| 3.13 | Allowance for sports lighting to Soccer | | Note | | Excluded |
| 3.14 | Allowance for sports lighting to Hockey | | Note | | Excluded |
| 3.15 | Allowance for sports lighting to Rugby | | Note | | Excluded |
| 3.16 | Allowance for sports lighting to Baseball / softball | | Note | | Excluded |
| 3.17 | Allowance for sports lighting to AFL | | P.Sum | | - |
| 3.18 | Allowance for sports lighting to Athletic Track | | Note | | Excluded |
| 3.19 | Allowance for sports lighting to Lawn Bowls | | Note | | Excluded |
| 3.20 | Allowance for sport lighting to BMX and Pump Track | | Note | | Excluded |
| 3.21 | Allowance for general CCTV coverage | | P.Sum | | - |
| 3.22 | Allowance for Main Contractors Preliminaries and Margin | 8% | Sum | - | Excluded |
| | External Services Sub Total | | | - | - |
| | TOTAL CONSTRUCTION COSTS | | | - | 4,295,984 |
| 4.01 | Design Contingencies | | | | - |
| 4.02 | Construction Contingencies | | | | - |
| 4.03 | Headworks and Statutory Charges | | P.Sum | | - |
| 4.04 | Building Act Compliance | | Note | | Excluded |
| 4.05 | Percent for Public Art | | | | - |
| 4.06 | Land Costs (if applicable) | | Note | | Excluded |
| 4.07 | Other Costs - FFE | | Note | | Excluded |
| 4.08 | Other Costs - ICT | | Note | | Excluded |
| 4.09 | Professional Fees | | | | - |
| | On-Costs - Sub Total | | | - | - |
| | GROSS PROJECT COST | | | - | 4,295,984 |
| 5.00 | Escalation | | | | |
| 5.01 | Base date of pricing - September 2020 | 177.00 | | | |
| 5.02 | Escalation to Start of Construction | | | | Excluded |
| | Escalation - Sub Total | | | | - |
| | ESCALATED NET PROJECT COST | | | | 4,295,984 |
| 6.00 | Local Authority Managed Costs | | | | |
| 6.01 | Special Client Agency Provisions | | Note | | Excluded |
| 6.02 | Project Director / Professional Fees | | Note | | Excluded |
| 6.03 | Administration Fees | | Note | | Excluded |
| 6.04 | Commissioning, Relocation Costs and Disbursements | | Note | | Excluded |
| 6.05 | Land Acquisition & Native Title Compensation (if applicable) | | Note | | Excluded |
| 6.06 | Loose Furniture and Equipment | | Note | | Excluded |
| 6.07 | Computing Equipment and Services | | Note | | Excluded |
| 6.08 | Site Master Planning | | Note | | Excluded |
| 6.09 | Other Provisions | | Note | | Excluded |
| | Total Local Authority Costs | | | | - |
| | Grand total before grant | | | | 4,295,984 |
| | | | | | - |
| | ESTIMATED GROSS PROJECT (COMMITMENT) TOTAL COST | | | | 3,007,693 |

| DCP Roads - Imported Fill inputs | | Average fill depth required before topsoil removal (mm) | Topsoil removal (mm) | Total Sand depth reqd (mm) | Length | Width | Vol | Total m3 | Notes |
|----------------------------------|--|---|----------------------|----------------------------|--------|-------|-----|----------|---|
| DCA3 | Bishop Road East | 150 | 150 | 300 | 1500 | 15 | 0.3 | 6,750.0 | Existing carriageway to be upgraded, no fill required, pavement to be upgraded. Full length new carriageway 150mm fill required |
| | Taylor Road | 150 | 150 | 300 | 1530 | 15 | 0.3 | 6,885.0 | Existing carriageway to be upgraded, no fill required, pavement to be upgraded. Full length new carriageway 150mm fill required |
| | Town Centre Distributor Road (Whitby New Road) | 150 | 150 | 300 | 3545 | 30 | 0.3 | 31,905.0 | 150mm fill required to lift full length |
| | North South Road | 150 | 150 | 300 | 1340 | 30 | 0.3 | 12,060.0 | 150mm fill required to lift full length |
| | Skyline Boulevard | 150 | 150 | 300 | 352 | 25 | 0.3 | 2,640.0 | 150mm fill required to lift full length |
| | Tinspar Avenue | 150 | 150 | 300 | 1162 | 25 | 0.3 | 8,715.0 | 150mm fill required to lift full length |